



سوئی ناردرن گیس
Sui Northern Gas

PURCHASE ORDER NO. D-3586/26.

Dated: 09.09.2026

M/s Gaircom (Gas & Air Compression Services (Pvt) Ltd,
712, Block-J2, Fatima Jinnah Road, M.A. Johar Town Lahore

Subject: AIR COMPRESSOR, AIR PRESSURE BOOSTER AND AIR DRYER REFRIGERANT

Refer to your quotation GAIRCOM/ 25/T-0129 dated 13.03.2026 in response to our Tender Enquiry No. SND-2592//25 and subsequent corresponding etc.

Dear Sir,

We are pleased to place an order on you for the following items, subject to terms and conditions printed overleaf, Charges, additions, thereto, including those to the ordered equipment or material will be authorized solely by an amendment to this order which will be executed in the same manner as this order.

Item No.	Description	Unit	Qty	Unit DPU Price (Rs.)	Total DPU Price (Rs.)
1	<u>Sullair Oil Free Screw Air Compressor</u> Sullair Series Model DSP 75 VSD Variable Speed Drive – Oil Free Screw – Air Cooled Capacity: 6.3 – 12.6 m3/min @ 7 bar Voltage: 380 V +-10 Frequency: 50 HZ Main Electric Motor Capacity: 75 kW VSD Manufacturer: Hitachi Global Air Power USA (Formerly Sullair LLC USA) Country Of Origin: For Sullair Oil Free Air Compressor origin is Japan Other detail as per technical literature attached. <u>Sullair Refrigerated Air Dryer:</u> Sullair Series Model: RFE-231 MAX Rated Air Flow: 23.16 m3/min Maximum pressure: 16 Bar Dew point: 3-5°C Bottle Type Heat Exchanger minimizes the air loss of the air dryer which increases dryer efficiency. Integrated line filters (FXF-1000 + FXH-1000) Air Cooled, 400V, 3phase, 50hz, Refrigerant type R-134a (environment friendly). Country Of Origin: Sullair Refrigerant Air Dryer Origin is Turkey <u>Particulate Line Filter (Pre-Filter)</u> Sullair Series Model: FXF-1000 Capacity: 28.31 m3/min Maximum pressure: 20 bar Maximum temperature: 80 0C (176 0F) Connection sizes in/out: 3" Remove particles to: 1 -microns coalesced liquid water and lubricants: 0.5 -ppm Up to 05-year warranty (terms & conditions apply), with auto drain. Country Of Origin: Air Receiver (Vessel) Origin is Pakistan <u>Coalescing In Line Filter (After-Filter)</u> Sullair Series Model: FXH-1000 Capacity: 28.31 m3/min Maximum pressure: 20 bar Maximum temperature: 80 0C (176 0F) Connection sizes in/out: 3" Remove particles to: 0.01 -microns coalesced liquid water and lubricants: 0.01 -ppm Up to 05-year warranty (terms & conditions apply), with auto drain.	No.	1	30,835,636.00	30,835,636.00

Registered Office:

Sui Northern Gas Pipelines Limited,
21- Kashmir Road, Lahore, Pakistan.
+92-42-99082000-06

www.sngpl.com.pk

Head Office:

21- Kashmir Road, Lahore, Pakistan.
+92-42-99082000-06

	<u>Locally Fabricated Air Storage Tank</u> Capacity: 3000 Liters Test Pressure: 15 Barg (With safety valve, pressure gauge man hole & auto drain valve). Paint (inside and outside) included Third party Hydro Testing Report of air storage tank is included. All the electrical wiring i.e. from existing MCC to the MCC for compressor and dryers with in compressor room including the cable from transformer to LT panel of compressor room. All the piping and valves including provision of using a standby compressor and a bypass system of air dryer with in compressor room. All the ducting to remove exhaust of hot compressed air and exhaust of condenser of refrigerant dryer with in compressor room. Hook-up of the condensate drains of compressor and air dryer with existing sewage line with in compressor room. Spares, 04 oil filters, 04 air filters, two complete fills of compressor oil, pre and post line filter cartridges 04. All the civil works with in compressor room. Installation supervision and Commissioning of Package.				
2	<u>Air Pressure Booster With After Cooler</u> Model: VW-90/6-40 Flow: 90 m³/hr or 53 CFM Discharge Pressure: 40 barg Motor power: 15 kW Manufacturer : Anqing Bailian Oil-Free Compressor Co., Limited Country of Origin: China Other details as per technical literatur attached. <u>Desiccant Air Dryer:</u> Model: HAD-2WXF MAX Rated Air Flow: 2.4 m³/min Maximum pressure: 40 Bar Pre and post line filters are included. Other details as per technical literatur attached. <u>Air Storage Tank (Imported)</u> Capacity: 500 Liters Pressure: 40 Barg (With safety valve, pressure gauge & auto drain valve). All the electrical wiring i.e. from existing MCC to the MCC for compressor and dryers with in compressor room. All the piping and valves included for interconnecting the booster with low pressure compressor, piping between booster and dryer line filter & final discharge line with in compressor room. All the ducting to remove exhaust of hot air from booster (if needed) with in compressor room. Hook-up of condensate drains of booster and air dryer with existing sewage line with in compressor room. Spares, 02 oil filters (if installed in booster), pre and post line filter cartridges 02 All the civil works with in compressor room. Installation supervision and Commissioning of Package.	No.	1	10,800,000.00	10,800,000.00
3	<u>Air Dryer Refrigerant Type 500 CFM:</u> Sullair refrigerated air dryer: Sullair Model: RFE-155 MAX Rated Air Flow: 15.52 m³/min or 548 CFM Maximum pressure: 16 Bar Dew point: -3-5°C Bottle Type Heat Exchanger minimizes the air loss of the air dryer which increases dryer efficiency.	No.	1	4,880,000.00	4,880,000.00

Integrated line filters (FXF-700 + FXH-700) Air Cooled, 400V, 3phase, 50hz, Refrigerant type R-134a (environment friendly). Manufacturer Hitachi Global Air Power USA (Formerly Sullair LLC USA) Country of Origin: Turkey Particulate Line Filter (Pre-Filter) Sullair Series Model: FXF-700 Capacity: 19.82 m³/min Maximum pressure: 20 bar Maximum temperature: 80 °C (176 °F) Connection sizes in/out: 2" Remove particles to: 1 -microns coalesced liquid water and lubricants: 0.5 -ppm Up to 05-year warranty (terms & conditions apply), with auto drain. Coalescing In Line Filter (After-Filter) Sullair Series Model: FXH-700 Capacity: 19.82 m³/min Maximum pressure: 20 bar Maximum temperature: 80 °C (176 °F) Connection sizes in/out: 2" Remove particles to: 0.01 -microns coalesced liquid water and lubricants: 0.01 -ppm Up to 05-year warranty (terms & conditions apply), with auto drain. All the electrical wiring i.e. from existing MCC to the MCC for compressor and dryer All the piping and valves including a bypass system of existing Air Dryer with in compressor room. All the ducting to remove exhaust of refrigerant air dryer with in compressor room. Hook-up of condensate drains of compressor and air dryer with existing sewage line with in compressor room. All the civil works with in compressor room. Installation supervision and Commissioning of Package.				
		Sub Total:	46,515,636.00	
		GST @ 18%	8,372,814.48	
		Total:	54,888,450.48	
Total Value DPU Lahore (D) Store including all Govt. Taxes/Duties & GST @ 18%.		Total:	54,888,450.00	
(Rupees: Fifty Four Million Eight Hundred Eighty Eight Thousand Four Hundred Fifty Only)				
Other detailed technical specifications as per your quotation, Technical Literature and our Technical Specifications as per Appendix-F.				
Notes				
1	Above material alongwith Delivery challan will be delivered at SNGPL 21-Industrial area, Gulberg-III, Lahore before			
2	Delivery material required within 30 days after receipt of PO.			
3	If need be please contact Mr. Nabeel Ishtiaq, Dy. Chief Officer (Procurement). PTCL No. 042-99085048.			
4	Annexure-I attached.			

Yours faithfully,
SUI NORTHERN GAS PIPELINES LTD

(NABEEL ISHTIAQ)
DY. CHIEF OFFICER (PROCUREMENT)
For MANAGING DIRECTOR

"All terms and conditions in this purchase order/contract, and tender referred here above, and Appendixes attached with the order and tender enquiry and terms and conditions specifically agreed through exchange of correspondence consequent to the tender enquiry are hereby accepted. The terms and conditions mentioned overleaf have been read over to me I have read over the terms and conditions over leaf which is hereby accepted. I We shall abide by all these terms and conditions of the purchase order."

Signature of Supplier/Manufacturer

1) PERFORMANCE/WARRANTY BOND GUARANTEE

Please arrange to provide us at your own cost a Performance Warranty Bond Guarantee in the amount of 10% of the total value of the contract (Excluding GST) which shall remain valid for 12 (Twelve) Months after the last portion of the goods received at the designated SNGPL Store. This guarantee should reach us within 15 days of receipt of this purchase order.

2) LATE DELIVERY CHARGES & FORCE MAJEURE

- a) If the material, as given in the order, has not been delivered as stipulated in the contract, except on account of Force Majeure, within the delivery period given in the contract Sui Northern Gas Pipelines Limited shall be entitled to recover 1% (One Percent) of the total value of the contract price (Excluding GST) of the delayed part of the material for each week of delay by way of Late Delivery Charges and not by way of penalty subject to a maximum of 10% of the total value of the delayed part of the material.
- b) The payment of such Late Delivery Charges shall not relieve the supplier from performing and fulfilling its obligations under the contract nor will be corresponding rights and entitlements of Sui Northern be affected to reduce in any manner.
- c) Whenever Late Delivery Charges become payable, Sui Northern Gas Pipelines Limited shall quantify the same and serve a written notice upon the supplier requiring immediate payment thereof. If the supplier fails to remit payment within 30 days of receipt of such notice to be served under registered postal cover, Sui Northern Gas Pipelines Limited will become entitled to recover the same forthwith by calling upon the Performance/Warranty Bond Guarantee. Any withdrawals by way of Late Delivery Charges by the supplier within 90 days of receipt for the above referred notice by way of amendment to the Performance/ Warranty Bond Guarantee failing which the remaining portion of this Guarantee would become encashable in favour of the Buyer on account of any such failure.

3) Supply of material should be made exactly as per the specifications of the purchase order / tender enquiry.

- i) Only brand-new material will be accepted

4) INSPECTION

- i. It is prime responsibility of 3rd party inspection firm to carry out 100% inspection of material strictly as per specifications of SNGPL and ensure that no faulty material is dispatched to our store location as SNGPL accept the material meeting the specifications only.

In case the material inspected & cleared by 3rd party inspector(s) against inspection order is subsequently rejected or not found acceptable by SNGPL during in-house inspection due as its non-conformance to the specifications or any inherent defect in material, SNGPL will deduct twice the relevant inspection charges as penalty from bill(s) of 3rd party inspection firm if overall rejection ratio is more than 5% of total quantity inspected by SNGPL. No such penalty of double deduction will be charged from 3rd party inspection firm for overall rejection up to 5% of total quantity inspected by SNGPL.

Therefore, the 3rd party inspection firm shall continue 100% inspection of material at manufacturer/ supplier's premises until complete ordered quantity is accepted during in-house inspection/ testing by SNGPL. No extra inspection charges shall be paid by SNGPL for re-testing of quantities found rejected by SNGPL during in-house inspection.

- ii. The inspection order will stand expired after 70 days of original delivery time period of the purchase order. The inspection order's validity is further extendable with mutual consent of both SNGPL & 3rd party inspection firm on same terms.

However, after expiry of inspection order the manufacturer shall pay the inspection charges to the 3rd party inspection firm to be appointed by SNGPL as per new inspection order or extended inspection order. The manufacturer must ensure to deliver the complete acceptable quantity within stipulated delivery period of the purchase order as per terms & conditions thereof. The extension in validity of inspection order; where required, does not mean to revise the original delivery period of the purchase order.

- iii. It is responsibility of manufacturer to develop and maintain their in-house QA/QC system at their manufacturing premises to ensure and certify that the material is being manufactured as per SNGPL's specifications.

Third party inspection firm deputed by SNGPL at manufacturer's premises will authenticate the certificate of the QA/QC of manufacturer along with all other responsibilities as per inspection order.

Therefore, the testing charges & transportation charges of samples for carrying out physical testing, chemical testing/ analysis and metallographic or any other prescribed test as per SNGPL's specifications of required material/item for which testing facility is not available at manufacturer's premises shall be paid / borne at actual by the manufacturer. However, SNGPL can arrange any test(s) or repeat the test(s) from outside lab(s) of the raw material/ final product as the case may be.

**Cont'd... P-2**

5) WARRANTY**Item No. 01**

Standard warranty is applicable on equipment, 1 year from date of commissioning or 18 months from the date of shipment whichever comes earlier, just need to maintain the machine as per manual of the Machine with genuine oil and parts, one oil sample needed every 6 months also. If two consecutive oil samples result not up the mark the warranty of on equipment will be void.

Item NO. 02

Standard warranty is applicable on equipment, 1 year from date of commissioning or 18 months from the date of shipment whichever comes earlier, just need to maintain the machine as per manual of the Machine with genuine oil and parts.

Item NO. 03

Standard warranty is applicable on equipment, 1 year from date of commissioning or 18 months from the date shipment whichever comes earlier. Warranty is only applicable with the use of genuine parts and maintenance equipment as per the supplier's recommendation.

6) DELIVERY / INSTALLATION & COMMISSIONING

Delivery including installation and commissioning should be made within **14- 28 Working Weeks** after receipt of purchase order at SNGPL Stores, 21- Industrial Area, Gurumangat Road, Gulberg-III, Lahore. In the event of failure to adhere to the stipulated delivery schedule, we reserve the right to cancel the purchase order, either whole or partially, and procure the material from alternative sources at your risk and cost.

7) SALES TAX

Above prices are inclusive of all Government Taxes and duties, including 18% Sales tax. Sales Tax will however be paid / deducted as per prevailing law subject to provision of documentary evidence.

8) TERMS OF PAYMENT

Payment will be made by our Accounts Department within 30 days after satisfactory completion of delivery against submission of Bills / Inspection Report / Invoices in triplicate. All queries relating to payment must be addressed directly to GM(Accounts).

9) INCOME TAX

Income tax will be deducted from supplier's bills as per prevailing Government Rules. If you are exempted from deduction of advance tax, you may state so and enclosed a photocopy of any such Exemption Certificate.

10) INTEGRITY PACT

You are required to furnish duly signed Integrity Pact within 15 days of receipt of this purchase order. (Applicable for purchase order valuing more than PKR: 10,000,000/-)

11) All terms and conditions of the tender enquiry No. **SND-2592/25 and those which have been agreed through exchange correspondence after bid opening are integral part of this purchase order.**

Yours faithfully,
SUI NORTHERN GAS PIPELINES LIMITED

(Nabeel Ishtiaq)

Dy Chief Officer (Procurement)
for MANAGING DIRECTOR

sh