




GOVERNMENT OF PAKISTAN
PAKISTAN MINT, LAHORE



Work Order. No.22

Dated: 03-04-2026

M/s Pak Engineering Enterprises (Pvt) Ltd,
371-Karim Block, Allama Iqbal Town,
Lahore.

Subject: - **INSTALLATION & COMMISSIONING OF 11 KV HT FEEDER FROM
SHALIMAR GRID STATION-II TO PAKISTAN MINT COLONY LAHORE.**

Please carry out the following job as per your bid as detail given below:-

Sr. No	Description	Quantity and physical unit	Rate Per Item (Rs)	Total
1.	Installation & Commissioning of 11 kV Feeder from Shalamar Grid Station-II to Pakistan Mint Colony Lahore. (BOQ List attached)	01 Job	Rs.6,064,680/- (Complete Job)	Rs.6,064,680/-
Total Cost Inclusive all taxes				Rs.6,064,680/-
Head of A/C. A-03919 Completion Performance Period 30 Days				


Procurement Officer
Pakistan Mint Lahore
03/04/2026

Estimated Cost for construction of 11 KV feeder Emanating from Pakistan Mint.

Sr No.	Description of Material	Unit Of Qty	Qty	Per unit Cost Included Taxes	Total Cost Included Taxes
1	HT Steel Structure 36'	No	3	60000	180,000
2	HT Steel Structure 58'	No	8	110000	880,000
3	HT Steel Structure 45'	No	10	99000	990,000
4	HT Spun Pole 45'	No	14	10000	140,000
5	11 KV Steel X-Arm with Braces	No	69	50000	345,000
6	Pin Insulators	No	102	3000	306,000
7	Disc Insulators	No	87	4000	348,000
8	Insulators Pins	No	102	1000	102,000
9	Dead End Clamp for ACSR Dog Cond	No	87	1000	87,000
10	Eye Nut	No	87	1000	87,000
11	Double Arming Bolt	No	66	1000	66,000
12	Anchors Shackles	No	87	1000	87,000
13	U.G.S Cable	MTR	126	4000	504,000
14	Out Door Termination Kit	No	6	50000	300,000
15	P.G Connector T-155	No	39	100	3,900
16	P.G Connector T-110	No	39	100	3,900
17	Danger Plate with Fitting	No	35	3857	135,000
18	Barbed Wire	Kg	175	1000	175,000
19	Nut & Bolts 5/8 x 9"	No	41	100	4,100
20	Nut & Bolts 5/8 x 2"	No	138	10	1,380
21	Nut & Bolts 5/8 x 6"	No	6	100	600
22	Round Washers	No	88	100	8,800
23	Stay Assembly Complete	No	12	5000	60,000
24	Stay Strip	No	12	5000	60,000
25	GS Wire 10 mm	Kg	185	1000	185,000
26	Earthing Unit Complete	No	37	5405	200,000
27	ACSR Dog	MTR	4181	14	60,000
28	H.T Cable 500 MCM S/Core	MTR	195	1615	315,000
29	Termination Kit (In Door) 500 MCM S/C	No	3	71667	215,000
30	Termination Kit (Out Door) 500 MCM S/C	No	3	71667	215,000
				561,736	6,064,680