Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018967

RFQ No	OP-20157MS
DATE	10.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	23.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of Aluminum Mobile Tower Scaffolding (40ft) at PSO Keamari Terminal C.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Scaffolding Plank** Supply and Installation of Aluminum Mobile Tower Scaffolding (40ft) Scope of Work: The job involves the supply, delivery, and setup of a heavy-duty aluminum mobile scaffolding tower equipped with a stairway<(>,<)> complete with all required safety components, in compliance with BS EN 1004:2004 standards. _____ Specifications of the Tower Scaffold: Material: Aluminum Length: minimum 2.50 m (8Ft) Width: minimum 1.50 M (5Ft) Platform Height: minimum 11.30 m (37Ft) Tower Height: minimum 12.30 m (40ft) Working Height: minimum 13.30 m (43.6ft) (Reached Height) Pipe OD: 50 mm Thickness 2.0mm/ T6 Standard: BS EN 1004:2004 Load Capacity: 250 kg/m² uniformly distributed load (u.d.l) Warranty: 5-year welding warranty Certification: Mobile Scaffolding fitness and Load test certification required as per OSHA Standard 29CFR1926.452(W)1 Special Features: Non-slip deck platforms, directional brakes, easy-fit connections. Pulley with stand. Scope: The work should be completed within 15 Days after issuance of PO. _____ Terms and Conditions: 1. All material and transportation shall be provided by the	**Keamari Terminal**	**EA**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018967

RFQ No	OP-20157MS
DATE	10.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	23.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of Aluminum Mobile Tower Scaffolding (40ft) at PSO Keamari Terminal C.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	contractor. 2. The cost includes all applicable taxes. 3. The contractor will provide 3rd party verified inspection certificate to the terminal engineer upon delivery. 4. The contractor will set up the complete scaffolding after delivery. 5. The contractor and their staff shall strictly adhere to the Health, Safety, and Environmental (HSE) and security rules of the company. It is the responsibility of the contractor to provide PSO-approved Personal Protective Equipment (PPE) to their staff. Workers are required to use PPE while working inside the depot; no worker will be permitted to work without it. 6. The contractor shall provide a minimum five-year warranty for the satisfactory performance of the parts supplied. In the event of any failure in the quality of the supplied items, the contractor shall be responsible for replacing the defective items at their own cost. 7. Acceptance of the parts is subject to inspection and approval by the Engineer-in-charge. 8. Delivery must be completed within fifteen (15) days following the issuance of the Work Order (W/O). 9. If the contractor fails to complete the work within the stipulated time, a penalty of 0.1% of the Purchase Order (PO)/Sales Order (SO) amount per day, up to a maximum of 10%, will be charged for delayed compliance with the work/purchase order.					