



PAKISTAN TELEVISION CORPORATION LIMITED

TENDER INVITING NOTICE

ENG/PLG/B-308/26018

Subject: **TENDER FOR CONSTRUCTION OF (COLLAPSED BOUNDARY WALL AT REBROADCAST STATIONS TIMERGARH**

M/s. Pakistan Television Corporation Limited invites sealed tenders through e-Pak Acquisition & Disposal System (EPADS) <https://eprocure.gov.pk> as well as manual on the subject cited above. Interested parties may download the tenders' documents from PTV and PPRA websites. Price tenders (single stage one envelope bidding procedure) as per PPRA Rule (36 - A). PEC Registered Category (C-6).

Sealed quotations should be addressed to **Controller Audit Chairman Senior Tender Committee**, Federal TV Complex, Constitution Avenue, Islamabad and must reach in the office on or before **11th February, 2026 at 11:00 am**. For any further information, please contact with undersigned. PTV reserves the right to reject all bids or proposals and grounds of rejection will be communicated to the parties if requested, but there will be no binding on PTV to justify those grounds.

TERMS AND CONDITIONS:

- Interested bidders must be registered themselves on the (EPADS) <https://eprocure.gov.pk/#/supplier/registration> and submit their tender documents accordingly through EPADS as well as manual.
- **Single Stage-one Envelop:** Each bid shall comprise one single envelope containing and technical proposal (if any). All bids received shall be opened and evaluated in the manner prescribed in the bidding document.
- Closing date of submission is **11th February, 2026 at 11:30 am**. The bid shall be opened half hour after the closing time in the presence of the bidders who wish to be present at PTV Headquarters Office, F-5/1, Islamabad.
- The earnest money in the shape of Bank Draft / Cash Deposit receipt (CDR) from a schedule bank in Pakistan in the favour of **PTVC**, equal to **Rs. 21,975/-** should be submitted at aforementioned address which will be refundable.
- Tenders received after due date and time will not be entertained.
- Quotation / tender validity period ((120) days.
- Manual overwriting will lead to rejection of bid.
- Full name of firm, address alongwith tool. Machinery staff etc.
- NO litigation certificate on stamp paper (original)

The contractor shall liable to complete the work and shall not

- a. Leave work as incomplete.
- b. Sublet or subcontract the assigned work.
- There should be no overwriting and /or cutting in the quotation. Similarly, lead pencil must not be used for writing.
- Job must be started within 15 days and completed within 45 days from the award of Contract / Work Order.
- Transportation charges whatsoever will be borne by the party to whom job will be awarded.
- In case of any dispute, only court of Jurisdiction at Islamabad / Rawalpindi shall have jurisdiction to decide the matter.

(SAGHEER-UD-DIN)

Controller Engineering Civil

Room No. 201, 2nd Floor, Block No. II,
PTV-Headquarters Office, Islamabad.
Ph. No. 051-9077326

PAKISTAN TELEVISION CORPORATION LIMITED

BOQ / COST ESTIMATE OF BOUNDARY WALL AT RBS-TIMERGARAH

SR. NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Excavation in all kind of soil including removal of existing material Shingle, Gravelly, Clay or Mud conglomiration of gravel are Boulders, Soft, Sandy or Dis-intigrated Sandy, of Hard Rock etc., including Staking of Serviceable Materials sepraty and back filling the excavated suitable material in Foundation Plinth or under floor Cutting / Blasting if required Breaking Clods, watering consolidation by ramming in layers dressing and disposal of surplus excavated stuff as directed.	1	job		-
2	Providing and laying Plumb concrete compacting and curing etc including frame work with cement concrete 1:2:4 with boulder complete in all respects.	260	Cft		-
3	Providing and laying reinfoced cement concrete 1:2:4 using Ordinary Portland Cement and 3/4" crushed aggrigate with local approved Sand including leveling compacting and curing etc including steel as desired by Engieer. complete in all respects.	85	Cft		-
4	Providing and laying brick Masonry Work in Wall Foundation & Plinth laid in 1:4 Cement Sand Mortar including Racking out Joints and Curing complete in all respects in and Height / Floor.	232	Cft		-
5	Providing Cement Sand Plaster 1:4 in boundary wall upto 8' height 1/2" thick including curing complete in all respects in any Height / Floor.	416	Sft		-
6	Provide and apply priming coat of chalk under S.P.D / weather shield 2 coats (as may be required and approved S.P.D / weather shield on new surface of ICI make (or equal) as per specifications and approved shade by the Engineer	416	Sftt		-
7	Providing and fixing 3' height barbed wire fencing, fixed with angle iron poles. Wall finished with cement plaster and white washing.	26	Rft		-
					-
	Add GST 18%				-
	TOTAL COST				