

Tender Covering Form
Directorate of Procurement (Navy)
Through Bahria Gate

Contact: For General Queries 051-9262306, Bahria Gate 0331-5540649,
Email: adpn33@paknavy.gov.pk

P-33/FOR Section (Contact: 051-9262314)

Tender No and Date R2602330552
Tender Description Stitching of Shirt and Trouser Dress No 4 GSDC 100% Cotton
IT Opening Date 17/03/2026
Firm Name _____
Postal Address _____
Email Address for Correspondence _____
Contact Person _____
Contact Number (Landline _____) (Mobile _____)

Document to be Attached with Quotation

Firm is to submit its proposal in a sealed envelope which shall contain 03 x Sealed Envelops as per details given below:

<u>Sealed Envelop 1 – Technical Offer in Duplicate</u>			
This envelope must contain 02 x sets of Technical Offer (01 x Original + 01 x Copy). Each Set must contain following documents as per this order and Supplier is to mark tick against each to ensure that these documents have been			
S No	Document	Original Set	Copy Set
1	Bank Challan of Rs. 200/- for DGDP registered firms and Rs. 300/- for all other firms (in favour of CMA(DP))		
2	DP-1 Form of IT with tick mark against each clause and initiated on each page		
3	DP-2 Form of IT with compliance remarks against each clause and initiated on each page		
4	Annex A of IT duly filled (with compliance remarks)		
5	Annex B & C of IT (with compliance remarks)		
6	DP-3 Form of IT (duly filled & Signed)		
7	Manufacturer Authorization letter (where applicable)		
8	Manufacturer Price list (where applicable)		
9	DRAP registration letter (in case of medical)		
10	DGDP Registration Letter (If firm is registered with DGDP)		
11	Tax Filling Proof		
<u>Sealed Envelop 2 – Earnest Money</u>			
This Envelop must contain Earnest Money only.			
<u>Sealed Envelop 3 – Commercial Offer</u>			
This Envelop must contain following documents:			
1	Firms Commercial Offer	01 x Original	
2	Principal Invoice (where applicable)	01 x Original	
3	Duly filled DP-2 Form of IT	01 x Original	

Firms Declaration

It is certified that we have submitted tender in compliance with above instructions and we understand

Firm's Authorized Signatures _____

DIRECTORATE PROCUREMENT (NAVY)

Directorate of Procurement (Navy)

Through Bahria Gate
Near SNIDS Centre,
Naval Residential ComplexContact: For General Queries: 051-9262306
Bahria Gate: 0331-5540649
Section: 051-9262314

Email: adpn33@paknavy.gov.pk

M/s _____

Dated :

INVITATION TO TENDER AND GENERAL INSTRUCTIONS

Dear Sir / Madem,

1. DP (Navy) invites you to tender for the supply of stores/equipment/ services as per details given in attached Schedule to Tender (Form DP-2).

2 Caution: This tender and subsequent contract agreement awarded to the successful bidder is governed by the rules / conditions as laid down in PPRA Rules-2004 and DPP&I-35 covering general terms and conditions of contracts laid down by MoDP / DGDP. As a potential bidder, it is incumbent upon you and your firm to first acquaint yourself with PPRA Rules 2004 (www.ppra.org.pk) and DPP&I-35 (print copy may be obtained from DGDP Registration Cell on Phone No. 051-9270967 before participating in the tender. If your firm / company possesses requisite technical as well financial capability, you must be registered or willing to register with DGDP to qualify for award of contract, which shall be made after security clearance and provision of required registration documents mentioned in Para 15 of this DP-1.

Understood
agreedUnderstood
not agreed

3 Conditions Governing Contracts. The 'Contract' made as result of this I/T (Invitation to Tender) i.a.w PPRA Rules 2004 shall mean the agreement entered into between the parties i.e. the „Purchaser and the „Seller on Directorate General Defence Purchase (DGDP) contract Form "DP-19" in accordance with the law of contract Act, 1872 and hose contained in Defence Purchase Procedure and Instructions and DPP&I-35 and other special conditions that may be added to given contract for the supply of Defence Stores / Services specified herein.

Understood
agreedUnderstood
not agreed

4 Delivery of Tender: The tender documents covering technical and commercial offers are to be furnished as under:-

a Commercial Offer: The commercial offer will be in single copy and indicate prices quoted in figures as well as in words in the currency mentioned in IT. It should be clearly marked in fact on a separate sealed envelope "Commercial Offer", tender number and date of opening. Taxes, duties, freight/transportation, insurance charges etc are to be indicated separately. Total price of the items quoted against the tender is to be clearly mentioned. In case of more than one option offered by the firm, DP(N) reserves the right to accept lowest technically accepted option if more than one options were accepted in Technical Scrutiny Report.

Understood agreed Understood not agreed

b Technical Offer: (Where Applicable) Should contain all relevant specifications in DUPLICATE (or as specified in IT) along with essential literature/brochure, drawings and compliance metrics in a separate sealed envelope and clearly marked "Technical Offer" without prices, with tender number and date of opening. Technical offer shall be opened first; half an hour after the date and time for receipt of tender mentioned in DP-2. Firms are to confirm/comply with IT technical specification in the following format:

Understood agreed Understood not agreed

S. No	Technical requirement as per IT	Firm's endorsement (Comply/Partially Comply/Comply Non)	Basis of C, PC of NC i.e. Refer to page or brochure	In case of non availability of enclosed proof from brochure/ Literature, quote/attach additional documents/data/undertaking as proof of compliance

(Legend: C = Fully Comply, PC = Partially Comply, NC = Not Comply)

(Firms must clearly identify where their offer does not meet or deviates from IT Specs)

c Special Instructions. Tender documents and its conditions may please be read point by point and understood properly before quoting. All tender conditions should be responded clearly. In case of any deviation due to non-acceptance of tender conditions(s), the same should be highlighted alongwith your offered conditions. Tender may however be liable to be rejected.

Understood agreed Understood not agreed

d Firms shall submit their offers in two separate envelopes (i.e. one copy of commercial offer and two copies of the technical offers as asked in the IT) and envelopes clearly marked "Technical proposal", "Commercial proposal" in bold. The commercial offer will include rates of items/services called for and the technical offer will not indicate the rates. Both types of offers are to be enclosed in separate covers and each envelope shall be properly sealed bearing of the bidder. Each cover shall indicate type of offer, number and date of IT and IT opening date. Thereafter both the envelopes (technical and commercial offer) shall be placed in one envelope (second cover) duly sealed and signed. This cover should bear the address

of the procurement agency indicating, issuance date of IT and No, with its opening date. This should be further placed in another cover (third cover), addressed and indicated in the tender documents, without any indication that there is a tender within it.

e FORM DP-1, DP-2, DP-3 and Questionnaires. Form DP-1, DP-2 (alongwith annexes), DP-3 and Questionnaires duly filled in are to be submitted with the technical offer duly stamped/signed by the authorized signatory/ person. It is pertinent to mention that all these are essential requirement for participation in the tender.

Understood
agreed

Understood
not agreed

f. The tender duly sealed will be addressed to the following:-

Directorate of Procurement (Navy)

Through Bahria Gate
Near SNIDS Centre,
Naval Residential

Contact: For General Queries: 051-9262306
Bahria Gate: 0331-5540649
Section: null

Email: dpn@paknavy.gov.pk
null

5 Date and Time For Receipt of Tender. Tender must reach this office by the date and time specified in the Schedule to Tender (Form DP-2) attached. This Directorate will not accept any excuse of delay occurring in post. Tenders received after the appointed/ fixed time will NOT be entertained. The appointed time will, however, fall on next working day in case of closed/forced holiday. Only legitimate/registered representatives of firm will be allowed to attend tender opening. In case your firm has sent tender documents by registered post or courier service, you may confirm their receipt at DP (Navy) on Phone No 051-9271468 well before the opening date / time.

Understood
agreed

Understood
not agreed

6 Tender Opening. Tenders will be opened as mentioned in the schedule to tender. Commercial offers will be opened at later stage if Technical Offer is found acceptable on examination by technical authorities of Service HQ. Date and time for opening of Commercial offer shall be intimated later. Only legitimate / registered representative of firm will be allowed to attend tender opening. Tenders received after date and time specified in DP-2 would be rejected without exception and returned un-opened i.a.w Rule 28 of PPRA-2004.

Understood
agreed

Understood
not agreed

7. Validity of Offer.

Understood
agreed

Understood
not agreed

a. The validity period of quotations must be indicated and should invariably be 120 days from the date of opening of Commercial offer or 30th June whichever is later. Firm undertakes to extend validity of offer if required by equal number of original bid period (i.e. 120 days as per original offer) i.a.w PPRA Rule-26.

b. The quoting firm will certify that in case of an additional requirement of the contract items (s) in any qty(s) within a period of 12 months from the date of signing the contract, these will also be supplied at the ongoing contract rates with discount.

8 Part Bid Firm may quote for the whole or any portion, or to state in the tender that the rate quoted, shall apply only if the entire quantity/range of stores is taken from the firm. The Director Procurement reserves the right of accepting the whole or any part of the tender or portion of the quantity offered, and firm shall supply these at the rate quoted.

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

9 Quoting of Rates. Only one rate will be quoted for entire quantity, item wise. In case quoted rates are deliberately kept hidden or lumped together to trick other competitors for winning contract as lowest bidder, DP(N) reserves the right to reject such offers on-spot besides confiscating firms Earnest Money / Bid Security and take appropriate disciplinary action. Conversion rate of FE/LC components will be considered w.e.f. opening of commercial offer as per PPRA Rule-30(2).

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

10. Return of I/T. ITs are to be handled as per following guidelines:

a. In case you are Not quoting, please return the tender inquiry stating the reason of NOT quoting. In case of failure to return the ITs either quoted or not quoted consequently on three occasions, this Directorate, in the interest of economy, will consider the exclusion of your firms name from our future distribution list of invitation to tender.

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

b. For registered firm(s), case will be referred to DGDP for necessary administrative action if firms registered / indexed for tendered items/stores do not quote / participate.

c. It is a standard practice to invite all firm(s) including those unregistered with DGDP who gave their preliminary budgetary/ technical proposals to end users / indentors. If your firm has been invited to participate in the tender, you must either participate in tender. In case of your inability to do so, you must inform DP (Navy) by a formal letter/email.

11. Withdrawal of Offer. Firms shall not withdraw their commercial offers before signing of the contract and within validity period of their offers. In case the firm withdraws its offer within validity period and before signing of the contract, Earnest Money of the firm shall be confiscated and disciplinary action may also be initiated for embargo up to 01 year.

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

12. Provision of Documents in case of Contract. In case any firm wins a contract, it will deposit following documents before award of contract:

- a. Proof of firms financial capability.
- b. Foreign Seller has to provide its Registration Number issued by respective Department of Commerce authorizing export of subject stores.
- c. Principal/Agency Agreement.
- d. Registration with DGDP (Provisional Registration is mandatory)

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

13. Treasury Challan.

a. Offers by registered firms must be accompanied with a Challan form of Rs.200/- (obtainable from State Bank of Pakistan/Government Treasury) and debit able to Major Head C02501-20, Main Head-12, Sub Head 'A' Miscellaneous (Code Head 1/845/30). Each offer will be covered by one Challan.

b. Firms, un-registered / un-indexed with GDP (Registration Section) are to participate in the tender by submitting Challan Form of Rs 300 in favour of CMA (DP).

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

14. Earnest Money/Tender Bond: Please ensure Earnest Money is contained in a separate envelop (not inside Technical or commercial offer). Offer is liable to be rejected in case Earnest Money is packed inside commercial or Technical offer. Your tender must be accompanied by a Call Deposit Receipt (CDR) in favor of CMA (DP), Rawalpindi for the following amounts:-

Understood
agreed

Understood
not agreed

a. Submitting improper Earnest Earnest Money/Bid Security furnished with tender is strictly in conformity of tender/IT conditions (Clause 14 of DP-1 and clause 10 of DP-2) on the subject. We have no objection on confiscation of Earnest Money/Bid security and rejection of our offer in case amount of Earnest Money/Bid Security is improper/insufficient in violation of IT condition.

b. Rates for Contract. The rate of earnest money and its maximum cell for different categories OF FIRMS would be as under:-

- (i) Registered/Indexed/Pre-Qualified Firms. 2% of the quoted value subject to maximum ceiling of Rs. 0.500 Million.
 (ii) Registered/Pre-Qualified but Un-indexed 3% of the quoted value subject to maximum ceiling of Rs. 0.750 Million.
 (iii) Unregistered/not Pre-Qualified/Un-indexed 5% of the quoted value subject to maximum ceiling of Rs. 1.000 Million.

c. Return of Earnest Money. (i) Earnest money to the unsuccessful bidders will be returned on finalization of the contract.
 (ii) Earnest money of the firm/firms with whom contract is concluded will be returned on submission of Bank Guarantee and its acceptance by CMA (DP).

15. Documents for provisional registration: In case your firm wins a contract on Earnest Money (EM) , it will deposit following documents to DGDP (Registration Section) before the award of contract for provisional registration:-

Understood
agreed

Understood
not agreed

S No	Local Supplier	Foreign Supplier
a.	Three filled copies of SVA-8121 of each member of management.	Three filled copies of SVA-8121-D of each member of management.
b.	Three filled copies of SVA-8121-A	Three filled copies of SVA-8121.
c.	Three photocopies of NIC for each member of management.	Three photocopy of Resident Card or equivalent identification Card for each member of management.
d.	Three PP size photographs for each member of management.r	Three PP size Photographs for each member of management.
e.	Challan Form	Challan Form
f.	Bank Statement for last one year.	Financial standing/audit balance
g.	Photocopy of NTN	Photocopy of passport
h.	Foreign Principal Agency Agreement in case of local agent.	Agency Agreement in case of Trading House/ Company/ Exporter /Stockiest etc.

16. Inspection Authority. CINS, Joint Inspection will be carried out by INS, Consignee and Specialist User or a team nominated by Pakistan Navy. CINS inspection shall be as prescribed in DPP & I-35 or as per terms of the contract.

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

17. Condition of Stores. Brand new stores will be accepted on Firms Warranty/Guarantee Form DPL-15 enclosed with contract.

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

18. Documents Required. Following documents are required to be submitted along with the quote:

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

a. OEM/Authorized Dealer/Agent Certificate along with OEM Dealership Evidence.

b. The firm/supplier shall provide correct and valid e-mail and Fax No to CINS and DP(N). Supplier/contracting firm shall either provide OEM Conformance Certificate to CINS or is to be e-mailed to CINS under intimation to DP (Navy). Hard copy of COC must follow in any case through courier. On receipt, CINS shall approach the OEM for verification of Conformance Certificates issued by OEM. Companies/firms rendering false OEM Conforming Certificates will be blacklisted.

c. Original quotation/Principal/OEM proforma invoice.

d. In case of bulk proforma invoice, a certificate that prices indicated in the bulk proforma invoice have not been decreased since the date of bulk proforma invoice from the manufacturers/suppliers.

e. Submit breakup of cost of stores/services on the following lines:

(i) Imported material with break down item wise along-with import duties.

(ii) Variable business overheads like taxes and duties imposed by the federal/provincial government as applicable:-

(1) General Sales Tax

(2) Income Tax

(3) Custom Duty. PCT code along with photocopy of the related page is to be attached where applicable.

(4) Any other tax duty.

(iii) Fixed overhead charges like labour, electricity etc.

(iv) Agent commission/profit, if any.

(v) Any other expenditure/cost/service/remuneration as asked for in the tender.

19. Rejection of Stores/Services. The stores/services offered as a result of contract concluded against this tender may be rejected as follows:

Understood agreed	Understood not agreed
<input type="checkbox"/>	<input type="checkbox"/>

a. 1st rejection on Govt. expense

b. 2nd rejection on supplier expense

c. 3rd rejection contract cancellation will be initiated.

20. Rejection of Stores/Services. To ensure timely and correct supply of stores the firm will furnish an unconditional Bank Guarantee (BG in the currency in which contract is concluded) from a schedule Bank of Pakistan for an amount upto 10 % of the contract value (excluding Taxes, duties/freight handling charges) on a Judicial Stamp Paper (All pages) of the value of (Rs 100.00) as per prescribed format or in shape of CSD/Bank draft. The Bank Guarantee shall be endorsed in favour of CMA (DP) Rawalpindi who is the Accounts Officer specified in the contract. The CMA (DP) Rawalpindi has the like power of seeking encashment of the Bank Guarantee as if the same has been demanded by the purchaser himself. The Bank Guarantee shall be produced by the supplier within 30 days from the date of issue of the contract and remain valid for upto 60 days after completion of warranty period and remain in force till one year ahead of the delivery date given in the contract. If delivery period is extended, the supplier shall arrange the extension of Bank Guarantee within 30 days after the original delivery period to keep its validity always one year ahead of the extended delivery period. The BG form can be obtained from DP(N) on e-mail address given on page 1. Format of BG is enclosed at Annex B.

Understood
agreed

Understood
not agreed

21. Integrity Pact. There shall be "zero tolerance" against bribes, gifts, commission and inducement of any kind or their promises thereof by Supplier / Firm to any Government official / staff whether to solicit any undue benefit, favour or otherwise. Following provisions must be clearly read and understood for strict compliance:

Understood
agreed

Understood
not agreed

a. Integrity Pact shall be applicable to all tenders / contracts irrespective of their financial value. However, a written Integrity Pact shall be signed for contracts exceeding Rs 10 Million between the procuring agency and the supplier / contractor i.a.w Rule-7 of PPRA-2004. The form is available at www.ppra.org.pk or can be requested at dpn@paknavy.gov.pk

b. If a Supplier / Contractor is found involved in any unbusiness-like / unethical activity, same would be considered a serious breach of the Integrity Pact. DP (Navy) shall take severe disciplinary action against that person(s) and the firm / company, which may include, but not limited to, PERMANENT BLACKLISTING of firm / company through DGDP and legal action against the individual (s) involved as per Pakistans Code of Criminal Procedure.

c. It is strictly forbidden to socialize, call or meet any official / staff of DP (Navy) in private or during off hours. If any official / staff from Purchaser side asks for any undue favour or gratification directly or indirectly, the matter is to be immediately brought to the personal notice of Director Procurement (Navy) on Respective Section Tel: 051-9271468 or through a personal meeting in office. Privacy of firms and their Reps sharing such information will be guaranteed without any prejudice to their normal business activities.

22. Correspondence. All correspondence will be addressed to the Purchaser i.e. DP (Navy). Correspondence with regard to payment or issue of delivery receipt may be addressed to CMA Rawalpindi and Consignee respectively with copy endorsed to the DP (Navy).

Understood
agreed

Understood
not agreed

23. Pre-Shipment Inspection. PN may send a team of officers including DP(N) member for the inspection of major equipments and machinery items at OEM premises as per terms of contract. If not already provided for and mentioned in the I.T, firm(s) must clarify the place, number of persons, duration and whether expenses on such visits would be borne by the Purchaser or Contractor. In case contractor is responsible for bearing such expenses, detailed breakdown of the same should be given separately in the commercial offer.

Understood
agreed

Understood
not agreed

24. Amendment to Contract. Contract may be amended/modified to include fresh clause (s) modify the existing clauses with the mutual agreement by the supplier and the purchaser; such modification shall form an integral part of the contract

Understood
agreed

Understood
not agreed

25. Discrepancy. The consignee will render a discrepancy report to all concerned within 60 days after receipt of stores for discrepancies found in the consignment. The quantities found short are to be made good by the supplier, free of cost.

Understood
agreed

Understood
not agreed

26. Price Variation.

Understood
agreed

Understood
not agreed

- a. Prices offered against this tender are to be firm and final.
- b. Where the prices of the contracted stores/raw material are controlled by the government or an agency competent to do so on government behalf then price increase/decrease will be allowed at actual on case to case basis on production of government notification by the Supplier for the subject stores where the firms are contractually obliged and bound to produce the stores from raw materials supplied by government/State controlled departments in consultation with Military Finance.
- c. Except for calculation or typographical errors, the rates of the contracts not having a price variation clause PVC clause will not be increased subsequently. But when such an increase is considered desirable in the interest of expeditious supply of stores and is necessitated by the circumstances beyond the control of the Supplier, the case may be decided accordingly.

27. Force Majeure.

Understood
agreed

Understood
not agreed

- a. The supplier will not be held responsible for any delay occurring in supply of equipment due to event of Force Majeure such as acts of God, War, Civil commotion, Strike, Lockouts, Act of Foreign Government and its agencies and disturbance directly affecting the supplier over which events or circumstances the supplier has no control. In such an event the supplier shall inform the purchaser within 15 days of the happening and within the same timeframe about the discontinuation of such circumstances / happening in writing. Non-availability of raw material for the manufacture of stores, or of export permit for the contracted stores from the country of its origin, shall not constitute Force Majeure.
- b. The Supplier shall provide the Purchaser with all the necessary proof of the occurrence of the events and its effect on the contract performance within 30 days from the start to force majeure event.
- c. The Purchaser shall be entitled to conduct investigation into the cause of delay reported by the Supplier.
- d. Where the delay was due to genuine force majeure event it shall extend the delivery for a period of equal to the period in which such force majeure remains operative.
- e. Such extension in delivery period, due to force majeure, shall not entitle the Suppliers to claim any extra from the Purchaser.

28. Arbitration. Parties shall make their attempt to settle all disputes arising under this contract through friendly discussions in good faith. In the event that either party shall perceive such friendly discussion to be making insufficient progress towards settlement of dispute (s) at any time, then such party may be written notice to the other party refer the dispute (s) to final and binding arbitration as provided below:

Understood agreed Understood not agreed

- a. The dispute will be referred for adjudication to two arbitrators one to be nominated by each party, who before entering upon the reference shall appoint an umpire by mutual agreement, and if they do not agree a judge of the Superior court shall be requested to appoint the umpire. The arbitration proceedings shall be held in Pakistan and under Pakistani Law.
- b. The venue of the arbitration shall be the place from which the contract is issued or such other places as the Purchaser at his discretion may determine.
- c. The arbitration award shall be firm and final.
- d. In course of arbitration the contract shall be continuously be executed except that part which is under arbitration
- e. All proceedings under this clause shall be conducted in English language and in writing

29. Court of Jurisdiction. In case of any dispute only court of jurisdiction at Rawalpindi, Pakistan shall have jurisdiction to decide the matter

Understood agreed Understood not agreed

30. Liquidated Damages(LD). Liquidated Damages upto 2% per month are liable to be imposed on the suppliers by the purchaser in accordance with DPP & I-35, if the stores supplied after the expiry of the delivery date without any valid reasons. Total value of LD shall not exceed 10% of the contract value.

Understood agreed Understood not agreed

31. Risk Purchase. In the event of failure on the part of supplier to comply with the contractual obligations the contract will be cancelled at the Risk and Expense (RE) of the supplier in accordance with DPP & I-35.

Understood agreed Understood not agreed

32. Compensation Breach of Contract. If the contractor fails to supply the contracted stores or contract is cancelled either on RE or without RE or contract become ineffective due to default of supplier / seller or stores / equipment declared defective and caused loss to the Government, contractor shall be liable to pay to the Government compensation for loss or inconvenience resulting for his default or from the rescission of his contract when such default or rescission take place such compensation will be in excess to the RE amount, if imposed by the competent authority. Compensation amount in terms of money will be decided by the purchase officer and will be deposited by contractor / seller in Government treasury in the currency of contract.

Understood agreed Understood not agreed

33. Gratuities/Commission/Gifts. No commission, rebate, bonus, fee or compensation in any form shall be paid to any local or foreign agent, consultant representative, sales promoter or any intermediary by the Manufacturer/Supplier except the agent commission payable as per the agent commission policy of the government and as amended from time to time and given in the contract. Any breach of such clause(s) of the contract by Manufacturer/Supplier and/or their sole nominated representative may result in cancellation of the contract blacklisting of the Manufacturer/Supplier financial penalties and all or any other punitive measure which the purchaser may consider appropriate.

Understood
agreed

Understood
not agreed

34. Termination of Contract.

Understood
agreed

Understood
not agreed

a. If at any time during the currency of the contract the Purchaser decides to terminate the contract for any reason whatsoever (other than for reasons of Non-Delivery) he shall have right to do so by giving the Supplier a registered notice to that effect. In that event the Purchaser will accept delivery at the contract price and terms of such stores/goods/services which are in the actual process of manufacture that is completed and ready for delivery within thirty days after receipt by the Supplier of such notice.

b. In the case of remainder of the undelivered stores/goods/services the Purchaser may elect either:

(i) To have any part thereof completed and take the delivery thereof at the contract price or.

(ii) To cancel the remaining quantity and pay to the Supplier for the articles or sub-components or raw materials purchased by the Supplier and are in the actual process of manufacture at the price to be determined by the Purchaser. In such a case materials in the process of manufacture shall be delivered by the Supplier to the Purchaser.

c. Should the Supplier fail to deliver goods/services in time as per quality terms of contract or fail to render Bank Guarantee within the stipulated time period or any breach of the contract the Purchaser reserves the right to terminate/cancel the contract fully or any part thereof at the risk and

35. Rights Reserved. Directorate of Procurement (Navy), Rawalpindi reserves full rights to accept or reject any or all offers including the lowest. Grounds for such rejections may be communicated to the bidder upon written request, but justification for grounds is not required as per PPRA Rule 33 (1).

Understood
agreed

Understood
not agreed

36. Application of Official Secrets Act, 1923. All the matters connected with this enquiry and subsequent actions arising there from come within the scope of the Official Secrets Act, 1923. You are, therefore, requested to ensure complete secrecy regarding documents and stores concerned with the enquiry and to limit the number of your employees having access to this information.

Understood
agreed

Understood
not agreed

37. Acknowledgment. Firms will send acknowledgement slips within 07 days from the date of downloading of IT from the PPRA Website i.e. WWW.PPRA.ORG.PK

Understood agreed Understood not agreed

38. Disqualification. Offers are liable to be rejected if:-

Understood agreed Understood not agreed

- a. Received later than appointed/fixed date and time.
- b. Offers are found conditional or incomplete in any respect.
- c. There is any deviation from the General /Special/Technical Instructions contained in this tender.
- d. Forms DP-1, DP-2 (along with Annexes), and DP-3 duly signed, are NOT received with the technical offer.
- e. Taxes and duties, freight/transportation and insurance charges NOT indicated separately as per required price breakdown mentioned at Para 17.
- f. Treasury challan is NOT attached with the technical offer.
- g. Multiple rates are quoted against one item.
- h. Manufacturers relevant brochures and technical details on major equipment assemblies are not attached in support of specifications.
- i. Subject to restriction of export license.
- j. Offers (commercial/technical) containing non-initialed/ unauthenticated amendments/corrections/overwriting.
- k. If the validity of the agency agreement is expired.
- l. The commercial offer against FOB/CIF/CandF tender is quoted in local currency and vice versa.
- m. Principals invoice in duplicate clearly indicating whether prices quoted are inclusive or exclusive of the agent commission is not enclosed.
- n. Earnest money is not provided.
- o. Earnest Money is not provided with the technical offer (or as specified).
- p. If validity of offer is not quoted as required in IT or made subject to confirmation later.
- q. Offer made through Fax/E-mail/Cable/Telex.
- r. If offer is found to be based on cartel action in connivance with other sources/ participants of the tender.
- s. If OEM and principal name and complete address is not mentioned.
- t. Original Principal Invoice is not attached with offer.

39. Appeals by Supplier/Firm. Any aggrieved Supplier/Firm against the decision of DP (N) or CINS or any other problematic area towards the execution of the contract may prefer an Appeal to Standing Appeal Committee (SAC) comprising PN Officers and military finance rep at Naval headquarters, Islamabad. The detail and timeline for preferring appeals is given below:

Understood agreed Understood not agreed

S.No	Cetegary of Appeal	Limitation Period
a	Appeals for liquidated damages	Within 30 days decision
b	Appeals for reinstatement of contracts	Within 30 days decision
c	Appeals for risk and expense amount	Within 30 days decision
d	Appeals for rejection of stores	Within 30 days decision
e	Appeals in all other Cases	Within 30 days decision

40. Limitation Any appeal received after the lapse of timelines given in para 39 above shall not be entertained.

Understood
agreed

Understood
not agreed

41. For Firms not Registered with For Firms not Registered with DGDP. Firms not registered with DGDP undertake to apply for registration with DGDP prior signing of Contract. Details can be found on DGDP website ww.dgdp.gov.pk. These firms can participate in tender law paras 12 and 14 above

Understood
agreed

Understood
not agreed

42. Firms which are not registered with DGDP should initiate provisional registration in accordance with Para 41. Besides, ground check by Field Security (FS) Team will be made for security clearance related to participation in the tender after technical opening. Firms undertake to provide following documents for ground check by FS Team:

Understood
agreed

Understood
not agreed

- a. NTN
- b. Income Tax Return
- c. Sales Tax Return
- d. Sales Tax Certificate
- e. Chamber of Commerce Industry Certificate
- f. Professional Tax Certificate (Excise and Taxation)
- g. Office/Home/Ware House Property documents
- h. Utility Bills (Phone/Electricity)
- j. Firm Vehicle/Personal Vehicle
- k. CEO Visiting Card/NIC Copy, 03Xspecimen signature of CEO
- l. DGDP Registration letter
- m. Firm Bank Statement
- n. Non Black List Certificate
- p. 2 X Witness + CNIC and Mobile Numbers
- q. Police Verification
- r. Agency Agreement
- s. OEM Certificate
- t. ISO Certificate
- u. Stock List with value
- v. Company Profile/Broachers
- w. Employees List
- x. Firm Categories
- y. Sole Proprietor Certificate
- z. Partnership Deed
- aa. Pvt Limited
- ab. Memorandum of Articles
- ac. Form 29 and Form A
- ad. Incorporation Certificate

43. We solemnly undertake that all IT clauses marked as "Understood and Agreed" shall not be changed / withdrawn after tender opening. The IT provisions accepted shall form the baseline for subsequent contract negotiations.

Understood
agreed

Understood
not agreed

44. The above terms and conditions are confirmed in total for acceptance.

Understood
agreed

Understood
not agreed

45. Format of DPL-15 (warranty form) and PBG are enclosed as Annex A and B.

Understood
agreed

Understood
not agreed

Sincerely yours,

(To be Signed by Officer Concerned)

Rank: _____

NAME: _____

DPL-15 (WARRANTY)

FIRM'S NAME M/s _____

1. We hereby guarantee that the articles supplied under the terms of this contract are produced new in accordance with approved drawings/specification and in all respect in accordance with the terms of the contract, and the materials used whether or not of our manufacture are in accordance with the latest appropriate standard specifications, as also in accordance with the terms of complete of good workmanship throughout and that we shall replace FOR/DDP Karachi free of cost every article or part thereof use or in use shall be found defective or not within the limits and tolerance of specifications requirement or in any way not in accordance with the terms of the contract.

2. In case of our failure to replace the defective stores free of cost within a reasonable period, we shall refund the relevant cost FOR/DPP Karachi (As the case may be in currency in with received).

3. This warranty shall remain valid for 01 Year after the acceptance of stores by the end user

The signature must be the same as that on the tender/contract, or if otherwise must be shown to be the signature of a person capable of giving a guarantee on behalf of the contractor

SIGNATURE _____

DATE _____

PLACE _____

BANK GUARANTEE FOR PERFORMANCE ON
JUDICIAL STAMP PAPER OF RS. 100/- OR
AS SUITABLE TO THE AMOUNT OF BG

- (i) Contract No. _____ dated _____
(ii) Name of Firm/Contractor _____
(iii) Address of Firm/Contractor _____
(iv) Name of Guarantor _____
(v) Address of Guarantor _____
(vi) Amount of Guarantee Rs. _____
(_____)
(in words)
(vii) Date of expire of Guarantee _____

To: The President of Islamic Republic of Pakistan through the
Controller of Military Accounts (Defence Purchase) Rawalpindi.

Sir

1. Whereas your good self have entered into Contract No. _____ dated _____
with Messers _____

(Full Name and Address)

hereinafter referred to as our customer and that one of the conditions of the Contract is
the submission of unconditional Bank Guarantee by our customer to your good self for a
sum of Rs. _____ Rupees/FE (as applicable) _____

2. In compliance with this stipulation of the contract, we hereby agree and undertake as
under: -

a. To pay to you unconditionally on demand and/or without any reference to our Customer
and amount not exceeding the sum or Rs. _____ Rupees or
FE (as applicable) _____ as would be mentioned in
your written Demand Notice.

b. To keep this Guarantee in force till _____.

c. That the validity of this Bank Guarantee shall be kept one clear year ahead of the
original/extended delivery period or the warrantee of the stores which so ever is later in
duration on receipt of information from our Customer i.e. M/s _____
or from your office. Claim, if any must be duly received by us on or before this day. Our
liability under this Bank Guarantee shall cease on the closing of banking hours on the last
date of the validity of this Bank Guarantee. Claim received thereafter shall not be
entertained by whether you suffer a loss or not. On receipt of payment under this
guarantee, this document i.e. Bank Guarantee must be clearly cancelled, discharged and
returned to us.

d. That we shall inform your office regarding termination of the validity of this Bank Guarantee one clear month before the actual expiry date of this Guarantee.

e. That with the consent of our customer you may amend/alter any term/clause of the contract or add/delete any term/clause to/from this contract without making any reference to us. We do not reserve any right to receive any such amendment/alternation or addition/deletion provided such like actions do not increase our monetary liability under this Bank Guarantee which shall be limited only to Rs. _____ (Rupees _____).

f. That the Bank Guarantee herein before given shall not be affected by any change in the constitution of the Bank or Customer/Seller or Vendor.

g. That this an unconditional Bank Guarantee, which shall be encashed on sight on presentation without any reference to our Customer/Seller or Vendor.

Guarantor

Dated: _____

(Bank Seal and Signatures)

AFFIDAVIT/UNDERTAKING
(WORTH RS. 100/- ON JUDICIAL STAMP PAPER)

Mr _____ Authorized signatory/
Partner/MD of M/s _____, do hereby solemnly affirm to DGP
(Army), DP (Navy), DP (Air) and Directorate General Defence Purchase, Ministry of Defence
Production, Rawalpindi that our firm M/s _____ has applied for registration
with Director General Defence Purchase (DGDP) duly completed all the documents required by
registration section on _____ (date) i,e before signing the contract. I certify that the above
mentioned statement is correct. In case it is detected on any stage that our firm has not applied
for registration with Director General Defence Purchase or statement given above is incorrect,
our firm will be liable for disciplinary action initiated (i,e debarring, the firm do business with
other Defence Establishment and Govt Agencies). I also accept that any disciplinary action
taken will not be challenged in any Court of Law.

Station: _____
Date: _____

Signature: _____
Name: _____
Appointment in Firm: _____

ATTESTED BY OATH COMMISSIONER WITH STAMP

INVITATION TO TENDER FORM

1 Schedule to Tender No. 525041\R2602330552 Dated This tender will be closed for acceptance at 1030 Hours and Will be opened at 11:03 Hours on 2026-03-17 11:00:00.0 Please drop tender in the Tender Box No. 203

2 You are requested to please use this Performa for price quotation, fill in the prices, affix your stamp on the same, sign it and forward it in original as your Commercial offer along with the covering letter of your firm. If you do not use this form as price quotations your offer might be rejected.

3 . You are requested to please attach DP-1 and DP-3 alongwith your quotation duly signed and stamped. Same are available at www.ppra.org.pk

S NO	DETAIL OF STORES	QTY	UNIT PRICE	TOTAL PRICE
1	8405502601214 Stitching of Shirt Dress No 4 100% Cotton GSDC Size XSL Collar 15 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	7000.0 NUMBERS		
2	8405502601213 Stitching of Shirt Dress No 4 100% Cotton GSDC Size XSF Collar 14.5 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	10000.0 NUMBERS		
3	8405502601216 Stitching of Shirt Dress No 4 100% Cotton GSDC Size SL Collar 15.5 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	3000.0 NUMBERS		
4	8405502601215 Stitching of Shirt Dress No 4 100% Cotton GSDC Size SF Collar 15 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	5000.0 NUMBERS		
5	8405502601211 Stitching of Shirt Dress No 4 100% Cotton GSDC Size 2XS Collar 14 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	3000.0 NUMBERS		

S NO	DETAIL OF STORES	QTY	UNIT PRICE	TOTAL PRICE
6	8405502601212 Stitching of Shirt Dress No 4 100% Cotton GSDC Size XXS Collar 14.5 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	7000.0 NUMBERS		
7	8405502701227 Trouser Dress No. 4 100% cotton gsdc size 2xs waist 28 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	3000.0 NUMBERS		
8	8405502701228 Stitching of Trouser Dress No 4 100% Cotton GSDC Size XXS Waist 30 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	7000.0 NUMBERS		
9	8405502701229 Stitching of Trouser Dress No 4 100% Cotton GSDC Size XSF Waist 32 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	10000.0 NUMBERS		
10	8405502701230 Stitching of Trouser Dress No 4 100% Cotton GSDC Size XSL Waist 32 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	7000.0 NUMBERS		
11	8405502701232 Stitching of Trouser Dress No 4 100% Cotton GSDC Size SL Waist 34 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	3000.0 NUMBERS		
12	8405502701231 Stitching of Trouser Dress No 4 100% Cotton GSDC Size SF Waist 34 Detailed: Technical Specification Special Instructions: As Per Annex A General Instructions : As Per Annex B	5000.0 NUMBERS		
Above mentioned price includes 18% sale Tax (Please tick Yes or No)		Yes	No	
Grand Total				

Terms and Conditions

1. Terms of Payment As per Annex B
2. Origin of OEM Indigenous
3. Origin of Stores Indigenous
4. Technical Scrutiny Report Required
5. Delivery Period 50% within 03 Months of receipt of cloth
50% within 06 Months of receipt of cloth
6. Currency PAK RUPEES
7. Basis for acceptance FOR
8. Bid validity The validity period of quotations must be indicated and should invariably be 120 days from the date of opening of commercial offer or 30th June whichever is later. Firm undertakes to extend validity of offer if required by equal number of original bid period (i.e, 120 days as per original offer) i.a.w PPRA Rule-26.
9. Tendering procedure Single Stage - Two Envelopes
bidding procedure will be followed . PPRA Rule 36 refers.

10. Earnest Money/Tender Bond

Please ensure Earnest Money is contained in a separate envelop (not inside Technical or commercial offer). Offer is liable to be rejected in case Earnest Money is packed inside commercial or Technical offer. Your tender must be accompanied by a Call Deposit Receipt (CDR) in favor of CMA (DP), Rawalpindi for the following amounts:-

a . Submitting improper Earnest Earnest Money/Bid Security furnished with tender is strictly in conformity of tender/IT conditions (Clause 14 of DP-1 and clause 10 of DP-2) on the subject. We have no objection on confiscation of Earnest Money/Bid security and rejection of our offer in case amount of Earnest Money/Bid Security is improper/insufficient in violation of IT condition.

b . Rates for Contract. The rate of earnest money and its maximum ceil for different categories OF FIRMS would be as under:-

(i) Registered/Indexed/Pre-Qualified Firms. 2% of the quoted value subject to maximum ceiling of Rs. 0.500 Million.

(ii) Registered/Pre-Qualified but Un-indexed 3% of the quoted value subject to maximum ceiling of Rs. 0.750 Million.

(iii) Unregistered/not Pre-Qualified/Un-indexed 5% of the quoted value subject to maximum ceiling of Rs. 1.000 Million.

c . Return of Earnest Money. (i) Earnest money to the unsuccessful bidders will be returned on finalization of the contract.
(ii) Earnest money of the firm/firms with whom contract is concluded will be returned on submission of Bank Guarantee and its acceptance by CMA (DP).

13. Special Note

All Participating firms must submit technical offers in duplicate (one for TSR committee and one for DP (Navy) record).

a. Unregistered (Not registered with Directorate General Defense Purchase) firms must provide the documentary evidence of their financial capability to undertake the project.

b. Unregistered firms are to submit a certificate along with their Technical offer stating that the firm is not black listed by any government organization and not under disciplinary trial or embargo.

c. Only registered suppliers on Active Taxpayers List (ATL) of FBR are eligible to participate in the Tender and submit quote.

d. Release of payments is subject to mandatory submission of Filer Certificate duly issued by FBR showing the name of supplier on ctiveTaxpayers List (ATL). No payment will be released by CMA (DP) unless latest Filer Certificate duly issued by FBR showing the name of supplier on its Active Taxpayers list is submitted alongwith payment documents.

e. In case of Pakistani firms, sales tax, NTN and income tax registration certificates are to be attached with the offer. These certificates are mandatory with the BID, otherwise offer shall be REJECTED.

f. Company registration certificates are to be attached with offer.

g. Requisite amount of earnest money (in shape of CDR/Demand Draft/Pay Order in the favour of CMA (DP) is to be attached in separate envelop in sealed condition with the Technical offer. Photocopy of the same shall also be attached with DP-2 as a testimony. Cheques/crossed cheques shall not be accepted. Technical offers received without earnest money shall not be accepted and will be rejected on spot.

h. Duly completed Form DP-1 and DP-3 are to be attached with Technical Offer.

i. DP-2 Form shall also be submitted with Technical Offer without mentioning of prices. Moreover, compliance or otherwise against each para/requirement of Annex A, B & C duly signed and stamped by firm authorized rep is to provide for technical scrutiny.

j. Price preference is admissible to local manufacturers over foreign vendors as per PPRA Rule 24 and Govt of Pakistan (Ministry of Commerce) SRO 827 (I)/2001.3

k. Indent having single item with different sizes will be dealt as a package depending on overall cost/ lowest bid.

Note: In case of failure to comply above instructions, Terms and conditions, offer will liable for rejection.

RESTRICTED



IMMEDIATE
DID
OFFICE OF NRDI (ITD
WING)

PN/DID/GENERAL/9585688

58455

See Distribution

02 August 2024

PROMULGATION OF AMENDMENTS IN PN SPECIFICATIONS : INCLUSION OF SECURITY CLAUSE IN PN SPECIFICATIONS OF CAMOUFLAGE DRESSES

Reference(s):

A. PN/NS Dte/GENERAL/2142599 dated 31 July 2024

Apropos reference A, amendments in following PN Specifications of Camouflage Dresses and Weather proof Jackets are promulgated herewith for compliance/ future reference, please:

S.No	PN Specifications	Description
a.	03/ 2018	Dress Pak Marines 60% Cotton - 40 % polyester
b.	10/2014	Dress Pak Marines 100% Cotton
c.	04/ 2018	Dress SSG(N) 60% Cotton - 40 % polyester
d.	08/2014	Dress SSG(N) 100% Cotton
e.	02/2018	GSD Dress 4 60% Cotton - 40 % polyester
f.	01/2018	GSD Dress 4 100% Cotton
g.	05/2019	Weather Proof Jackets

AZHAR HUSSAIN TI(M)
CAPT PN
DID

RESTRICTED

RESTRICTED

Encl(s):

1. Amendment in PN Specifications w.r.t inclusion of security clauses

Distribution:

External:

Action:

CSD N
Attn: CO PNCSD

Chief Inspector of Naval Stores
Attn: IO CLOTHING CINS

DP Navy
Attn: ADP 33 PRE AND POST

Information:

DNS

DCINS

Internal:

Information:

MD ITD (AOL)

DID
Attn: SO TEXTILE I ID

PN/DID/GENERAL/9585688 approved by DID CAPT PN AZHAR HUSSAIN TI(M) on
02 August 2024 (1022 Hrs)

Note: Computer generated documents do not require signature

RESTRICTED

AMENDMENTS IN PN SPECIFICATION 01/2018
GSDC DRESS 4 100% COTTON

FOR:

Article No	Page No	ITEM
16.	7	<p><u>PACKING DETAILS</u> The store when ordered to be delivered 'PACKED' shall be packed as per following instructions:</p> <ul style="list-style-type: none"> • The Dress shall be packed in a neat, dry and clean condition in standard polyethylene bags. • 10 Dresses shall be further packed in a thick Boxboard. • Each Box Board packing shall be securely and properly packed. • Each box board shall consist of same size.
17.	8	<p><u>IDENTIFICATION LABEL</u> Each Dress shall bear following minimum information mentioned on identification label, attached as indicated in the drawing:</p> <ol style="list-style-type: none"> a. Item name/ Item description with NSN/ Pattern No. b. Material Composition and size. c. Contract number and Date. d. Year of Manufacturing. e. Firm's name, initials or Trade mark. f. Batch no.

READ:

Article No	Page No	ITEM
16.	7	<p><u>PACKING DETAILS</u></p> <p>16.1. The store when ordered to be delivered 'PACKED' shall be packed as per following instructions:</p> <ul style="list-style-type: none"> • The Dress shall be packed in a neat, dry and clean condition in standard polyethylene bags. • 10 Dresses shall be further packed in a thick Boxboard. • Each Box Board packing shall be securely and properly packed. • Each box board shall consist of same size.

		<p>16.1.1 Unique Security Code As embossed on the Inside of each Items along with corresponding Barcode, may also be indicated on outside of each polythene bag in form of stickers at a suitable place.</p> <ul style="list-style-type: none"> • Complete list of tracking/ security code must be placed inside the thick Boxboard/ Flouiring.
17.	8	<p><u>IDENTIFICATION LABEL</u></p> <p>17.1. Each Dress shall bear following minimum information mentioned on identification label, attached as indicated in the drawing:</p> <ol style="list-style-type: none"> Item name/ Item description with NSN/ Pattern No. Material Composition and size. Contract number and Date. Year of Manufacturing. Firm's name, initials or Trade mark. Batch no. <p>17.2. <u>Unique Security/ Tracking Code Mechanism</u> Same with permanent ink should be embossed in the following way on inside of each Shirt and Trouser at a suitable place:</p> <ol style="list-style-type: none"> A unique security/tracking code (10-12 digits) with permanent ink should be embossed/ printed on the inner side of each Shirt and Trouser (preferably at collar or cuff) as well as the Trouser (inner side of the front/back pocket or waist belt). The complete security/ tracking code must start with a 4-letter alphabet to represent manufacturing supplier/ firm name followed by 6 to 8 digits. For instance, 'ABCD00010786' for M/s ABCDE or 'CBDA00020786' for M/s CBDAEF. Specific alphabet should be defined in indent of store initiated by concerned depot.

RESTRICTED



PN/DID/03/13316519

See Distribution

MOST IMMEDIATE

DID
OFFICE OF NRDI (ITD
WING)

58455

23 May 2022

AMENDMENTS IN PN SPECIFICATIONS 01/2018 GSDC DRESS NO 4 (AFLOAT) 100 PERCENT COTTON

Reference:

A. PN/NS Dte/03/3717615 dated: 19 May 2022

It is intimated that proposed amendments in PN Specifications 01/2018 of GSDC Dress No 4 (100% Cotton) have been approved by NHQ (NS Dte) vide Reference above. Same are enclosed and hereby promulgated for further necessary action, please.

MUHAMMAD AFSAR
Capt PN
DID

Encl(s):

1. Amendments in PN Specifications No 01 2018

Distribution:

External:

Action:

NS Dte
Attn: DDNS II

DP Navy

RESTRICTED

AMENDMENTS IN PN SPECIFICATION 01/2018

FOR:

Article No	ITEM
0103.	INTRODUCTION
	1. This specification is prepared by Directorate of Indigenous Technical Development, Karachi, to provide necessary guidance to the potential manufacturers/ suppliers of the items mentioned herein. This specification is to be used for testing and deciding upon acceptance, or otherwise, of the items mentioned. Any alteration or addition in this specification can be suggested to ITD Directorate. However, it cannot be implemented without prior approval of DITD. This specification supersedes and replaces PN Specifications No. 03/2017 and PN Specifications 04/2017 promulgated earlier in relation to the items mentioned herein.

READ:

Article No	ITEM
0103.	INTRODUCTION
	1. This specification is prepared by Directorate of Indigenous Technical Development, Karachi, to provide necessary guidance to the potential manufacturers/ suppliers of the items mentioned herein. This specification is to be used for testing and deciding upon acceptance, or otherwise, of the items mentioned. Any alteration or addition in this specification can be suggested to ITD Directorate. However, it cannot be implemented without prior approval of DITD. This specification supersedes and replaces PN Specifications No. 03/2017.

RESTRICTED



DID
OFFICE OF NRDI (ITD
WING)

PN/DID/03/12913337

58455

See Distribution

28 March 2022

CONTRACT NO. 025022/R 2102/330364 DATED 28 MAY 2021 CLOTH FOR DIGITAL
CAMOFLAGE DRESS PAK MARINES 60/40 AND CONTRACT NO. 025024/R
2102/330422 DATED 22 JUNE 2021 CLOTH FOR DRESS NO. 4B GSDC 100
PERCENT COTTON

Reference:

- A. PN/NS Dte/03/3593754 dated: 22 Mar 2022
- B. PN/DID/03/12717170 dated: 11 Mar 2022
- C. PN/DID/03/12342044 dated: 14 Feb 2022

1. It is intimated that proposed amendments in PN specifications 01/2018 and 03/2018 have been approved by NHQ (NS Dte) vide reference A. Same are enclosed and hereby promulgated for incorporation in relevant PN specifications.

2. Letter at reference C may be treated as cancelled, please.

MUHAMMAD AFSAR
Capt PN
DID

Encl(s):

- 1. Amendment in PN specification 01 2018
- 2. Amendment in PN specification 03 2018

Distribution:

External:

RESTRICTED

AMENDEMENTS IN PN SPECIFICATION 01/2018

FOR:

S NO	ITEM	REQUIREMENT
BASE FABRIC MATERIAL SPECIFICATION (RIBBED CAMOUFLAGE CLOTH)		
4.	Colors Scheme	
	Black	19-1101 TCX
	Dark Grey	18-4006 TCX
	Medium Grey	17-4405 TCX
	Light Grey	15-4003 TCX
	Grey	16-4702 TCX
	Pastel Grey	13-4303 TCX
		Or as per approved samples held with CINS

READ:

S.NO	ITEM	REQUIRMENT
BASE FABRIC MATERIAL SPECIFICATION (RIBBED CAMOUFLAGE CLOTH)		
4.	Color Shade	Panton Shade OR L a b Values
a.		L a b
	Black	19-1101 TCX 30.96 2.44 0.82
	Dark Grey	18-4006 TCX 49.64 0.26 0.75
	Medium Grey	17-4405 TCX 54.41 -0.17 0.28
	Light Grey	15-4003 TCX 65.30 -0.31 2.28
	Grey	16-4702 TCX 72.92 -1.23 3.12
	Pastel Grey	13-4303 TCX 77.34 -0.64 3.25
b.	Color Difference	($\Delta E \leq 1$)

RESTRICTED



DID
OFFICE OF NRDI (ITD
WING)

PN/DID/03/11690723

58455

See Distribution

17 December 2021

AMENDMENT IN PN SPECIFICATION NO. 01/2018 AND 03/2018

Reference:

A. PN/NS Dte/03/3377058 dated: 09 Dec 2021

The amendments proposed in PN Specifications 01/2018 and 03/2018 have been approved by NHQ (NS Dte) vide Reference A. Same are hereby promulgated and may be incorporated in PN Specifications 01/2018 and 03/2018 as given below, please.

FOR:

Spec No.	Clause	Page No.	Description
01/2018	11.1	5	Tender Sample to be approved by INS
03/2018	11.1	5	Tender Sample to be approved by INS

READ:

Spec No.	Clause	Page No.	Description
01/2018	11.1	5	Tender Sample to be approved by TSR Committee
03/2018	11.1	5	Tender Sample to be approved by TSR Committee

MUHAMMAD AFSAR
Capt PN
DID

Distribution:

External:

RESTRICTED

RESTRICTED



DID
OFFICE OF NRDI (ITD
WING)

PN/DID/03/9509258

58455

See Distribution

16 June 2021

TENDER NO 025024/R 2102/330422 DATED 15 FEBRUARY 2021 CLOTH FOR
DRESS NO 4 GENERAL SERVICE DIGITAL CAMOUFLAGE 100 PERCENT COTTON

Reference:

- A. PN/NS Dte/03/3002010 dated: 15 Jun 2021
- B. PN/DID/03/9303197 dated: 21 May 2021
- C. PN/NS Dte/03/2956254 dated: 21 May 2021
- D. PN/DID/03/9118268 dated: 23 Apr 2021
- E. PN/COMDEP/CSD N/03/9053183 dated: 19 Apr 2021

The amendment proposed in PN Specifications 01/2018 of cloth for Dress No 4 (100% Cotton-Ashore) have been approved by NHQ (NS Dte) vide Reference A. It is requested that approved amendment as per enclosed format may be incorporated in PN Specification 01/2018 at your end, please.

BURHAN AHMAD
Capt PN
DID

Encl(s):

1. Amendment in PN Specification 01 2018

Distribution:

External:

RESTRICTED

AMENDMENT IN PN SPECIFICATION 01/2018

EOR:

PN Specification (01/ 2018) Annex A			
Heading at Annex A : BASE FABRIC PERFORMANCE TESTING			
S. No.	Page. No.	Description	Requirements
7	11	Tensile (1) Warp (2) Weft	1000 ± 5% 800 ± 5%
8		Tear Strength (1) Warp (2) Weft	44 ± 5% 48 ± 5%

READ:

PN Specification (01/ 2018) Annex A			
Heading at Annex A : BASE FABRIC PERFORMANCE TESTING			
S. No.	Page. No.	Description	Requirements
7	11	Tensile (1) Warp (2) Weft	1000 ± 5% 750 ± 5%
8		Tear Strength (1) Warp (2) Weft	35 ± 5% 44 ± 5%



DID
OFFICE OF MD ITD NRDI
(ITD WING)

PN/DID/03/5598116

58455

See Distribution

23 June 2020

CHANGE OF TITLE DRESS 4

Reference:

- A. PN/COMDEP/CSD N/03/5666972 dated 12 June 2020
- B. PN/DID/03/5622998 Dated 9 June 2020
- C. PN/NS Dte/03/2335545 Dated 5 June 2020
- D. PSO Conference 3/2020
- E. PN Specification 01/2018
- F. PN specification 02/2018
- G. PN/DGITD/03/1056882 dated 28 March 2018

1. It is submitted that the term Dress No 4 (Camouflage) or 4B (Digital) is to be discontinued, and replaced as Dress No 4 as directed vide reference 'C'. Therefore, PN Specifications at reference E & F, same is promulgated vide reference G have been amended.

2. Aforesaid in view, it is requested that Amendment at respective places may be endorsed at your end as per enclosed format.

For: Dress 4B

Read: Dress 4

MUHAMMAD AYUB
Cdr PN
DID

Encl(s):

1. Amendments in PN Specification 01 2018
2. Amendment in PN Specification 02 2018

AMENDMENTS IN PN SPECIFICATION 01/2018

S. NO	PN Specification 01/2018, along with Page No/ clause No	Description
1.	Page 1	General Service Digital Camouflage Dress No 4B (Afloat) 100% Cotton
2.	Page 3 Details & Annexes	Technical Details of GSDC Dress No 4B (Afloat) 100% Cotton Manufacturing Details of GSDC Dress No. 4B (Afloat) 100% Cotton
3.	Page 4 clause 1.1	General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % Cotton (Bush Jacket, Trouser, PAK NAVY soft tally and Camouflage Jockey Cap)
4.	Page 4 Clause 4.1	This specification covers the manufacturing / inspection requirements of cloth made from cotton to be used in the manufacturing of uniform, namely General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % Cotton (Bush Jacket & Trouser) to be used by personnel of Pakistan Navy. This specification lays down the standard to which the stores shown under designation above should conform. It defines and lays down the quality, standard and details of materials, workmanship and finish. It also lays down the details of sampling, testing, inspection rejection, marking, preservation, packing and delivery etc.
5.	Page 5 Clause 7	Technical details for General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % cotton
6.	Page 5 Clause 7.1	The technical details of General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % Cotton is given at Annex A of this specification.
7.	Page 5 Clause 8.	Manufacturing details for General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % cotton
8.	Page 5 Clause 8.1	Manufacturing details of General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % cotton will be as per Annex B of this specification.
9.	Page 5 Clause 9.1	Workmanship and finish of the General Service Digital Camouflage (GSDC) Dress No. 4B shall be equal to the sealed sample. It shall be best of its class and to the entire satisfaction of the inspector.
10.	Page 9 & 10 Annex A	Technical details for General Service Digital Camouflage (GSDC) Dress No 4B (Afloat) 100% Cotton-

11.	Page 9 Annex B	Manufacturing details for General Service Digital Camouflage (GSDC) Dress No 4B (Afloat) 100% Cotton-
12.	Page 12 and 13 Appendix I to Annex A:	Digital Camouflage Design/ Pattern Of Dress NO. 4B
13.	Page 14 Annex B	Manufacturing details of General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100% cotton-
14.	Clause 1	GSDC Dress No. 4B (Afloat) 100 % cotton is to be manufactured as per measurement schedule and drawing at Appendix I and Appendix II respectively.
15.	Clause 2	'PAK NAVY' soft tally as per Annex C and D of this specification shall be attached above left chest pocket of Dress No. 4B . Jockey /Sea Cap shall be supplied as per Annex E and F.
16.	Page 14, 15 ,16 and Appendices I to annex B	Measurement schedule of Dress No.4B Bush Jacket and Trouser
17.	Appendices II to annex B	Drawing of Dress No. 4B Bush Jacket and Trouser
18.	Page 21	Tech. Details of 'PAK NAVY' soft tally for Camouflage Dress No 4B
19.	Page 23	Pak Navy soft tally for Camouflage Dress (4B)
20.	Page 28	Jockey Sea Cap Officers Dress 4B
21.	Page 29	Jockey Sea Cap CPO's, Sailors Dress 4B



DGITD
MATERIEL BRANCH
NAVAL HEADQUARTERS
NSSD AREA WEST
WHARF ROAD KARACHI

PN/DGITD/03/1463776

59256

See Distribution

21 December 2018

AMENDMENT IN PN SPECIFICATION OF DRESS 4B

Reference:

- A. PN/NS Dte/03/1375033 dated: 12 Nov 2018
B. PN/DGITD/03/1285656 dated: 10 Sep 2018
C. PN/DGITD/03/1086039 dated: 12 Apr 2018
D. PN/DGITD/03/1056882 dated: 28 Mar 2018

Apropos letter at reference A, following amendments may please be incorporated in PN Specification No. 01/2018 & 02/2018 promulgated vide reference D:

a. **Amend Para (16) Packing Details of PN Specification No. 01/2018 & 02/2018**

- (i) Packing details at Para 16 may be amended after addition of fabric and Jockey cap packing instruction as follows:

FABRIC PACKING DETAILS

- Accepted fabric shall be packed in the form of rolls.
- Each roll shall have length from 100 yards up to 200 yards (within multiple of 4 yds).
- The rolls should be packed/ wrapped in polyethylene sheet, vacuumed and in sealed packing.
- Each roll shall bear identification label indicating description of store, year of manufacture and contract

no, material composition, fabric width and length,
contractors name, batch no. ,shrinkage

JOCKEY CAP PACKING DETAILS.

- 10 X Camouflage Jockey/ Sea Caps bundles shall be packed in a neat and tidy condition in standard polyethylene packing of 0.035 mm thickness. These bags/ bundles shall be sealed with transparent adhesive tape 2.54 cm of thickness 0.04 – 0.05 mm.
- 05 X such bundles (50 caps) shall be packed in Carton Corrugated Card board box (07 ply).
- Each Carton shall contain one size of Camouflage Sea Caps only.
- Each box Board Packing shall be securely and properly packed with transparent adhesive tape 10 cm of thickness 0.04– 0.05 mm.

(ii) Amended measurement schedule and drawings are also enclosed to replace Appendix 1 and 2 of Annex B at your end please.

ASMA SOHAIL
Lt Cdr PN
SO TEXTILE DITD (S)


Encl(s):

1. Appendix 2 page 17
2. Appendix 2 page 18
3. Appendix 2 page 19
4. Appendix 2 page 20
5. Appendix 1

Distribution:

External:

Action:




FRONT VIEW

BACK VIEW


1252

NOTE:
FOR FURTHER DETAILS SEE SEALED STOCK SAMPLE.


				DITD KARACHI							
				TITLE: SHIRT CAMOUFLAGE (MAIN BODY) SIZE- MF-40							
				DWG.NO. TD-2445/2018		DIMENSIONS: INCHES					
				DATE: 28-08-2018		SCALE: N.T.S					
DRAWN BY		CHECKED BY		APPROVED BY							
--SD--		--SD--		--SD--							
H.O/M M.ASGHAR I/c DWG		LTCDR ASMA SOHAIL SO,R&D		CDR AZHAR MIR DITD							
		24	FRONT POCKET VELCRO WIDTH	5	12	FLAG VELCRO SIZE	4x6 CM				
		23	FRONT POCKET VELCRO HIGHT	0.5	11	SLEEVE PATCH WIDTH BOTTOM	7				
		22	FRONT POCKET HEM	1	10	SLEEVE PATCH WIDTH TOP	8				
33	FRONT POCKET WIDTH	5.25	21	FRONT POCKET PLACEMENT	7.5	09	SLEEVE PATCH LENGTH	7			
32	FRONT PLACKET W LEFT SIDE	1.75	20	FRONT POCKET SIDE BOX	1.5	08	ARM HOLE	10.5			
31	FRONT PLACKET W RIGHT SIDE	1.25	19	FRONT POCKET LENGTH INCLUDING FLAP	6.75	07	SLEEVE OPENING	6			
30	FRONT POCKET TALLY VELCRO	1x5.25	18	FRONT FLAP HEIGHT	2.5	06	SLEEVE LENGTH	23			
29	SIDE LOOP LENGTH	3	17	FRONT FLAP WIDTH	5.25	05	SHOULDER	18.75			
28	SIDE LOOP WIDTH	2	16	SLEEVE LOOP WIDTH	2	04	BOTTOM	23			
27	COLLAR CORNER	2.5	15	SLEEVE LOOP LENGTH	3	03	WAIST	22			
26	COLLAR HEIGHT FROM CENTER BACK	3	14	CLIFF HEIGHT	2	02	CHEST	23			
25	COLLAR	15.5	13	FLAG VELCRO PLACEMENT FROM SHOULDER SEAM	1.75	01	LENGTH FROM CENTER BACK	29			
S.NO	ITEM	INC	S.NO	ITEM	INC	S.NO	ITEM	INC			
				DESCRIPTION 17							




POCKET




ELBOW PATCH




SIDE LOOP




SHOULDER FLAP



CUFF LOOP




COLLAR




NAME TALLY




BUTTON HOLE TAG



FLAG PATCH



AIR VENT



FRONT

SIDE




BACK

BUTTON SCALE: 1:2

NOTE:
18 FOR FURTHER DETAILS SEE SEALED SAMPLE.

1253

DITD KARACHI		
TITLE: SHIRT CAMOUFLAGE (SMALL PARTS) SIZE: MF-40		
DWG.NO. TD-2446/2018	DIMENSIONS: INCHES	
DATE: 28-08-2018	SCALE: N.T.S	
DRAWN BY --SD-- H.D/M M.ASGHAR 1/c DWG.	CHECKED BY --SD-- LTCDR ASMA SOHAIL SQ, R&D	APPROVED BY --SD-- CDR AZHAR MIR DITD



1254

S.NO	ITEM	INC	S.NO	ITEM	INC
25	NOTION ADJUSTABLE ROPE	Ø2/Ø	14	THIGH POCKET FLAP HEIGHT	3
24	FLY LENGTH FULL	7	13	THIGH POCKET FLAP WIDTH	7.5
23	FLY WIDTH	1.5	12	THIGH POCKET LENGTH	8
22	BELT LOOP WIDTH TOP	1	11	FRONT POCKET SIDE SEAM	7
21	BELT LOOP WIDTH BOTTOM	1.75	10	FRONT POCKET OPENING WAIST SEAM	2.25
20	BELT LOOP LENGTH	5	9	FRONT PATCH LENGTH	10
19	THIGH POCKET PLACEMENT	10.5	8	BACK RISE	16.75
18	WAIST BELT	1.75	7	FRONT RISE	11.75
17	BACK PATCH INSIDE LENGTH	6.25	6	OUT SEAM	39
16	BACK POCKET FLAP HEIGHT	2.5	5	BOTTOM	9.25
15	BACK POCKET FLAP WIDTH	6	4	KNEE ON 13" FROM CROUCH	10.25
			3	THIGH	28
			2	HIPER FROM BELT	45
			1	WAIST	36
19 DESCRIPTION					

DITD KARACHI

TITLE:
**TROUSER CAMOUFLAGE
(MAIN BODY) SIZE:MF-36**

DWG.NO. TD-2447/2018 DIMENSIONS: INCHES

DATE: 28-08-2018 SCALE: N.T.S

DRAWN BY CHECKED BY APPROVED BY

--SD--

--SD--

--SD--


H.D/M
M.ASGHAR
I/c DWG

LTCDR
ASMA SOHAIL
SO,R&D


CDR
AZHAR MIR
DITO

NOTE:


FOR FURTHER DETAILS SEE SEALED SAMPLE.




FRONT POCKET




THIGH POCKET




KNEE PATCH




BACK POCKET



HIP PATCH



BELT LOOP




WAIST ADJUSTMENT TAPE

1255



FLY



FRONT

SIDE

BACK

SCALE: 1:2

NOTE:

20 FOR FURTHER DETAILS SEE SEALED SAMPLE.

DITD KARACHI

TITLE: TROUSER CAMOUFLAGE (SMALL PARTS) SIZE: MF-36

DWG.NO. TD-2448/2018	DIMENSIONS: INCHES	
DATE: 28-08-2018	SCALE: N.T.S	
DRAWN BY --SD-- H.D/M M.ASGHAR 1/c DWG.	CHECKED BY --SD-- LTCDR ASMA SOHAIL SO.R&D	APPROVED BY --SD-- CDR AZHAR MIR DITD



DGITD
NSSD WEST WHARF
ROAD KARACHI

PN/DGITD/03/1086039

59256

See Distribution

12 April 2018

AMENDMENT PN SPECIFICATION OF GENERAL SERVICE DIGITAL CAMOUFLAGE (GSDC) DRESS NO.4B 100 COTTON AND 60 COTTON 40 POLYESTER

Reference:

- A. PN/NS Dte/03/1078667 dated: 11 Apr 2018
- B. PN/ Chief Inspector of Naval Stores/ 03/1073494 dated 06 Apr 18
- C. PN/DGITD/03/1056882 dated: 28 Mar 2018
- D. PN/DGITD/03/1083677 dated 11 Apr 18

1. Apropos letter at reference A and B, following amendments may please be incorporated in PN Specification No. 01/2018 and 02/2018 promulgated vide reference C:

a. Amend Para (3) under heading "Base Fabric Performance testing" Annex A of PN Specification No 01/2018 and 02/2018

Color Fastness to Rubbing (Wet) Staining

For	GS: 3 or better
Read	GS: 4 or better

b. Amend Para (14) under heading "Base Fabric Performance testing" Annex A of PN Specification No 01/2018 and 02/2018"

Pilling resistance after 5,000 cycles

For	Grade 4
Read	Grade 5

2. Letter at reference D may please be treated as cancelled.

ASMA SOHAIL
Lt Cdr PN
SO TEXTILE DITD (S)

Viewed by: NSO Naqem Uddin CAO NC dated: 27/04/2018 12:27:34



PN SPECIFICATION NO 01/2018

PAKISTAN NAVY SPECIFICATION 01/2018

PROMULGATION DATE: 26 Mar 2018

GENERAL SERVICE DIGITAL
CAMOUFLAGE
DRESS NO 4B (AFLOAT) 100%
COTTON

Prepared by:

Directorate of Indigenous
Technical Development
at NSSD, West Wharf Road
KARACHI
Tel: 021 48508410
Fax: 021 99214765

AMENDMENT RECORD

Amd No	Date	Text Effected	Signature and Date

REVISION NOTE

The specification has been prepared to bring the test methods and procedures into line with up-to-date. PN requirements and facilities held in Pakistan. CINS may request to amend any test requirement/ test procedure in light of the experience emanating from its inspection history, through the feedback form placed at Annex J. However, such an alternation will be effective when the amendment is promulgated by this Directorate, and will be effective on the contracts which materialize after the promulgation date of respective amendment.

CONTENTS

<u>Description</u>	<u>Page</u>
Contents	03
<u>Details</u>	
Designation	04
Usage	04
Introduction	04
Scope	04
Related Documents	04
Terms & Definitions	05
Technical Details of GSDC Dress No. 4B (Afloat) 100% Cotton	05
Manufacturing Details of GSDC Dress No. 4B (Afloat) 100% Cotton	05
Quality of Workmanship and finishing	05
Testing	05
Tender Sample	05
Advance Sample	06
Inspection	06
Stamping of Accepted/Rejected Stores by Inspector	07
Special Instructions	07
Packing details	08
Identification label	08
Packing list	08
Marking of Stores	08
Delivery	08
<u>Annexes:</u>	
A. Technical Details of GSDC Dress No. 4B (Afloat) 100% Cotton	10
B. Manufacturing Details of GSDC Dress No. 4B (Afloat) 100% Cotton	14
C. Technical details of PAK Navy Soft Tally	21
D. Manufacturing details of Pak Navy Soft Tally	22
E. Technical details of Camouflage Jockey Cap / Sea Cap	24
F. Manufacturing details of Camouflage Jockey Cap / Sea Cap	26
G. Terms & Definitions	30
H. Guidelines for Inspection – Specific Parts Defects	31
J. Feedback Form	33

1. DESIGNATION

General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % Cotton (Bush Jacket, Trouser, PAK NAVY soft tally and Camouflage Jockey Cap)

2. USAGE

2.1 This dress will be used by Officers, CPOs and Sailors of Pakistan Navy on afloat vide NHQ letter PN/NS Dte/03/878204 dated 30 Nov 17.

3. INTRODUCTION

3.1 This specification is prepared by Directorate of Indigenous Technical Development, Karachi, to provide necessary guidance to the potential manufacturers/ suppliers of the items mentioned herein. This specification is to be used for testing and deciding upon acceptance, or otherwise, of the items mentioned. Any alteration or addition in this specification can be suggested to ITD Directorate. However, it cannot be implemented without prior approval of DITD. This specification supersedes and replaces PN Specifications No. 03/2017 and PN Specification 04/2017 promulgated earlier in relation to the items mentioned herein.

3.2 This specification booklet includes 09 Annexes, and consists 33 pages, including the cover.

4. SCOPE

4.1 This specification covers the manufacturing / inspection requirements of cloth made from cotton to be used in the manufacturing of uniform, namely General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % Cotton (Bush Jacket & Trouser) to be used by personnel of Pakistan Navy. This specification lays down the standard to which the stores shown under designation above should conform. It defines and lays down the quality, standard and details of materials, workmanship and finish. It also lays down the details of sampling, testing, inspection rejection, marking, preservation, packing and delivery etc.

4.2 The supplier/ manufacturer shall comply in every respect with the terms of this specification and ensure that the stores conform to it, in all respects.

5. RELATED DOCUMENTS

5.1 The standards and documents that have been referred to in this specification are:

a.	ISO 1833	Textile – Quantitative chemical analysis
b.	ISO-3801	Determination of mass per unit length and area
c.	ISO-7211/2	Determination of number of threads per unit length
d.	ISO-7211/5	Determination of linear density of yarn removed from fabric
e.	ISO-105-C03	Colour fastness to Washing test No. 3
f.	ISO-105-E02	Colour fastness to Seawater test
g.	ISO-105-X12	Colour fastness to Rubbing test
h.	ISO-105-E04	Colour fastness to Perspiration
j.	ISO 13934-01 1999	Textile- Tensile properties of fabrics (strip method)
k.	ISO 13937-01 1999	Textile- Tear properties of fabric (Elmendorf)
m	AATCC 128-2009	Wrinkle Recovery of fabric
n.	AATCC 79-2010	Absorbency of Textiles
o.	ISO 9237:1995	Determination of permeability of fabric to air
p.	AATCC 195:2010	Test for evaluation of Moisture Management
q.	ASTM D 1230	Flammability of Apparels

r.	ISO 6330 (3A)	Domestic washing and drying procedures for textile testing
s.	BS EN ISO 12945-2	Determination of fabric propensity to surface fuzzing and to pilling
t.	BS EN ISO 12947-4	Determination of the abrasion resistance of fabrics by the Martindale method
u.	BS EN 25077	Determination of Dimensional Change in washing and drying
v.	ISO 3071	Determination of pH of aqueous extract
w.	AATCC 16 option 3	Colorfastness to light
x.	BS 4162	Methods of test for buttons
y.	AATCC 133	Colorfastness to hot press
z.	ASTM D 5171	Standard test method for impact resistance of plastic sew through buttons
a1.	ASTM D5169	Dynamic shear strength of hook and loops touch fastener (Velcro)
a2.	ASTM D 5170	T Peel Strength of hook and loop touch fastener (Velcro)

6. TERMS & DEFINITIONS

6.1 Definitions for the terms used in this standard are given at Annex G.

7. TECHNICAL DETAILS FOR GENERAL SERVICE DIGITAL CAMOUFLAGE (GSDC) DRESS NO. 4B (AFLOAT) 100 % COTTON

7.1 The technical details of General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % Cotton is given at Annex A of this specification.

8. MANUFACTURING DETAILS FOR GENERAL SERVICE DIGITAL CAMOUFLAGE (GSDC) DRESS NO. 4B (AFLOAT) 100 % COTTON

8.1 Manufacturing details of General Service Digital Camouflage (GSDC) Dress No. 4B (Afloat) 100 % cotton will be as per Annex B of this specification.

9. QUALITY OF WORKMANSHIP AND FINISHING

9.1 Workmanship and finish of the General Service Digital Camouflage (GSDC) Dress No. 4B shall be equal to the sealed sample. It shall be best of its class and to the entire satisfaction of the inspector.

10. TESTING

10.1 The material shall be subjected to tests laid down in this specification at Annex A of this specification and related documents. At least one complete dress and 03 meter fabric will be required to complete all the tests mentioned at Annex A of this specification. The material may also be subjected to such tests which are deemed necessary by the inspection authority in order to determine their suitability. Inspecting Authority reserves the right to get any B/R samples tested from any reputable Laboratory other than PN. However, any test considered important by Inspecting Authority other than Annex A may also be conducted in order to check its suitability.

11. TENDER SAMPLE

11.1 Tender sample to be approved by INS

11.2 For each contract following material shall be supplied by the manufacturer at the time of tendering.

a.	Finished Garment	-	03 Nos.
b.	Fabric	-	05 Meter

c.	Fused Buckram	-	01 Meter
d.	Buttons	-	05 Nos.
e.	Stitching Thread	-	50 Grams
f.	Velcro	-	0.5 meter
g.	Waist adjustment Tape	-	02 No.s

12. ADVANCE SAMPLE

12.1 Advance sample or pre-production sample, when required, shall be submitted in accordance with terms of the contract for inspection, testing and approval by CINS. The minimum quantities required are 05 dresses along with samples of materials used in manufacturing of garments for inspection.

12.2 Whenever Tender, Advance or pre-production sample is not required, the suppliers / manufacturer are advised in their own interest to submit to the Inspecting Officer or his representative an initial delivery of One % of the contract or ten dresses, whichever are more along with samples of materials for inspection.

12.3 The approval of the sample mentioned in Para 11 & 12 authorizes the commencement of bulk production but does not relieve the suppliers/ manufactures from compliance with all the provisions of this specification. One approved sample shall be properly sealed by INS and returned to the firm for guidance; rest of the approved sample shall be retained by INS for future use in bulk Inspection.

12.4 The Pre-production sample shall be manufactured by the manufacturer with the same facilities which will be used for manufacturing of the bulk items.

12.5 Firm shall provide advance sample along with quality verification reports of fabric from an accredited laboratory to ensure in process inspection/ quality procedure of the firm.

13. INSPECTION

13.1 Bulk representative sample B/R random sampling will be carried out as per rules in vogue.

13.2 Bulk Inspection Bulk inspection will be carried out after satisfactory completion of Visual Examination and Testing of B/R Sample.

13.3 Inspection of Store 100% of the offered store shall be inspected. The guide lines for such examination/inspection are listed at Annex H. Stage inspection of Dresses be carried out as deemed appropriate.

13.4 Inspection/ Acceptance and Rejection of Stores Inspection/ acceptance is to be carried out to the satisfaction of Chief Inspector Naval Stores.

13.5. The dresses shall be examined for the correctness of material, shape, design, dimension, size, workmanship and finish.

13.6. All dresses shall be inspected w.r.t defective shape, discoloration/ fading, pinholes, closing of dresses are to be especially checked.

13.7. CINS reserves the right to reject the whole supply in case, upon examination, material or packing of any sample or portion of the consignment is found NOT CONFORMING to this specification.

13.8. If on examination of 5% of any delivery, 20% of those examined from bulk supply are found NOT CONFORMING to this specification in respect of the pattern, dimensions, workmanship and finish, the whole consignment may be rejected without any compromise.

13.9. All stores and packing NOT fully in accordance with this specification shall be rejected.

13.10. Dresses with major defects as described in Annex H of this specification will be rejected.

13.11. **Responsibility for Inspection** The supplier is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. PN reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

13.12 **Responsibility for Compliance** The inspection set forth in this specification shall become a part of the supplier's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to PN for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit PN to acceptance of defective stores (material).

13.13 **Replacement by the Contractor** The supplier/ manufacturer is responsible for replacement of the consignment or any part thereof whenever it is found to be not conforming to this specification. The supplies so tendered in replacement, shall be subjected to testing/inspection and acceptance by the Inspecting Officer.

13.14 **Responsibility for Safety** The supplier/manufacturer is wholly responsible for the safety of supplies during inspection, storage at firm's premises, proper packing, dispatch and delivery up to consignee.

14. **STAMPING OF ACCEPTED/ REJECTED STORES BY THE INSPECTOR** Following instructions are to be followed:

14.1 **Stamping of Accepted Stores** Each acceptable Dress shall be stamped with Inspector's Individual Acceptance Mark. The stamping shall be legible.

14.2 **Stamping of Rejected Stores** The rejected Dress shall be marked with Inspector's Rejection Mark to avoid re-submission by the supplier.

14.3 The Inspector is the authority in all matters pertaining to inspection.

15. **SPECIAL INSTRUCTIONS**

15.1 **CARE INSTRUCTIONS** Care instructions in English and Urdu shall be attached with each Dress as indicated in the drawing and have minimum requirement as follows:

- Washing procedure.
- Drying procedure.
- Any Prohibition.

16. **PACKING DETAILS** The store when ordered to be delivered 'PACKED' shall be packed as per following instructions:

- The Dress shall be packed in a neat, dry and clean condition in standard polyethylene.
- 10 Dresses shall be further packed in a thick Boxboard.
- Each Box Board packing shall be securely and properly packed.
- Each box board shall consist of same size.

17. **IDENTIFICATION LABEL** Each Dress shall bear following minimum information mentioned on identification label, attached as indicated in the drawing:

- a. Item name/ item description with NSN/Pattern No.
- b. Material Composition and size
- c. Contract number and Date
- d. Year of manufacture
- e. Contractor's name, initials, or trade mark
- f. Batch no.

18. **PACKING LIST** Firm is bound to provide a packing list of store offered for inspection alongwith the challan, which include complete details about the store i.e Pattern No., Designation, quality packed, size, quantity, contract No, and Date, Challan No. and Date. A packing list shall be enclosed after completion of inspection with each packed box giving full details about the stores packed i.e. Pattern No., Designation, quality packed, size, quantity, contract No, and Date, I/Note No. or voucher No. and date, consignee, Consignor, Date of packing and packer's signature.

19. **MARKING OF STORES** In addition to any special marking required by contract or order, the marking of packages shall be stenciled with quick drying Black ink/ Paint in accordance with Specification No. NS/MISC/002/80 with clearly defined characters as described below:

- a. On Front and Top
 - (1) Catalogue No and Designation of the store packed.
 - (2) Contract No and date.
 - (3) Quantity of the Item packed.
- b. On Back
 - (1) Consignee address.
 - (2) Designation i.e Railway Station.
 - (3) Weight of the Package.
 - (4) The No. of individual Package and the total No of Packages in the consignment joined by the Word 'of 'e.g. 2 of 300.
- c. On Bottom
 - (1) Consignor's Name.
 - (2) Voucher No. or inspection note no. and date.
 - (3) Month and year of packing.

20. **DELIVERY**

- 20.1 The consignment of store will be delivered in accordance with the terms of contract.
- 20.2 The store shall be delivered in Brand new, clean and dry condition.

20.3 The contractor / manufacturer is fully responsible for the safety of the supplies during inspection, storage at firms premises proper packing, dispatch and delivery up to consignee.

XXXXSDXXX

AZHAR MIR

Commander Pakistan Navy

Director

Annexes:

- A. Technical details for General Service Digital Camouflage (GSDC) Dress No. 4 B (Afloat) 100 % Cotton
- B. Manufacturing details for General Service Digital Camouflage (GSDC) Dress No. 4 B (Afloat) 100 % Cotton
- C. Technical details of PAK Navy Soft Tally
- D. Manufacturing details of Pak Navy Soft Tally
- E. Technical details of Camouflage Jockey Cap / Sea Cap
- F. Manufacturing details of Camouflage Jockey Cap / Sea Cap
- G. Terms & Definitions
- H. Guidelines for Inspection – Specific Parts Defects
- J. Feedback Form

Distribution:

DP (N)

CINS

DNS

CO PNCSD

**TECHNICAL DETAILS FOR GENERAL SERVICE DIGITAL CAMOUFLAGE (GSDC) DRESS
NO. 4B (AFLOAT) 100% COTTON**

S NO	ITEM	REQUIREMENT
BASE FABRIC MATERIAL SPECIFICATION (RIBBED CAMOUFLAGE CLOTH)		
1.	Material	100% Cotton
2.	Count of Yarn	Warp $20^{\circ} \pm 2$ (29.5 \pm 2 Tex) Weft $16^{\circ} \pm 2$ (37 \pm 2 Tex) Ring spun Combed yarn shall be used
3.	Threads per Inch	Warp 123 ± 5 (Ends) Weft 63 ± 5 (Picks)
4.	Colors Scheme	Black Dark Grey Medium grey Light grey Grey Pastel Grey 19-1101 TCX 18-4006 TCX 17-4405 TCX 15-4003 TCX 16-4702 TCX 13-4303 TCX Or As per approved sample held with CINS
5.	Weave Pattern	Twill weave 2/1 + Rip Stop
6.	Threads /Rip	Warp 2 each single Weft 2 each single
7.	Size of Rip	Warp $6\text{mm} \pm 1\text{mm}$ Weft $6\text{mm} \pm 1\text{mm}$
8.	Weight (gm/sq.mtr)	$245 \text{ gm} \pm 2\%$
9.	Finish	Mercerize, pre- shrink by sanforize and hydrophilic softener (nano finish)
10.	Finish width	59"
11.	Nature of Dye	Ground Print Vat dye Vat print
12.	Digital Camouflage Design Pattern	As per Appendix I and approved sample held with CINS
BASE FABRIC PERFORMANCE TESTING		
1.	Color fastness to washing a. Change in Shade b. Staining	GS: 4 or better GS: 4 or better
2.	Color Fastness to Rubbing (Dry) Staining	GS: 4 or better
3.	Color Fastness to Rubbing (Wet) Staining	GS: 3 or better
4.	Color Fastness to light Change in Shade	GS: 4 or better
5.	Color Fastness to perspiration a. Change in Shade b. Staining	GS: 4 or better GS: 4 or better

PN SPECIFICATION NO 01/2018

6.	Color Fastness to Sea Water a. Change in Shade b. Staining		GS: 4 or better GS: 4 or better
7.	Tensile strength (N)	Warp Weft	1000 \pm 5% 800 \pm 5%
8.	Tear Strength(N)	Warp Weft	44 \pm 5% 48 \pm 5%
9.	Flammability		Class1 Flame spread time \geq 3.5 sec
10.	Dimensional Stability test after 3 HL 40°C Warp Weft		\pm 2% \pm 2%
11.	Wrinkle recovery		Minimum 2
12.	Crease recovery		150° \pm 3%
13.	Appearance after 5-10 washes (3A) with tumble dry		Satisfactory
14.	Pilling resistance after 5,000 cycles		Grade 4
15.	Abrasion resistance after 6,000 cycles		No thread break
16.	Air permeability(mm/sec at 100 Pa)		Minimum 45
17.	Moisture Management		0.65 Min
18.	Water absorbency (drop test)		Front side 7 sec(max) Back side 6 sec (max)
19.	pH level		6-8

STITCHING THREAD SPECIFICATION

1.	Material		Polyester
2.	Construction		2 cord each single
3.	Count of yarn		2/31.5 Tex \pm 3%
4.	Breaking Strength (24")		2.23 Kg \pm 250 gms
5.	Shade		Light grey or Pantone 15-4003 TCX
6.	Color fastness to washing (Test No. 3) a. Change in Shade b. Staining		GS: 4 GS: 4

VELCRO TAPE MATERIAL SPECIFICATION

1.	Material Male Female		Nylon Nylon
2.	Colour		Light grey or Pantone 15-4003 TCX

VELCRO TAPE PERFORMANCE TESTING

1.	1. Before sticking / unsticking 300 times at 300 g. 2. After sticking / unsticking 300 times at 300g.		Satisfactory Satisfactory
2.	Peel Strength (lbs per in width)		1.5
3.	Shear strength(PSI)		10

WAIST ADJUSTMENT TAPE

1	Material		100% Cotton
---	----------	--	-------------


2.	Color	Light grey or Pantone 15-4003 TCX
BUTTONS		
1	Material	Plastic
2.	Color	Black Pantone # 19-4006 TCX
BUTTON PERFORMANCE TESTING		
1.	Color fastness to water	GS 4 or better
2.	Pull test at 90 N	No crack, chips or breakage No structural failure No center break out
3.	Impact resistance	No crack, chips or breakage
4.	Color fastness to heat (hot pressing)	GS 4
5.	Appearance after washing	No color transfer on fabric

Appendix:

- I. DIGITAL CAMOUFLAGE DESIGN/ PATTERN OF DRESS NO. 4B

DIGITAL CAMOUFLAGE DESIGN/ PATTERN OF DRESS NO. 4B

4B Pixilated Camo



ANNEX B TO
PN SPECIFICATION NO 01/2018
PROMULGATION DATE 26 Mar 2018

MANUFACTURING DETAILS OF GENERAL SERVICE DIGITAL CAMOUFLAGE (GSDC)
DRESS NO. 4B (AFLOAT) 100% COTTON

1. GSDC Dress No. 4 B (Afloat) 100 % cotton is to be manufactured as per measurement schedule and drawing at Appendix I and Appendix II respectively.
2. 'PAK NAVY' soft tally as per Annex C and D of this specification shall be attached above left chest pocket of Dress No. 4 B. Jockey /Sea Cap shall be supplied as per Annex E and F.
3. The sewing/stitching thread should match with the base fabric colour i.e light grey or Pantone 15-4003 TCX and spun polyester.
4. In Bush jacket metallic air vents are placed at arm pits both side front and back and two in upper and lower side of each back pleat. Outer dia is 11mm and inner dia is 4.5 mm. Shade of metallic brass air vent should match with the base fabric color i.e. light grey or Pantone 15-4003 TCX.
5. Polyester Buttons used should be Mat finished, 4 holes with 19 mm dia (30) ligne with 4 mm thickness and black in colour. Buttons of 16 mm dia with 4 mm thickness shall be used on shoulders only. The button is to be fastened with same matching black colour thread with cross sewing neatly.
6. On bush jacket collar ends, pockets and flaps, front placket, sleeves loops and back pleats are to be reinforced with bartack.
7. In Bush jacket on back pleats, joint of front and back panels, sleeves, arm joint, shoulder, cuffs and elbow patch double needle stitching is required.
8. Bush jacket shall be 1" bottom hemmed.
9. Soft paper fusing shall be used in collar, front pocket flaps and shoulder flaps.
10. Buttonholes are to have at least 22 stitches per 2 cm and to be bar-tacked or taper barred.
11. In trouser fly, cross pockets, knee and seat patches, thigh pockets, and side and seat seam are to be double needle stitched.
12. On trouser on front cross pockets end, thigh pockets, pockets bag and its flaps and back pockets and its flap, waist loops inner side bartack shall be done.
13. Two spare buttons each for bush jacket and trouser be provided/ stitched on the garment.
14. Pocket lining of same camouflage fabric shall be used.
15. Bottom adjustment dori/ rope of same camouflage fabric shall be attached at bottom of trouser. One end of the rope shall be stitched with the trouser to avoid slippage of dori/ rope during washing.

Appendices:

- I. MEASUREMENT SCHEDULE OF DRESS NO. 4B BUSH JACKET AND TROUSER
- II. DRAWING OF DRESS NO. 4B BUSH JACKET AND TROUSER

PN SPECIFICATION NO 01/2018


APPENDIX I TO ANNEX B TO
PN SPECIFICATION NO 01/2018
PROMULGATION DATE 26 Mar 2018

MEASUREMENT SCHEDULE OF DRESS NO. 4B CAMOUFLAGE BUSHJACKET (INCHES)																		
SR	Description	XXS 34	XSF 36	XSL 36	SF 38	SL 38	MF 40	ML 40	LF 42	LL 42	XLF 44	XLL 46	XXL 48	XXL1 48	XXL2 50	XXL3 52	XXL4 54	TOL
1	Length from center back.	29.5	29.5	31	29.5	31	29.5	31	29.5	31	31	31	31	31	31	32	32	0.75
2	Chest.	20	21	21	22	22	23	23	24	24	25	26	27	27	28	29	30	0.5
3	Waist.	19	20	20	21	21	22	22	23	23	24	25	26	26	27	28	29	0.5
4	Bottom.	20	21	21	22	22	23	23	24	24	25	26	27	27	28	29	30	0.5
5	Shoulder.	16.75	17.25	17.25	18	18	18.75	18.75	19.5	19.5	20.25	20.25	21	21	21	21	21.5	0.25
6	Sleeve Length.	23.5	24	24.75	24	24.75	24.5	25.25	24.5	25.25	25	25.5	25.5	25.5	26	27	27	0.5
7	Sleeve opening.	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	0.375
8	Arm hole.	10	10.5	10.5	10.5	10.5	11	11	11	11	11.5	11.5	11.5	11.5	11.5	12	12	0.5
9	Sleeves patch length.	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	7.75	0.25
10	Sleeves patch width top.	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	0.25
11	Sleeve patch width bottom.	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	0.25
12	Flag Velcro size.	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	4/6CM	
13	Flag Velcro placement from shoulder seam.	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	
14	Cuff height.	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	0.125
15	Sleeve loop height.	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	0.25
16	Sleeve loop Width.	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	0.125
17	Front flap width.	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	0.25
18	Front flap height.	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	0.125
19	Front pocket length including flap.	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	0.25
20	Front pocket width.	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	5.25	
21	Front pocket side box.	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.125
22	Front pocket placement.	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5	0.25
23	Front placket width right side.	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	1.25	0.125
24	Front placket width left side.	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	0.125
25	Front pocket hem.	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.125
26	Front pocket Velcro height.	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	
27	Front pocket Velcro width.	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	
28	Front pocket tally Velcro (width & Length).	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	1/5.25	
29	Collar.	15	15.5	15.5	16	16.5	16.5	16.5	17	17	17.5	18	18	18	18.5	19	19	0.375
30	Collar height from center back.	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	3.125	0.125
31	Collar corner.	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	0.125
32	Side loop width	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	0.125
33	Side loop length	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	0.125

MEASUREMENT SCHEDULE OF DRESS NO. 4 B CAMOUFLAGE TROUSER (INCHES)

SIR	DESCRIPTION	XXS	XSF	XSL	SF	SL	MF	ML	LF	LL	XLF	XL1	XXL	XXL1	XXL2	XXL3	XXL4	TOL
28		30	30	32	32	34	34	34	36	36	38	40	42	44	46	48	50	
1	Waist	30	30	32	32	34	34	34	36	36	38	40	42	44	46	48	50	0.5
2	Hip (Bin from belt)	39	39	41	41	43	43	43	45	45	47	49	51	54	56	58	60	0.5
3	Thigh	26	26	27	27	28	28	28	29	29	30	31	32	34	35	36	37	0.5
4	Bottom Knee on 13" from crotch	21.5	21.5	22	22	22.5	22.5	22.5	23	23	23.5	24	24	24	25	26	26	0.25
5	Bottom	17.75	17.75	18	18	18.25	18.25	18.25	18.5	18.5	18.75	19	19	19	19	19	19	0.25
6	Inseam	33	33	33	33	33	33	33	33	33	33	33	33	33	33	33	33	1
7	Front rise include	11.25	11.5	11.75	11.75	12	12	12.25	12.25	12.5	12.75	13	13.25	13.25	13.5	13.75	14	0.25
8	Back rise	16.25	16.5	16.75	16.75	17	17	17.25	17.25	17.5	17.75	18	18.25	18.25	18.5	18.75	19	0.25
9	Front patch length	11	11	11	11	11	11	11	11	11	11	11	11	11	11	11	11	0.25
10	Front pocket opening waist	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	2.25	0.25
11	Front pocket side seam	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	7	0.25
12	Thigh pocket length	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	8.5	9	9	9	9	9	9	9	0.25
13	Thigh pocket width	8	8	8	8	8	8	8	8	8	8.5	8.5	8.5	8.5	8.5	8.5	8.5	0.25
14	Thigh pocket flap height	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	2.75	0.125
15	Back pocket flap width	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	0.25
16	Back pocket flap height	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	2.5	0.125
17	Back pocket inside length	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	6.25	0.25
18	Waist belt	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	0.125
19	Thigh pocket placement	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	10.5	0.25
20	Belt loop length	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	4.75	0.25
21	Belt loop width bottom	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	0.125
22	Belt loop width top	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.875	0.125
23	Fly width	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	1.75	0.125
24	Fly length full	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.25	7.75	7.75	7.75	7.75	7.75	7.75	7.75	0.25

APPENDIX II TO ANNEX B TO
PN SPECIFICATION NO 01/2018
PROMULGATION DATE 26 Mar 2018



FRONT VIEW

BACK VIEW

1220

NOTE: METRIC DIMENSIONS SHOWN IN PARENTHESIS

DITD KARACHI

TITLE: SHIRT CAMOUFLAGE

(MAIN BODY) SIZE- MF-40

DATE: 10-24/12/2017 DIMENSIONS: INCHES

SCALE: N.T.S

CHECKED BY: APPROVED BY:




---SD--- --SD--

LT.CDR M. USGHAR

CDR ALI HAN MIB

ITEM	DESCRIPTION	QTY	UNIT
24	FRONT POCKET HIGH	1	INCH
25	FRONT POCKET WIDTH LEFT SIDE	1	INCH
26	FRONT POCKET WIDTH RIGHT SIDE	1	INCH
27	FRONT POCKET PLACEMENT	2	INCH
28	FRONT POCKET SLEEVE BOX	1	INCH
29	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
30	FRONT FLAP HEIGHT	2.5	INCH
31	FRONT FLAP WIDTH	5.5	INCH
32	SLEEVE LOOP WIDTH	2	INCH
33	SLEEVE LOOP LENGTH	5.75	INCH
34	CUFF HEIGHT	2	INCH
35	LOW VELOCEZ CLAS	1	INCH
36	FRONT POCKET WIDTH	1	INCH
37	FRONT POCKET LENGTH	1	INCH
38	FRONT POCKET PLACEMENT	1	INCH
39	FRONT POCKET SLEEVE BOX	1	INCH
40	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
41	FRONT FLAP HEIGHT	2.5	INCH
42	FRONT FLAP WIDTH	5.5	INCH
43	SLEEVE LOOP WIDTH	2	INCH
44	SLEEVE LOOP LENGTH	5.75	INCH
45	CUFF HEIGHT	2	INCH
46	LOW VELOCEZ CLAS	1	INCH
47	FRONT POCKET WIDTH	1	INCH
48	FRONT POCKET LENGTH	1	INCH
49	FRONT POCKET PLACEMENT	1	INCH
50	FRONT POCKET SLEEVE BOX	1	INCH
51	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
52	FRONT FLAP HEIGHT	2.5	INCH
53	FRONT FLAP WIDTH	5.5	INCH
54	SLEEVE LOOP WIDTH	2	INCH
55	SLEEVE LOOP LENGTH	5.75	INCH
56	CUFF HEIGHT	2	INCH
57	LOW VELOCEZ CLAS	1	INCH
58	FRONT POCKET WIDTH	1	INCH
59	FRONT POCKET LENGTH	1	INCH
60	FRONT POCKET PLACEMENT	1	INCH
61	FRONT POCKET SLEEVE BOX	1	INCH
62	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
63	FRONT FLAP HEIGHT	2.5	INCH
64	FRONT FLAP WIDTH	5.5	INCH
65	SLEEVE LOOP WIDTH	2	INCH
66	SLEEVE LOOP LENGTH	5.75	INCH
67	CUFF HEIGHT	2	INCH
68	LOW VELOCEZ CLAS	1	INCH
69	FRONT POCKET WIDTH	1	INCH
70	FRONT POCKET LENGTH	1	INCH
71	FRONT POCKET PLACEMENT	1	INCH
72	FRONT POCKET SLEEVE BOX	1	INCH
73	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
74	FRONT FLAP HEIGHT	2.5	INCH
75	FRONT FLAP WIDTH	5.5	INCH
76	SLEEVE LOOP WIDTH	2	INCH
77	SLEEVE LOOP LENGTH	5.75	INCH
78	CUFF HEIGHT	2	INCH
79	LOW VELOCEZ CLAS	1	INCH
80	FRONT POCKET WIDTH	1	INCH
81	FRONT POCKET LENGTH	1	INCH
82	FRONT POCKET PLACEMENT	1	INCH
83	FRONT POCKET SLEEVE BOX	1	INCH
84	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
85	FRONT FLAP HEIGHT	2.5	INCH
86	FRONT FLAP WIDTH	5.5	INCH
87	SLEEVE LOOP WIDTH	2	INCH
88	SLEEVE LOOP LENGTH	5.75	INCH
89	CUFF HEIGHT	2	INCH
90	LOW VELOCEZ CLAS	1	INCH
91	FRONT POCKET WIDTH	1	INCH
92	FRONT POCKET LENGTH	1	INCH
93	FRONT POCKET PLACEMENT	1	INCH
94	FRONT POCKET SLEEVE BOX	1	INCH
95	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
96	FRONT FLAP HEIGHT	2.5	INCH
97	FRONT FLAP WIDTH	5.5	INCH
98	SLEEVE LOOP WIDTH	2	INCH
99	SLEEVE LOOP LENGTH	5.75	INCH
100	CUFF HEIGHT	2	INCH
101	LOW VELOCEZ CLAS	1	INCH
102	FRONT POCKET WIDTH	1	INCH
103	FRONT POCKET LENGTH	1	INCH
104	FRONT POCKET PLACEMENT	1	INCH
105	FRONT POCKET SLEEVE BOX	1	INCH
106	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
107	FRONT FLAP HEIGHT	2.5	INCH
108	FRONT FLAP WIDTH	5.5	INCH
109	SLEEVE LOOP WIDTH	2	INCH
110	SLEEVE LOOP LENGTH	5.75	INCH
111	CUFF HEIGHT	2	INCH
112	LOW VELOCEZ CLAS	1	INCH
113	FRONT POCKET WIDTH	1	INCH
114	FRONT POCKET LENGTH	1	INCH
115	FRONT POCKET PLACEMENT	1	INCH
116	FRONT POCKET SLEEVE BOX	1	INCH
117	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
118	FRONT FLAP HEIGHT	2.5	INCH
119	FRONT FLAP WIDTH	5.5	INCH
120	SLEEVE LOOP WIDTH	2	INCH
121	SLEEVE LOOP LENGTH	5.75	INCH
122	CUFF HEIGHT	2	INCH
123	LOW VELOCEZ CLAS	1	INCH
124	FRONT POCKET WIDTH	1	INCH
125	FRONT POCKET LENGTH	1	INCH
126	FRONT POCKET PLACEMENT	1	INCH
127	FRONT POCKET SLEEVE BOX	1	INCH
128	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
129	FRONT FLAP HEIGHT	2.5	INCH
130	FRONT FLAP WIDTH	5.5	INCH
131	SLEEVE LOOP WIDTH	2	INCH
132	SLEEVE LOOP LENGTH	5.75	INCH
133	CUFF HEIGHT	2	INCH
134	LOW VELOCEZ CLAS	1	INCH
135	FRONT POCKET WIDTH	1	INCH
136	FRONT POCKET LENGTH	1	INCH
137	FRONT POCKET PLACEMENT	1	INCH
138	FRONT POCKET SLEEVE BOX	1	INCH
139	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
140	FRONT FLAP HEIGHT	2.5	INCH
141	FRONT FLAP WIDTH	5.5	INCH
142	SLEEVE LOOP WIDTH	2	INCH
143	SLEEVE LOOP LENGTH	5.75	INCH
144	CUFF HEIGHT	2	INCH
145	LOW VELOCEZ CLAS	1	INCH
146	FRONT POCKET WIDTH	1	INCH
147	FRONT POCKET LENGTH	1	INCH
148	FRONT POCKET PLACEMENT	1	INCH
149	FRONT POCKET SLEEVE BOX	1	INCH
150	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
151	FRONT FLAP HEIGHT	2.5	INCH
152	FRONT FLAP WIDTH	5.5	INCH
153	SLEEVE LOOP WIDTH	2	INCH
154	SLEEVE LOOP LENGTH	5.75	INCH
155	CUFF HEIGHT	2	INCH
156	LOW VELOCEZ CLAS	1	INCH
157	FRONT POCKET WIDTH	1	INCH
158	FRONT POCKET LENGTH	1	INCH
159	FRONT POCKET PLACEMENT	1	INCH
160	FRONT POCKET SLEEVE BOX	1	INCH
161	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
162	FRONT FLAP HEIGHT	2.5	INCH
163	FRONT FLAP WIDTH	5.5	INCH
164	SLEEVE LOOP WIDTH	2	INCH
165	SLEEVE LOOP LENGTH	5.75	INCH
166	CUFF HEIGHT	2	INCH
167	LOW VELOCEZ CLAS	1	INCH
168	FRONT POCKET WIDTH	1	INCH
169	FRONT POCKET LENGTH	1	INCH
170	FRONT POCKET PLACEMENT	1	INCH
171	FRONT POCKET SLEEVE BOX	1	INCH
172	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
173	FRONT FLAP HEIGHT	2.5	INCH
174	FRONT FLAP WIDTH	5.5	INCH
175	SLEEVE LOOP WIDTH	2	INCH
176	SLEEVE LOOP LENGTH	5.75	INCH
177	CUFF HEIGHT	2	INCH
178	LOW VELOCEZ CLAS	1	INCH
179	FRONT POCKET WIDTH	1	INCH
180	FRONT POCKET LENGTH	1	INCH
181	FRONT POCKET PLACEMENT	1	INCH
182	FRONT POCKET SLEEVE BOX	1	INCH
183	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
184	FRONT FLAP HEIGHT	2.5	INCH
185	FRONT FLAP WIDTH	5.5	INCH
186	SLEEVE LOOP WIDTH	2	INCH
187	SLEEVE LOOP LENGTH	5.75	INCH
188	CUFF HEIGHT	2	INCH
189	LOW VELOCEZ CLAS	1	INCH
190	FRONT POCKET WIDTH	1	INCH
191	FRONT POCKET LENGTH	1	INCH
192	FRONT POCKET PLACEMENT	1	INCH
193	FRONT POCKET SLEEVE BOX	1	INCH
194	FRONT POCKET LENGTH (INCLUDING FLAP)	0.1	INCH
195	FRONT FLAP HEIGHT	2.5	INCH
196	FRONT FLAP WIDTH	5.5	INCH
197	SLEEVE LOOP WIDTH	2	INCH
198	SLEEVE LOOP LENGTH	5.75	INCH
199	CUFF HEIGHT	2	INCH
200	LOW VELOCEZ CLAS	1	INCH



DESCRIPTION



1221

NOTE:
FOR FURTHER DETAILS SEE SEALED SAMPLE.

DITD KARACHI		
TITLE: SHIRT CAMOUFLAGE		
(SMALL PARTS) SIZE: MF-40		
DWG. NO.	TD-2413/2017	DIMENSIONS: INCHES
DATE:	19-12-2017	SCALE: N.T.S
DRAWN BY	CHECKED BY	APPROVED BY
--SD--	--SD--	--SD--
H.D/M MLASGHAR I/c DWG.	LT.CDR ASMA SOHAIL SO, RAD	CDR AZHAR MIR DITD



1222

			14	THIGH POCKET FLAP HEIGHT	2.75
			13	THIGH POCKET WIDTH	6
			12	THIGH POCKET LENGTH	8.5
25	BOTTOM ADJUSTMENT ROPE	2/0	11	FRONT POCKET SIDE SEAM	7
24	FLY LENGTH FULL	7.25	10	FRONT POCKET OPENING WIDTH	2.25
23	FLY WIDTH	8.75	9	FRONT PATCH LENGTH	11
22	BELT LOOP WIDTH TOP	2	8	BACK RISE	17
21	BELT LOOP WIDTH BOTTOM	2	7	FRONT SIDE PULLER	12
20	BELT LOOP LENGTH	4.75	6	INSEAM	31
19	THIGH POCKET PLACEMENT	80.5	5	BOTTOM	18.25
18	WAIST BELT	8.75	4	HEEL ON CUFF FROM CROUCH	22.5
17	SAFETY PATCH 20000 LENGTH	6.25	3	THIGH	28
16	BACK POCKET FLAP HEIGHT	2.5	2	HIPS FROM BELT	43
15	BACK POCKET FLAP WIDTH	6	1	WAIST	34
S.NO	ITEM	INC	S.NO	ITEM	INC
DESCRIPTION					

DITD KARACHI

TITLE:
TROUSER CAMOUFLAGE
SIZE: MF-34

DWG.NO. TD-2414/2017 DIMENSIONS: INCHES

DATE: 19-12-2017 SCALE: N.T.S

DRAWN BY CHECKED BY APPROVED BY

--SD--

--SD--

--SD--


H.D./M
M.ASGHAR
I/c DWG

LT.COR
ASMA SOHAIL
SO.R&D


CDR
AZHAR MIR
DITD

NOTE:


FOR FURTHER DETAILS SEE SEALED SAMPLE.




FRONT POCKET




THIGH POCKET




KNEE PATCH



BACK POCKET



HIP PATCH




BELT LOOP



LENGTH EQUALS TO WAIST EXCEEDING 12"

WAIST ADJUSTMENT TAPE

1223



BUTTON
SCALE: 1:2



FLY

NOTE:
FOR FURTHER DETAILS SEE SEALED SAMPLE.

DITD KARACHI		
TITLE: TROUSER CAMOUFLAGE (SMALL PARTS) SIZE: MF-34		
DWG.NO. TD-2415/2017	DIMENSIONS: INCHES	
DATE: 19-12-2017	SCALE: N.T.S	
DRAWN BY --SD--	CHECKED BY --SD--	APPROVED BY --SD--
H.D/M M.ASGHAR 1/c DWG	LT.CDR ASMA SOHAIL SO.R&D	CDR AZHAR MIR DITD

TECH. DETAILS OF 'PAK NAVY' SOFT TALLY FOR CAMOUFLAGE DRESS NO 4B

S NO	MAIN FABRIC	REQUIREMENT
BASE FABRIC MATERIAL SPECIFICATION		
1.	Material	As per Annex A of this specification
2.	Colour	Light grey or Pantone 15-4003 TCX
EMBROIDERY THREAD MATERIAL SPECIFICATION		
1.	Material	100% Viscose
2.	Color	Black Pantone # 19-4006 TCX
3.	Count of yarn	2/36
EMBROIDERY THREAD PERFORMANCE TESTING		
1.	Color fastness to washing (Test No. 3) a. Change in Shade b. Staining	GS: 4 GS: 4
VELCRO TAPE MATERIAL SPECIFICATION		
1.	Material Male Female	Nylon Nylon
2.	Colour	Light grey or Pantone 15-4003 TCX
VELCRO TAPE PERFORMANCE TESTING		
1.	Manual Sticking/ Unsticking	a. Satisfactory after sticking and un-sticking 300 times. b. Satisfactory after sticking ad un-sticking 300 times on applying weight of 300g.
2.	Peel Strength (lbs per in width)	1.5
3.	Shear strength(PSI)	10

ANNEX D TO
PN SPECIFICATION NO 01/2018
PROMULGATION DATE 26 Mar 2018


MANUFACTURING DETAILS OF 'PAK NAVY' SOFT TALLY

1. PAK NAVY Soft Tally shall be fabricated in accordance with the shape and design as illustrated in the drawing at Appendix I of this Annex.
2. The thickness of embroidery shall be 3mm.
3. The embroidery shall be neat and clean and all loose ends shall be trimmed off. The embroidery shall be parallel to the centre line of the tally.


Appendix:

- I DRAWING OF 'PAK NAVY' SOFT TALLY.

APPENDIX I TO ANNEX D TO
 PN SPECIFICATION NO 01/2018
 PROMULGATION DATE 26 Mar 2018



FRONT VIEW



BACK VIEW

1235

DITD KARACHI		
TITLE: SOFT PAK NAVY TALLY FOR CAMOUFLAGE DRESSES		
DWG.NO. TD-2428/2018	DIMENSIONS: INCHES	
DATE: 21-03-2018	SCALE: N.T.S	
DRAWN BY	CHECKED BY	APPROVED BY
--SD--	--SD--	--SD--
H.D/M M.ASGHAR I/c DWG	LT.CDR ASMA SOHAIL SO, R&D	CDR AZHAR MIR DITD

NOTE:
 FOR FURTHER DETAILS SEE STOCK SAMPLE

ANNEX E TO
PN SPECIFICATION NO 01/2018
PROMULGATION DATE 26 Mar 2018

TECHNICAL DETAILS FOR CAMOUFLAGE JOCKEY / SEA CAP

S NO	ITEM	REQUIREMENT
BASE FABRIC MATERIAL SPECIFICATION		
1.	Material specification	As per Annex A of this specification
STITCHING THREAD MATERIAL SPECIFICATION		
1.	Material	Polyester
2.	Color	Light grey or Pantone # 15-4003 TCX
3.	Count of yarn	26/3 3/22.7 Tex \pm 3%
4.	Construction	3 cord each single
STITCHING THREAD PERFORMANCE TESTING		
1.	Color fastness to washing (Test No. 3) a. Change in Shade b. Staining	GS: 4 GS: 4
2.	Strength, cN	2680
3.	Tenacity, cN/Tex	39.24
4.	Elongation %	18.53
PLASTIC PEAK MATERIAL SPECIFICATION		
1.	Material	Plastic (virgin)
2.	Thickness	1.5 -1.7 mm
3.	Hardness	97 \pm 1 IRHD
4.	Density	0.92 g/cc \pm 0.01
CARE LABEL MATERIAL SPECIFICATION		
1.	Material	Polyester with visible printing which remain satisfactory after washing test.
2.	Shade	Nearest to ground fabric color i.e. light grey
EMBROIDERY THREAD MATERIAL SPECIFICATION		
1.	Colour	Black Pantone# 19-4006 TCX
2.	Material	Viscose
3.	Count of yarn	2/44 \pm 2
EMBROIDERY THREAD PERFORMANCE TESTING		
1.	Colour fastness to washing Test No. 3 1. Change in Shade 2. Staining Cotton Wool	GS: 4 GS: 4 GS: 4

<u>VELCRO TAPE MATERIAL SPECIFICATION</u>		
1.	Material Male Female	Nylon Nylon
2.	Colour	Light Grey or Pantone # 15-4003 TCX
<u>VELCRO TAPE PERFORMANCE TESTING</u>		
1.	<u>Performance Test</u> 1. Before sticking / unsticking 300 times at 300 g. 2. After sticking / unsticking 300 times at 300g.	Satisfactory Satisfactory
2.	Peel Strength (lbs per in width)	1.5
3.	Shear strength(PSI)	10

MANUFACTURING DETAILS OF CAMOUFLAGE JOCKEY / SEA CAP

- 1 Camouflage Jockey / Sea Cap shall be fabricated in accordance with the shape and design as illustrated in the drawing at Annex C.
- 2 It is a 6 panel style Jockey Cap. The panels are stitched with each other using double needle stitch neatly using 10-12 SPI.
- 3 Piping used on inner side of Cap is 10mm wide of same fabric used in upper of cap.
- 4 Velcro tape used for adjustment of cap shall be 2.5 cm of best trade quality. The color of Velcro and embroidery on eyelets shall be light grey and matches with the base color of fabric.
- 5 The dia of top Button is 16mm and it is covered with same fabric used in upper of cap.
- 6 Sweat absorbing band and inner side of peak shall be of same upper fabric.
- 7 Care label and identification label may be attached with the sweat absorbing band.

Appendices:

- I MEASUREMENT SCHEDULE OF CAMOUFLAGE JOCKEY / SEA CAP.
- II DRAWING OF CAMOUFLAGE JOCKEY / SEA CAP.


MEASUREMENTS AND DIMENSIONS


S.No.	DESCRIPTIONS	SIZE CM				TOLERANCE
		55	57	59	61	
	Internal circumference	55	57	59	61	+0.5
a.	Peak width from center	7.5	7.5	7.5	7.5	+0.2
b.	Peak width from edges	13	13	13	13	+0.2
c.	Peak Length from bottom edges	16	16	16	16	+0.2
d.	Peak Length from top edges	18	18	18	18	+0.2
e.	Height of Cap	12	12	12	12	+0.5

Note:

The tolerances are given only for made up caps to cover the stitching allowance. Manufacturer will ensure exact size.

PN SPECIFICATION NO 01/2018
 APPENDIX II TO ANNEX F TO
 PN SPECIFICATION NO 01/2018
 PROMULGATION DATE 26 Mar 2018





1181

DITD KARACHI		
TITLE: JOCKEY SEA CAP		
CPO's & SAILORS (DRESS NO-48)		
DWG. NO. TD-2282/2017	DIMENSIONS: mm	
DATE: 11-04-2017	SCALE: NTS	
DRAWN BY	CHECKED BY	APPROVED BY
-SD-	-SD-	-SD-
ADMAN NISAR D/WAN	LT ASMA SOHAD SO. RSD	CAPTAIN GAZ AHMED (C/O)

NOTE:
FOR FURTHER DETAILS SEE SPECY SAMPLE

TERMS & DEFINITIONS

1. **Inspection Authority**. Chief Inspector of Naval Stores (CINS). His verdict in respect of inspection matters is to be taken as final.
2. **Inspecting Officer**. An officer nominated by the Chief Inspector of Naval Stores (CINS) for carrying out inspection of stores supplied by the supplier, against a specified contract or order, in accordance with the particulars stipulated therein.
3. **Inspector**. The term inspector shall include the "Inspection Authority", inspecting officer and their representatives, duly authorized for the purpose of discharging inspection duties involved.
4. **Sealed Pattern**. It denotes a pattern, sealed and signed by the Inspection Authority & held in his custody, and represents the standard of store in respect of materials, dimensions, design, workmanship and finish, etc. There is only one sealed pattern for each store, which cannot be removed from custody of the inspection authority.

GUIDELINES FOR INSPECTION – GENERAL DEFECTS

Defect	
1.	<u>Material Defect and Workmanship Damages</u> a. Any hole, scissor or knife tear, mend, burn or weakening defect, such as smash, multiple float, loose slub, or needle chews, that might develop in to hole. b. Cloth stiffened, hardened, or seared by heat, where thermo activated shade. c. Any garment portion puckered, twisted, or pleated at joining seam.
2.	<u>Shaded Parts</u> a. Any part shaded or any shade bar.
3.	<u>Colour</u> a. Any component of not specified colour.
4.	<u>Cleanliness</u> a. Any slub, spot, or stain on outer side. b. Threads ends not trimmed or loose threads ends not removed (to be scored only when condition exists on major portion of garment). c. Any shade identification stamping visible on outer side.
5.	<u>Component and Assembly</u> a. Any component not as specified or any defect of component or defect of assembly not herein classified. b. Any component, component part, or required operation omitted or any other operation improperly performed not herein specified/ classified.
6.	<u>Seams and Stitching</u> a. Any seam twisted, puckered, or pleated (unless otherwise classified herein) b. Any part of Jacket and Trouser caught in unrelated operation or stitching.

- c. Any edge not properly forced out, i.e, having fold more than specified.
- d. Ends of stitching that are not caught in other seam or stitching not securely tacked.
- e. Ends of seams or stitches that are not caught in other seams or stitching secured but backstitched for distance less than specified.
- f. Thread breaks not securely overstitched
- g. Stitching tension tight resulting in breakage of stitches when normal pull is applied.
- h. Stitching per 20 mm on major portion of seam one or two stitches more or less than specified, except on labels.
- j. Stitches per 20 mm on major portion of seam more than three stitches more or less than specified, except on labels.
- k. Any bar tacks omitted, loose, misplaced or not serving intended purpose.
- l. Three or more bar tacks missing, loose, misplaced, or not serving intended purpose on multiple pencil compartment pockets.
- m. Skipped or broken stitches in two or more sewn eyelets
- n. Stitch tension loose resulting in loose seam.
- p. Stitches in sewn eyelet one or two stitches less than specified.

<u>GENERAL REQUIREMENTS/CONDITIONS</u>		<u>ANNEX 'B' TO</u> Indent No 525041 Indent Date. 2025-11-07 00:00:
<u>S.No and Description</u>	<u>Firm's Reply</u> <u>(Complied)/</u> <u>Partially Complied/</u> <u>Not Complied</u>	<u>Reference to</u> <u>attached Firm's</u> <u>proposal/ Brochure</u>
<p>1. SCOPE OF SUPPLY/ WORK</p> <p>The Supplier undertakes to deliver equipment/goods/stores including Supplies and Services to the Purchaser on FOR/ FOB Karachi basis as per INCOTERMS 2020 as per details specified in Annex-A (Technical Specifications) and General Terms and Conditions given at Annex-B to this Indent.</p> <p>The Supplier shall, in accordance with the terms and conditions as set forth in the Indent, with due care and diligence, provide the equipment/goods/stores and supply the Services within the date(s) specified in the Project Time Schedule.</p>		
<p>2. PERFORMANCE BANK GUARANTEE (PBG)</p> <p>To ensure timely and correct supply of stores, the Supplier shall furnish an unconditional and irrevocable PBG within 30 days of contract signing from a scheduled Pakistani Bank for an amount equivalent to 10% of the contract value (on a Judicial Stamp Paper of the value of Rs.100.00), in the same currency as that of the Contract and endorsed in the favour of CMA(DP) Rawalpindi. The CMA(DP), Rawalpindi has the like power of seeking encashment of the PBG as if the same has been demanded by the Purchaser himself. This PBG shall remain valid for 60 days beyond the completion of warranty period.</p> <p>If the Supplier fails to issue the Bank Guarantee within the specified period because of circumstances that the Supplier is responsible for, the Purchaser reserves the right of cancelling the Contract.</p> <p>In the event of any material breach of terms of Contract having implication on Time schedule and Scope of Work beyond the acceptable limits defined in this Contract, the Supplier shall be given a written notification to satisfy the breach within 30 days and if the Supplier fails to take satisfactory remedial actions, Purchaser shall have the right to forfeit the PBG but only to the extent of Purchaser's loss or damage resulting from such material breach. For this purpose, the Supplier undertakes not to hinder/restrain encashment of PBG provided to the Purchaser on account of this contract through any Court, extra judicial or any other process including administrative in nature whatsoever.</p>		
<p>3. PRICES OF THE ITEMS</p> <p>The Supplier should mention the price of all deliverables (i.e. Equipment/ Services, Spares, Documentation, Test Bench/ Tools/ Test Equipment, Trainings, FATs (Factory Acceptance Trials), Installation/ Integration, Acceptance Test/ Trials/ Commissioning etc where applicable) separately in financial quote. The same are to be</p>		

subsequently incorporated in the contract document.		
<p>4. TRANSFER OF TITLE AND RISK</p> <p>Risk of loss and damage to the Equipment shall be transferred to the PURCHASER according to the „INCOTERM 2020 used in the Contract and stated in Article 1.</p> <p>Title to the Equipment shall be transferred to the Purchaser when the Supplier has received full payment of the Contract Price.</p>		
<p>5. WARRANTY/ GUARANTEE</p> <p>a. Warranty period of all items except defective/non-operational shall commence from the date of acceptance of Goods/ Equipment, whereas warranty of defective/non-operational equipment (at the time of commissioning/ acceptance) shall commence after defect rectification of equipment.</p> <p>b. The stores and all its associated accessories should be warranted against DPL-15 by the Supplier for a period of 01 year, for all defects in hardware from the date of final acceptance by PN. Software provided with the systems should also have warranty for a minimum period of 05 years for any bugs found in operations. The Supplier shall provide/incorporate all software updates in this period.</p> <p>c. The Supplier should provide guarantee that the article supplied are of latest version and all modifications/up gradation have been incorporated in the equipment being supplied.</p> <p>d. The Supplier should provide guarantee that the stores produced are of current production and brand new, in accordance with approved drawing, and in all respects. The materials used, whether or not of his manufacture should also be in accordance with the latest appropriate standard specifications.</p> <p>e. The Supplier shall provide guarantee for through life supportability of the equipment and software for at least 05 years after acceptance of the entire system.</p>		
<p>6. NON DISCLOSURE AGREEMENT</p> <p>Any information about the sale/ purchase/ services/ drawings/ infrastructure etc of the project under the contract shall not be communicated to any person, other than the manufacturer/ provider of the stores/ drawings/ machinery/ equipment/ tools etc or to any press or agency not authorized by the Purchaser to receive it. Any breach on this account shall be punished under the Official Secret Act 1923.</p> <p>Promotional rights for publication of the projects are the sole responsibility of the Purchaser, and any use by the consultant shall be subject, in all instances, to the Purchaser's prior written approval.</p>		
7. INSPECTION OF STORES/ ACCEPTANCE TEST		

<p>PROCEDURE</p> <p>The stores shall be accepted and inspected by following officers/ Reps:</p> <p>(1) Rep of CINS</p> <p>b. Above team shall inspect and test the goods to on Supplier their conformity to the contract specifications.</p> <p>c. The conditions of the contract and technical specifications shall specify inspections/ tests criteria as required by the Purchaser and place of conduct.</p> <p>d. Purchaser shall notify the Supplier in writing of the identity to any representatives entrusted for this purpose.</p> <p>e. If any inspected or tested goods fail to conform to the specifications, Purchaser may reject them and the Supplier shall either replace the rejected goods or make alterations necessary to meet specification requirements free of cost to Purchaser.</p> <p>f. Purchaser's right to inspect, test and where necessary, reject the goods after arrival in Pakistan shall in no way be limited or waived by reasons of the goods having previously been inspected, tested and passed by Purchaser or its representative prior to the goods shipment from the country of origin.</p>		
<p>8. DISCREPANCY</p> <p>The Supplier shall render a discrepancy report to all concerned within 30 days after receipt of stores for discrepancies found in the consignment. The quantities found short or defective are to be made by the Supplier, without any additional cost on "DDP "consignee's warehouse "within 30 days.</p>		
<p>9. COMPENSATION ON BREACH OF CONTRACT</p> <p>If the Supplier fails to supply of contracted stores or contract is cancelled either on RE or without RE or contract become ineffective due to default of Supplier/ Supplier or stores/ equipment declared defective and caused loss to the Government, Supplier shall be liable to pay to the Government compensation for loss or inconvenience resulting for his default or from the rescission of his contract when such default or rescission take place such compensation shall be in excess to the RE amount, if imposed by the competent authority. Compensation amount in terms of money shall be decided by the purchase officer and shall be deposited by Supplier/ Supplier in Government treasury in the currency of contract.</p>		
<p>10. PENALTY</p> <p>a. The Supplier before making the shipment shall carry out complete test of the equipment at its facilities to ensure that the same has been manufactured as per specifications.</p>		

<p>In case the equipment does not pass the test/ trials, Purchaser has the right to outright reject the equipment or impose penalty at the rate of 10 - 15% of the value of the relevant equipment/ items.</p> <p>b. The penalty shall not absolve the Supplier to undertake the repairs in Pakistan or abroad at his cost and expense including freight charges. This shall be in addition to the penalties and obligations covered in the contract like warranty/ guarantee obligations on Form DPL-15.</p>		
<p>11. CONTRACT COMPLETION CERTIFICATES</p> <p>Upon completion of all contractual obligations under this Contract, the Supplier shall submit a "No Demand Certificate" to the Purchaser stating that no stores/ goods, Supplies, Services and payments are outstanding. Concurrently, the Purchaser shall certify through a "No Objection Certificate" that the requirement placed by the Purchaser as per terms and conditions set forth in this Contract has been fulfilled. Specimen of Contract Completion Certificate/ No Demand Certificate shall be added in the contract prior contract signing. Upon receipt of both certificates, Bank Guarantee(s) shall be returned by CMA(DP) to the Purchaser for onward return to the Supplier.</p>		
<p>12. COMPLIANCE WITH INTERNATIONAL STANDARDS</p> <p>The Goods/Equipment shall comply with all relevant ISO standards stipulated in the Contract and valid on the date of signature of the Contract. The Parties agree that any variation of any ISO standard after signature of the Contract is deemed explicitly not to be a circumstance within the responsibility of the Supplier. Implementation of any variations to the relevant ISO standards for the purpose of operating the Equipment shall be agreed between the Parties within the contractual change management procedure, prior to realization.</p>		
<p>13. TECHNICAL SCRUTINY</p> <p>Technical scrutiny of quotations forwarded by the bidder shall be carried out by a committee nominated by CO PNCSD as per instructions of NHQs. The TSR committee may ask the Suppliers to demonstrate their equipment or give a presentation for clarification. TSR committee may also visit the OEM premises at the invitation/expense of the Supplier to evaluate the manufacturing/system's capabilities of the OEM.</p>		
<p>14. DELAYS AND LIQUIDATED DAMAGES (LDs)</p> <p>Following Liquidated Damages shall apply for late completion of Consultancy Services as given in the Contract:</p> <p>a. Delay in the completion of all contracted stores/ deliverables up to Twenty One (21) days and for subsequent schedule/orders up to 15 days (from the original Delivery Period only) shall be regarded as "grace period" and no extension/ amendment shall be</p>		

<p>required. When LD is imposed, grace period shall be inclusive.</p> <p>b. For delays beyond the Grace period of Twenty One (21) days culpably caused by consultant, Purchaser shall have the right to impose LDs.</p> <p>LD, if imposed shall be recovered at the rate of up to 2% but not less than 1% (depending upon the merit of the case as decided by Competent Purchase Officer) of the value of stores supplied late per month or a part of a month for the period exceeding the original delivery period are liable to be imposed on the Supplier by the Purchaser in accordance with DPP&I-35 (Revised 2019), if the stores/ services supplied after the expiry of the delivery date without any valid reasons, subject to provision that the total LD thus imposed shall not exceed 10% of the total value excluding taxes/ duties, freight, KPT, insurance charges of the stores delivered late.</p>		
<p>15. BIDDING PROCEDURE</p> <p>This tender shall be floated on Open Tender using Single Stage Two Envelope Bidding procedure.</p>		
<p>16. LANGUAGE, MEASUREMENTS AND WORKING METHODS</p> <p>All drawings, data-files in soft media, Man-Machinery Interface (MIMI) of software and hardware, all marking and identification systems and all other documentation required to be produced or delivered to the Purchaser under the Contract shall be written, and meetings conducted, in the English language. Measurements shall be in metric units of measurement unless otherwise specified.</p>		
<p>17. INTEGRITY PACT</p> <p>Integrity Pact duly signed by the Supplier and Purchaser. The principal/Supplier must strictly adhere to the provisions of this pact and any contravention in this regard would be dealt with severely, which may include (but not limited to) Permanent blacklisting of the principal / Supplier and/or initiation of criminal proceedings against the persons / individuals involved in a court of law.</p>		
<p>18. AMENDMENT IN CONTRACT</p> <p>Amendment in the contract if required shall be processed by Purchaser upon mutual agreement of both parties i.e. Purchaser and Supplier and formally issued through amendment in the contract/corrigendum.</p>		
<p>19. FORCE MAJEURE</p> <p>The Supplier shall not be held responsible for any delay occurring in delivery of the Goods, Supplies and Services due to event of Force Majeure, such as acts of God, war, terrorist activities, floods, earthquakes, tsunamis and other such events like, Pandemics, Lock down, acts of Governments or any other authority competent in relation to any action in connection with this Contract (including delay,</p>		

refusal, denial, revocation or any other decision regarding any Export License/permit), riots, civil commotion, acts of foreign government and its agencies and disturbance directly affecting the deliveries, and events or circumstances, including, but not limited to, any action and/or inaction by or on the part of any other person or entity, on or over which the Supplier has no control. In such an event the Supplier shall inform the Purchaser within 15 (fifteen) days of the happening and within the same timeframe about the discontinuation of such circumstances/ happening in writing.

The Party initiating the Force Majeure shall provide the other Party with reasonable proof of the occurrence of any of the aforementioned aspects along with Force Majeure event and of its effects on the delivery of the Supplies or any of its obligations towards this Contract.

Once the Party initiating the Force Majeure has provided the reasonable proof of occurrence of Force Majeure event, it shall be verified by the other Party and acknowledged to be realistic. In such case the Force Majeure shall be considered to have occurred.

If the delivery of Goods, Supplies and Services to the Purchaser has been delayed by Force Majeure conditions then additional period to the extent of such delay shall be allowed to the Supplier for completion of his obligations so affected without any increase in Contract Price.

If Force Majeure is considered present for a continuous period of more than 06 (six) months or exceeding a cumulative period of 12 (twelve) months, then both Parties shall mutually decide future course of action.

20. TERMINATION OF CONTRACT

If at any time during the currency of the contract the Purchaser decides to terminate the contract for any reason whatsoever (other than for reasons of Non- Delivery) he shall have right to do so by giving the Supplier a registered notice to that effect. In that event the Purchaser shall accept delivery at the contract price and terms of such stores/goods/services which are in the actual process of manufacture that is completed and ready for delivery within thirty days after receipt by the Supplier of such notice.

In the case of remainder of the undelivered stores/goods/services the Purchaser may elect either:

- a. To have any part thereof completed and take the delivery thereof at the contract price or to cancel the remaining quantity and pay to the Supplier for the articles or sub-components or raw materials purchased by the Supplier and are in the actual process of manufacture at the price to be determined by the Purchaser. In such a case materials in the process of manufacture shall be delivered by the Supplier to the Purchaser.

<p>b. No payment shall however be made for any materials not yet in the actual process of manufacture on the date notice of cancellation is received.</p> <p>c. Should the Supplier fail to deliver goods/services in time as per quality terms of contract or fail to render Bank Guarantee within the stipulated time period or any breach of the contract the Purchaser reserves the right to terminate/cancel the contract fully or any part thereof at the risk and expense (RE) of the Supplier. If due to any reasons Purchaser fails to perform its obligations required and needed for the smooth conduct and management of the Contract, Supplier has a right to initiate legal proceedings.</p>		
<p>21. CONFIDENTIALITY</p> <p>The Supplier and the Purchaser shall keep confidential all information of the other party, whether designated as confidential or not, obtained under or in connection with the Contract and shall not divulge the same to any third party without the written consent of the other party. The provisions of this clause shall not apply to any information in the public domain otherwise than by breach of the Contract; or information obtained from a third party who is free to divulge the same.</p> <p>The Supplier and the Purchaser shall divulge confidential information only to those employees who are directly involved in the Contract or have use of equipment and/or software used in connection with the Contract and shall ensure that such employees are aware of and comply with these obligations as to confidentiality.</p> <p>The Supplier shall undertake that any information about the sale/ purchase of the stores under this contract shall not be communicated to any person, other than the manufacturer/ Supplier/company's lawyer(s), or to any press or agency not authorized by the Purchaser to receive it. Any breach on this account shall be punishable under the Official Secret Act-1923 in addition to termination of the Contract at the risk and expense of the Supplier.</p>		
<p>22. SECURE EXCHANGE OF CORRESPONDENCE</p> <p>All correspondence pertaining to contract between Supplier and PN shall be on secured media.</p>		
<p>23. ASSIGNMENT AND SUBCONTRACTING</p> <p>Neither Party shall assign any of its rights or obligations (in whole or in part) under the Contract without the prior written consent of the other Party, which shall not be unreasonably withheld.</p> <p>The Supplier shall not subcontract any part of the Contract without the written consent of the Purchaser, which shall not be unreasonably withheld.</p>		
<p>24. INTELLECTUAL PROPERTY RIGHTS</p> <p>Unless otherwise agreed in writing, all intellectual property</p>		

<p>rights arising out of this Contract shall vest in the Supplier. The Purchaser shall have a worldwide, non-exclusive, non-transferable, royalty- free license to use, and have used, that intellectual property for anypurpose.</p>		
<p>25. OWNERSHIP OF CONTRACT</p> <p>In the event of a change of ownership of Supplier, the Supplier shall ensure that the legal instrument or mode by which the change of ownership takes place shall have specified provisions to the effect that:</p> <p>a. Such change of ownership shall not in any way change, alter or modify the Terms and Conditions of this Contract, and</p> <p>b. The Supplier under new ownership shall continue to be bound by the Terms and Conditions of this Contract.</p>		
<p>26. INDEMNITY</p> <p>In the framework of the implementation of this project, both Parties shall waive off any claim against each other regarding every claim for indemnity for the losses caused to their respective personnel or respective personnel of sub-contractors/agents and their properties. However, if these losses result from deliberate fault or unmistakable error or gross negligence of Supplier or his sub-contractors/agents and/or the Purchaser, the Party involved shall bear alone the burden of the damage repairs.</p>		
<p>27. CERTIFICATION REQUIREMENT</p> <p>Supplier/OEM shall confirm through OEM certificate at the time of supply/delivery of the equipment at consignee that equipment being supplied is proven equipment.</p> <p>Supplier through certificate is to confirm that he shall provide import documents at the time of delivery of stores.</p> <p>Supplier certificate for conformance of 100% indent specifications, any deviation to be clearly indicated in the offer shall be provided at the time of delivery of stores.</p> <p>OEM's "Certificate of Conformity" originating from "Principle" who is neither the OEM nor the OEM's authorized dealer/agent/ stockiest shall not be acceptable.</p>		
<p>28. COURT OF JURISDICTION</p> <p>All disputes arising in connection with this contract shall be sorted out through mutual discussions. Unsettled issues may however be dealt with under the Laws of Pakistan. The Courts at Rawalpindi shall be the Courts of Jurisdiction for any dispute relating to this contract for adjudication.</p>		
<p>29. MISCELLANEOUS</p> <p>a. The Supplier should provide the copies of standard/ specifications referred to or used for the equipment and its accessories.</p> <p>b. Stores to be accepted on DPL-15 at consignees end.</p> <p>c. Supplier shall provide a conformance certificate that item supplied conforms to relevant international standards.</p> <p>d. The Supplier should mention the price of all deliverables separately in financial quote. The same are to be subsequently incorporated in the contract document.</p>		

<p>30. CHECKING OF SUPPLIES AT CONSIGNEE'S END</p> <p>Upon arrival, Supplies shall be checked at consignee's end in the presence of the Purchaser and Supplier's representatives. If for the reasons of economy, or any other reason, the Supplier decides not to nominate his representative for such checking; an advance written notice to this effect shall be given by the Supplier to the consignee prior to or immediately on shipment of stores. In such an event, the Supplier shall clearly undertake that the decision of consignee with regard to quantities and description of the consignment shall be taken, as final and any discrepancy found shall be accordingly made up by the Supplier. In all other cases, the consignee shall inform the Supplier about arrival of consignment immediately on receipt of stores through fax. If no response from the Supplier is received within four (04) working days from initiation of letter through fax, the consignee shall have the right to proceed with the checking without Supplier's representative. Consignee's report on checking of stores shall be binding on the Supplier in such cases.</p>		
<p>31. QUALITY STANDARDS</p> <p>The equipment and accessories are manufactured and assembled in accordance with international standards. The quality standards compliance certificate is to be submitted with the offer.</p>		
<p>32. REPEAT ORDER</p> <p>Supplier shall not increase the cost of stores if additional quantity of same item is purchased in next 12 months after commissioning of the equipment. He may however decrease the cost by considering lower market trend.</p>		
<p>33. RISK PURCHASE</p> <p>In the event of failure on the part of the supplier to comply with the contractual obligations, the contract is liable to be cancelled at the risk and expense of the supplier in accordance with DPP&I-35 (Revised 2019). The Purchaser shall be entitled to receive back all advance payments made by him along with any other compensation as mutually agreed to offset the Purchaser's risk of cost escalation of meeting same requirement from elsewhere.</p>		
<p>34. PROJECT MANAGEMENT REVIEW (PMR) MEETINGS</p> <p>The Supplier's key professionals, covering the various technical disciplines shall attend, actively participate and cooperate with the Purchaser's request for meetings without any additional cost, which shall include but not limited to the following meetings:</p> <ol style="list-style-type: none"> a. Design Review Meetings. b. Progress timeline/ payment bills meetings. c. Any other meetings held in relation to the project. 		
<p>35. TENDER SAMPLE</p> <p>Tender samples are to be provided as per clause 11(11.2) of PN Specifications under heading Tender Sample.</p>		

<p>Lab Testing Report w.r.t. PN Specification is required for TSR. If considered appropriate, tender samples will also be tested through renowned Lab. Lab testing charges are to be borne by the supplier and same has to be paid by the supplier prior finalization of TSR.</p>		
<p>36. WORKMANSHIP AND MATERIALS</p> <p>a. All work to be done shall be executed in the manner set out in the Contract. Where the manner of manufacture and execution is not set out in the Contract, the work shall be executed in a proper and workmanlike manner in accordance with recognized good practice. The Supplier shall submit for approval of the purchaser, his detailed method statement(s) for the execution of such items of work as may be desired by the Purchaser. Approval of such method statement(s) shall neither relieve the Supplier of his responsibilities under the Contract nor form any basis for claiming additional costs.</p> <p>b. The Supplier shall give the Purchaser full opportunity to examine, measure and test any work onboard/ Site which is about to be covered up or put out of view. The Supplier shall give due notice to the Purchaser whenever such work is ready for examination, measurement or testing. The Purchaser shall then, unless he notifies the Supplier that he considers it unnecessary, without unreasonable delay carry out the examination, measurement or testing.</p>		
<p>37. TERMS OF PAYMENT</p> <p>100% Contract value of the stores will be paid by the CMA(DP) Rawalpindi to the Suppliers. The amount will be claimed direct from CMA(DP) Rawalpindi on production of the following documents, under a covering letter, a copy of which shall be addressed to DP(NAVY).</p> <p>a. Bill Form (DP-5 in duplicate) to be completed according to inspection.</p> <p>b. Received copy of the Inspection Note/Delivery Receipt.</p> <p>c. Supplier delivery Challan duly received by the Consignee.</p> <p>d. Copy Registration Certificate of Sales Tax Department.</p> <p>e. Part payment/Part delivery is allowed.</p>		
<p>38. Special Instructions as Annex C</p> <p>(1). Inspection/Packing/Delivery terms</p> <p>a. CO PNCSD may order 15% of contracted</p>		

quantity against DPL-15 to meet urgent/critical requirement, under intimation to CINS. the firm is required to deliver/supplies within 45 days against receipt of such order. Liquidated damages (LD) upto 2% per month are liable to be imposed on the supplier in accordance with DP-35 for late delivery of stores without any valid reason.

b. CINS may draw random samples from the stores received by PNCSD against DPL-15 to ascertain quality. after detailed laboratory analysis, suitable price reduction (PR) as authorized may be applied by CINS for minor deviation/non- conformance from stated PN Specification. In case of major deviation/non- conformance, the stores may be rejected.

(2). Inclusion of Instructions Regarding Disposal of Rejected Uniforms.

a. Contracted firm will be responsible for proper disposal of rejected clothing stores. same are to be amended/destroyed under supervision of PN authorities to prevent their misuse by terrorists/ anti-social elements.

b. In case a supplier intends to sale rejected uniform items in local market, the procurement agency will be approached for approval of sample after suitable alteration of military appearance into civilian fashion after approval, CINS will inspect the bulk stores once again clear the lot for disposal in local market.

c. The contractor/ supplier shall submit a certificate / undertaking on firm's letter pad that the firm will be held responsible for any misuse of rejected uniforms.

(3). In case firm is unable to get approval of advance sample within 6 months from date of contract, then contract cancellation should be recommended by CINS or CSD.

(4). Marking of stores in accordance with specification NS/MISC/002/80.

(5). Firm will give two week clear notice for the inspection.

(6). Free delivery to consignee warehouses.

(7). As per NHQs instructions promulgated vide NHQ letter ST- P/9314/INS/04 dated 05 April 2006. rejection of stores supplied by contractors will be dealt as under:

- a. 1st rejection on Govt expense.
- b. 2nd rejection on supplier's expense
- c. On 3rd rejection, contract cancellation will be recommended by CINS or CSD.

(8). Tracking Identification:
Stitching of PN uniforms for given sizes as per Unique Garments tracking technological coding system.

<p>(9). The purchaser will have the flexibility to extend contract up to 03 months and also can order 15% excess of the total contracted quantity, from the supplying firm at the contract price</p> <p>(10). Purchaser is not bound to lift the entire quantity of contract.</p> <p>(11). Barcode sticker to be attached on each plastic packet containing Dress No. 4 100% Cotton, containing Combat Shoes Camel Color.</p> <p>(12). <u>Packing</u>: Packing as per PN Specification 01/2018.</p> <p>(13). Care Label:</p> <ol style="list-style-type: none"> a. Washing Instructions b. Drying Instructions c. Ironing Instructions d. Any prohibitions 		
<p>39. LIABILITY</p> <p>The supplier shall not be liable under any circumstances to the buyer, its officers, agent, employees, successors and / or assignees, for any special, consequential and / or incidental damage of whatsoever kind or nature, including, without limitation, any loss, cost, damage loss of revenue or profit or loss of user, incurred or suffered by the buyer or any third party arising out of or in connection with this contract. The foregoing shall not affect buyers right to claim compensation against the supplier for damages suffered by the buyer arising directly from the performance, bad performance or non-performance of the suppliers duties and / or obligations under the contract provided however that the aggregate liability of the suppliers in connection with this contract for any cause whatsoever including indemnity and risk purchase, shall not exceed hundred percent (100%) of the total price actually paid to the supplier under this contract.</p>		
<p>40. CORRUPT GIFTS COMMISSIONS</p> <p>The Supplier shall not:</p> <ol style="list-style-type: none"> a. Offer or give or agree to give to any person in the service of the Purchaser any gift or consideration of any kind as an inducement or reward for doing or forbearing to do for having done or forborne to do any act in relation to the obtaining or execution of this Contract or for showing or forbearing to show favor or disfavor to any person in relation to this Contract. b. Enter into this or any other Contract with the Purchaser in connection with which commission has been or agreed to be paid by him or on his behalf, or to his knowledge, unless before the Contract is made, particulars of any such commission and of any agreement for the payment therein have been disclosed in writing to the Purchaser. 		

41. PROJECT SCHEDULE

The Contract shall be executed in accordance with the dates in the Project Schedule. In case of delayed performance of any other dates or periods the Supplier shall strive to compensate such overruns in order to finally meet any subsequent binding dates. If by reason of any change order, or of any act or omission on the part of the Purchaser, or any event of force majeure the Supplier shall be delayed in the completion of the Contract then provided that the Supplier shall as soon as reasonably practicable have given to the Purchaser notice of his claim for an extension of time with supporting details, the Purchaser shall on receipt of such notice grant the Supplier an extension of time as may be reasonable.

42. CUSTOMS, IMPORT DUTIES, TAXES AND OTHER CHARGES

The Purchaser shall pay all applicable customs, import duties taxes and other charges due on the Equipment payable upon its importation into the country of destination.

The Supplier shall pay all taxes, assessments, duties, levies or charges levied in the country of the manufacturer of the Equipment in connection with the supply by the Supplier of Equipment and Services.

All amounts stated to be payable by Purchaser pursuant to this Contract exclude any value added tax (VAT), sales tax, service tax, taxes on turnover or similar taxes. If the supply of Equipment or Services hereunder are chargeable to any value added tax, sales tax, service tax, taxes on turnover or similar taxes inside country of destination, and such taxes are not recoverable by the Supplier then such taxes shall be paid and borne by the Purchaser.

Purchaser shall pay and bear all other taxes, assessments, duties, levies or charges by whosoever levied in the country of destination of the Equipment. If Purchaser is required by any law to make any deduction or withholding from any amount payable to Supplier under this Contract, then the sum payable in respect of which such deduction or withholding is required to be made shall be increased to the extent necessary to ensure that, after the making of such deduction or withholding, Supplier shall receive (free from any liability in respect of any such deduction or withholding) a net sum equal to the amount which it would have received had no deduction or withholding been required to have been made. Purchaser shall pay any such withholding or deduction to the relevant authority as required by law and shall promptly provide Supplier with an official receipt or certificate in respect of the payment of the withholding or deduction.

DP-3

Tender No .R2602330552.....

Name of the Firm.....
DGDP Registration No.....
Mailing Address.....
Date.....
Telephone No.
Official E-Mail.....
Fax No
Mobile No of contact person.....

To:

Directorate of Procurement (Navy)
through Bahria Gate Near SNIDS
Center, CDA Market
at Naval Residential Complex
Sector E-8, Islamabad
Tele : 051-9262314
Email : adpn33@paknavy.gov.pk

Dear Sir,

1. I/We hereby offer to supply to the Director of Procurement (Navy) the stores detailed in schedule to the tender inquiry or such portion thereof as you may specify in the acceptance of tender at the prices offered against the said schedule and further agree that this offer will remain valid up to 120 day and will not be withdrawn or altered in terms of rates quoted and the conditions already stated therein or on before this date. I/we shall be bound by a communication of acceptance to be dispatched within the prescribed time.

2. I/We have understood the Instructions to Tenders and General Conditions Governing Contract in Form No. DDP&I included in the pamphlet entitled, Government of Pakistan, Ministry of Defence (Directorate General Defence Purchase) "General Conditions Governing Contracts" and have thoroughly examined the specifications/drawings and/ or patterns quoted in the schedule hereto and am/are fully aware of the nature of the stores required and my/our offer is to supply stores strictly in accordance with the requirements.

3. The following pages have been added to and form part of this tender:

- a.
- b.
- c.

YOURS FAITHFULLY,

.....
(SIGNATURE OF TENDERER)

.....
(CAPACITY IN WHICH SIGNING)

ADDRESS.....

DATE.....

SIGNATURE OF WITNESS.....

ADDRESS.....

*Individual signing tender and/or other documents connected with a contract must specify:-

- (a) Whether signing as "Sole Proprietor" of the firm or his attorney.
- (b) Whether signing as a "Registered Active Partner" of the firm or his attorney.
- (c) Whether signing for the firm "per procuration".
- (d) In the case of companies and firms registered under the Act, 1913 as amended up-to-date and under the Partnership Act 1932, the capacity in which signing e.g., the Director, Secretary, Manager, Partner, etc. or their attorney and produce copy of document empowering him so to sign, if called upon to do so.
- (e) Principal's proforma invoice (in original)
- (f) Earnest money
- (g) Treasury Challan Form for tender Fees as applicable

NECESSARY DATA FOR ISSUANCE OF CONTRACTS ON EARNEST MONEY

IMPORTANT

Each column must be filled in with BLOCK CAPITAL LETTERS,
incompletion shall render disqualification.

1. Name : _____
2. Father's Name : _____
3. Address (Residential) :

4. Designation in Firm :

5. CNIC : _____
(Attach Copy of CNIC)
6. NTN : _____
(Attach Copy of NTN)
7. Firm's Address :

8. Date of Establishment of Firm :

9. Firm's Registration Certificate with FBR/Chamber of Commerce/Registrar of Companies.
(Attach Copy of relevant CERTIFICATE)
10. In case PARTNERSHIP (Attach particulars at serial 1,2,3,4,5 and 6 of each partner).

(Kindly fill in the above form and forward it under your own letter head with contact details)