



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Civil Works</u>	<u>Keamari</u>				
1.01	<u>Dismantling of existing floor</u> Dismantling / excavation of existing floor of any type (hard standing /asphalt road / pavers /cc floor/stone/bricks etc .) of max 1 ft thick as per site requirement and as per instruction of site engineer. Job includes removal, shifting of debris & surpls material to a suitable place outside the terminal premises; shifting & stacking of usable material (on proposed location) within the terminal premises and general cleaning of the site as per instruction of PSO's site engineer. Note: Quoted rates should be for 1' depth. Any variation in depth will be calculated accordingly as per actual site strata.	<u>Terminal</u>	<u>M2</u>	5		
1.02	<u>Excavation of strata</u> Excavation Excavation in all kinds of strata / soil (dry or wet, hard or soft, etc) including clearing and grubbing of site complete in all respects, including all operation, complete with breaking clods, levelling, dressing, dewatering, shoring & compacting. Also nclude backfilling of excavated stuff inclusive of breaking clods, dressing, watering and consolidating by ramming (by power roller, mechanical rammer, plate vibrator, roller of suitable size or other approved equipment as per instructions of PO Site Engineer) in layers not exceeding 6" depth. 95% modified AASHTO density to be achieved where applicable. Lifting, shifting or disposing of surplus strata outside the premises or as per instructions & approval of PSO Engineer area also included in his item. Contractor will carryout compaction test as per specification & instructions (where required by PSO) without any extra cost Note: Excavation dimensions as per approved drawing / PSO instruction shall be considered for measurement / payment. Cost includes Compaction Test and other related tests to be carried out (where required) through approved laboratory to be arranged and pid by the contractor. No extra charges/payments will be paid to contractor.		<u>M3</u>	55.000		
1.03	<u>STONE SOLING 6" TO 9"</u>		<u>M3</u>	2.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	Stone Soling Providing and laying stone soling of approved quality under foundations, plinth, floors, hard standing etc including hand packing vertically and filling voids with spawels (stone dust), consolidating and compacting with mechanical means, as per instructions of PSO Engineer. <u>Laying of CC 1:4:8 S.R. Cement</u> Concrete CC 1:4:8 Providing and laying C.C. 1:4:8 with S.R.Cement specified strength at any level using approved quality 3/4" max. size graded crushed stone and fine aggregate of required properties of approved source including water tight approved form work (installatio & removal), mixing, transporting, placing, compacting, vibrating, finishing and curing etc., scaffolding, racking out and cleaning complete in all respects and as per instructions of PSO Engineer. Note: C.C 1:4:8 dimensions as per approved drawing/ PSO instruction shall be considered for measurement / payment.		<u>M3</u>	8.000		
1.05	<u>Laying of CC 1:3:6 S.R Cement</u> Concrete 1:3:6 Providing and laying C.C 1:3:6 with S.R.Cement specified strength at any level using approved quality 3/4" max. size graded crushed stone and fine aggregate of required properties of approved source including water tight approved form work (installation & removal), mixing, transporting, placing, compacting, vibrating, finishing and curing etc., scaffolding, racking out and cleaning complete in all respects and as per instructions of PSO Engineer. Note: C.C 1:3:6 dimensions as per approved drawing/ PSO instruction shall be considered for measurement / payment.		<u>M3</u>	2.000		
1.06	<u>Laying of CC 1:1-1/2:3 S.R Cement</u> Concrete CC 1:1.5:3 Providing and laying C.C 1:1.5:3 with S.R.Cement specified strength at any level using approved quality 3/4" max. size graded crushed stone and fine aggregate of required properties of approved source including water tight approved form work (installation & removal), mixing, transporting, placing, compacting, vibrating, finishing and curing etc., scaffolding, racking out and cleaning complete in all respects and as		<u>M3</u>	2.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.07	per instructions of PSO Engineer. Note: C.C 1:1.5:3 dimensions as per approved drawing/ PSO instruction shall be considered for measurement / payment. <u>Laying of CC 1:2:4 S.R Cement</u> Concrete CC 1:2:4 Providing and laying CC 1:2:4 (using S.R cement) of specified strength using approved quality 3/4" max. size graded crushed stone and and fine aggregate of required properties including water tight approved form work, mixing, transporting, placing, levelling, compaction, rodding, vibrating, finishing and curing etc. scaffolding, racking out and cleaning, excluding cost of reinforcement, complete in all respects and as per instructions of PSO Engineer. Cube test for finding the crushing strength of concrete will be carried out to confirm the desired strength at contractors own cost i.e. (3000 psi at 28 days, 2100 psi at 7 days). The cube tests will be carried out by contractor from PSO approved laboratory or as per instruction of PSO site Engineer. Cost also includes preparation of construction joints as per site conditions, specifications and directions of Engineer Incharge. Note: 1) No extra charges/payment will be made for cube testing. 2) C.C 1:2:4 dimensions as per approved drawing/ PSO instruction shall be considered for measurement / payment.		<u>M3</u>	20.000		
1.08	<u>Providing and applying Cement Plaster</u> Plaster Providing and applying cement plaster 3/4" thick in 1:4 cement sand mortar (using SR cement) to walls, base including all corners, recesses, jams and racking out joints, roughing the surfaces and cement slurry backing to all surfaces, curing and scaffolding. This job also includes using of pudlo 5 lbs per bag of cement. All work will be carried out as per instructions of PSO Engineer.		<u>M2</u>	20		
1.09	<u>Installation of deformed steel</u> Installation of Deformed Steel		<u>KG</u>	2,000.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.10	Installation of deformed steel reinforcement bars including straightening, removing twists, cutting, bending, binding, wastage and overlaps, placing in position on precast cc chairs, tying with binding wire 18 SWG, complete as per instructions of the PS Engineer. Only actual laid quantities will be considered for payment. Deformed steel reinforcement of yield strength 60000psi. <u>PB4 CONCRETE WAT.PROOF.</u> PB4 Hot Bitumen Providing & applying PB4 Hot/Cold Bitumen of approved make with water proof chemical on foundations (inside/ outside) upto plinth level to sides and top of footings, situ walls, columns, sides of plinth beams and floor etc. as per manufacturer recommendaions including cost of all material, labour, equipments complete as per specification and as directed by the PSO Engineer Incharge.		<u>M2</u>	150		
1.11	<u>BRICK / BLOCK MASONARY</u> Providing & laying first class brick / machine made block masonry (in super structure using graded screened 'Bajri') in SR cement of specified thickness set in 1:4 cement sand mortar. The job includes required scaffolding, staging, racking out, curing D.P.C. etc. & cleaning and provision of expansion joints & 15 days water curing of masonry. The complete Job to be done as per directives of PSO Engineer. Supply & application of expansion joint is included in this item.		<u>M3</u>	2.000		
1.12	<u>Non-shrinkage grout</u> Supply & laying of 25 mm thk. non-shrinkage grout, having minimum compressive strength of 40 N/mm ² , it is applied with cement in accordance with the manufacturer specification, standard drawings, etc.		<u>M2</u>	5		
1.13	<u>Sand Filling</u> Providing and laying sand fill of approved quality as per drawing, including compacting (by power roller, mechanical rammer, plate vibrator, roller of suitable size or other approved equipment as per instructions of PSO Site Engineer) and watering in layers not exceeding 8" depth to obtain 95% modified AASHTO density. Contractor will carryout compaction test (where required by PSO) as per specification & instructions with out any extra cost.		<u>M3</u>	5.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.14	Note: Dimensions as per approved drawings/ PSO instruction shall be considered for measurement / payment. Cost includes compaction tests (at least 1 no. for each layer) where required, and other related tests shall be carried out and paid by the contractor. Earth filling Filling of approved earth (sweet) obtained from outside source and filling the same in foundation, plinth and under floors, embakements, open areas etc i/c breaking clods, dressing, watering, ramming in layers not exceeding 150 mm in depth compaction of soil as to achieve 95% AASHTO modified dry density to i/c all lead and lift as per instruction drawings & specification of the Consultant and approval <(>&<)>instructions of PSO Engineer. Note: Actual compacted depth shall be considered for measurement /payment. Cost includes Compaction Test and other related tests shall be carried out to find suitability of soil through approved laboratory to be arranged and paid by the contractor. No extra charges/payments will be paid to contractor.		M3	5.000		
1.15	Stone pitching for tanks Providing & laying stone pitching with hard stone of 6" thick perfectly embedded in cement mortar 1:4 maintaining proper top levels in such a way that required slopes are maintained at required gradient for flow of storm water.		M2	5		
2	<u>Mechanical Works</u>	<u>Keamari</u>				
2.01	<u>Cutting / Removal of Pipelines 8" dia</u> Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.	<u>Terminal</u>	M	1,380		
2.02	08" dia <u>Cutting / Removal of Pipelines 6" dia</u> Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within		M	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.					
2.03	06" dia Cutting / Removal of Pipelines 4" dia Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.		<u>M</u>	2		
2.04	04" dia Cutting / Removal of Pipelines 3" dia Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.		<u>M</u>	2		
2.05	03" dia Cutting / Removal of Pipelines 2½" dia Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.		<u>M</u>	2		
2.06	2 1/2" dia Cutting / Removal of Pipelines 2" dia Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.		<u>M</u>	2		
2.07	02" dia Cutting / Removal of Pipelines 1" dia Cutting, removal and transportation of existing above ground /		<u>M</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.					
2.08	01" dia Cutting / Removal of Pipelines 3/4" dia Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.		<u>M</u>	2		
2.09	3/4" dia Cutting / Removal of Pipelines 1/2" dia Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO Installation and stacking the same in position for safe store-keeping within the Installation premises.		<u>M</u>	2		
2.10	1/2" dia Shifting and Placing of Pipes 12" dia Shifting and placing CS pipes & fittings in position underground , aboveground pipe for welding or screwing, as per sizes below:		<u>M</u>	2		
2.11	12" dia Shifting and Placing of Pipes 8" dia Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:		<u>M</u>	1,380		
2.12	08" dia Shifting and Placing of Pipes 6" dia Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:		<u>M</u>	12		
2.13	06" dia Shifting and Placing of Pipes 4" dia		<u>M</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:					
2.14	04" dia <u>Shifting and Placing of Pipes 3" dia</u>		<u>M</u>	2		
	Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:					
2.15	03" dia <u>Shifting and Placing of Pipes 2½" dia</u>		<u>M</u>	2		
	Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:					
2.16	2 1/2" <u>Shifting and Placing of Pipes 2" dia</u>		<u>M</u>	2		
	Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:					
2.17	02" dia <u>Shifting and Placing of Pipes 1½" dia</u>		<u>M</u>	6		
	Shifting and placing CS pipes & fittings in position underground<(>,<)> aboveground pipe for welding or screwing, as per sizes below:					
2.18	1 1/2" dia <u>Shifting and Placing of Pipes 1" dia</u>		<u>M</u>	6		
	Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:					
2.19	01" dia <u>Shifting and Placing of Pipes ¾" dia</u>		<u>M</u>	6		
	Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below:					
	¾" dia					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.20	<u>Shifting and Placing of Pipes 1/2" dia</u> Shifting and placing CS pipes & fittings in position underground, aboveground pipe for welding or screwing, as per sizes below: 1/2" dia		<u>M</u>	6		
2.21	<u>Making weld joints of Pipes 10" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor.		<u>EA</u>	1		
2.22	<u>Making weld joints of Pipes 8" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note:		<u>EA</u>	300		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.23	1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 08 dia <u>Making weld joints of Pipes 6" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 06" dia		EA	2		
2.24	<u>Making weld joints of Pipes 4" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.25	cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 04" dia <u>Making weld joints of Pipes 3" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 03" dia		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

12	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.26	<u>Making weld joints of Pipes 2 1/2" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges<(>,<)> bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 2 1/2" dia		<u>EA</u>	2		
2.27	<u>Making weld joints of Pipes 2" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges<(>,<)> bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint.		<u>EA</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

13	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.28	2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 02" dia <u>Making weld joints of Pipes 1" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges<(>,<)> bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 01" dia		EA	2		
2.29	<u>Making weld joints of Pipes 3/4" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges<(>,<)>		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

14	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.30	bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 3/4" dia <u>Making weld joints of Pipes 1/2" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges<> ,<> bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), cold cutting or flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the toe- connections in the pipelines. Branch pipe connection will be considered for welding joint. 3) The job also includes Radiography of weld joints as per Standard (at		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

15 OF 38

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

RFQ No CF-19823AS

DATE 23.07.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.31	least 10%). Contractor has to arrange PSO approved inspection company for radiography and all charges for job will be borne by the contractor. 1/2" dia <u>Bolting flanged joints in Pipes 12" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 12" dia		EA	1		
2.32	<u>Bolting flanged joints in Pipes 10" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 10" dia		EA	1		
2.33	<u>Bolting flanged joints in Pipes 8" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B		EA	70		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

16	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.34	16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 08" dia <u>Bolting flanged joints in Pipes 6" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 06" dia		EA	6		
2.35	<u>Bolting flanged joints in Pipes 4" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 04" dia		EA	2		
2.36	<u>Bolting flanged joints in Pipes 3" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

17	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.37	B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 03" dia <u>Bolting flanged joints in Pipes 2½" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 2 1/2" dia		EA	2		
2.38	<u>Bolting flanged joints in Pipes 2" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 02" dia		EA	2		
2.39	<u>Bolting flanged joints in Pipes 1" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

18 OF 38

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

RFQ No CF-19823AS

DATE 23.07.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.40	Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 1" dia <u>Bolting flanged joints in Pipes 3/4" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 3/4" dia		EA	2		
2.41	<u>Bolting flanged joints in Pipes 1/2" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. RATES SHOULD INCLUDE COST OF GASKET RINGS (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS with washers (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 1/2" dia		EA	2		
2.42	<u>Unbolting flanged joints 8" dia</u> Unbolting flanged joints in pipelines / pipings as per sizes below.		M	20		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

19 OF 38

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

RFQ No

CF-19823AS

DATE

23.07.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.43	8" Unbolting flanged joints 6" dia Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>M</u>	10		
2.44	6" Unbolting flanged joints 4" dia Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>M</u>	2		
2.45	4" Unbolting flanged joints 3" dia Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>M</u>	2		
2.46	3" Unbolting flanged joints 2" dia Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>M</u>	2		
2.47	2" Unbolting flanged joints 1" dia Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>M</u>	2		
2.48	1" Unbolting flanged joints 3/4" dia Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>M</u>	2		
2.49	3/4" Unbolting flanged joints 1/2" dia Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>M</u>	2		
2.50	1/2" Installation of Valve 8" dia Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as		<u>EA</u>	16		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

20	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.51	per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 8" <u>Installation of Valve 6" dia</u> Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc.		EA	2		
2.52	6" <u>Installation of Valve 4" dia</u> Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc.		EA	2		
2.53	4" <u>Installation of Valve 2" dia</u> Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

21	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.54	joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 2" Installation of Valve 1" dia		EA	2		
2.55	Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 1" Installation of Valve 3/4" dia		EA	2		
2.56	Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 3/4" Installation of Valve 1/2" dia		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

22	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.57	fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 1/2" Hydrostatic testing of Pipe 8" dia Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system.		<u>M</u>	1,380		
2.58	08" Hydrostatic testing of Pipe 6" dia Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system.		<u>M</u>	12		
2.59	06" Hydrostatic testing of Pipe 4" dia Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All		<u>M</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

23 OF 38

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

RFQ No CF-19823AS

DATE 23.07.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.60	04" Hydrostatic testing of Pipe 3" dia Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system.		<u>M</u>	2		
2.61	03" Hydrostatic testing of Pipe 2½" dia Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system.		<u>M</u>	2		
2.62	2 1/2" Hydrostatic testing of Pipe 2" dia Hydrostatic testing of complete piping system including product loading,		<u>M</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

24	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.63	decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system. 02" <u>Hydrostatic testing of Pipe 1½" dia</u> Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system. 1 1/2"		<u>M</u>	2		
2.64	<u>Hydrostatic testing of Pipe 1" dia</u> Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system.		<u>M</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

25	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.65	01" Hydrostatic testing of Pipe 3/4" dia Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system.		<u>M</u>	2		
2.66	3/4" Hydrostatic testing of Pipe 1/2" dia Hydrostatic testing of complete piping system including product loading, decanting piping etc., as per API. 1110 (recommended practice for the pressure testing of liquid petroleum pipelines) and ASME B31.3. All piping, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be arranged by the contractor. Hydrotesting activity may have to be carried out in different phases as per site requirements i.e. underground lines before being buried etc. Rates should be quoted accordingly for testing of complete piping system.		<u>M</u>	2		
2.67	1/2" Mechanical cleaning Mechanical cleaning of external surface of tank shell, allied pipelines, platform, structural supports, etc. as per instructions of PSO engineer. All equipment, material labour required to be provided by the contractor.		<u>M2</u>	20		
2.68	Grit Blasting Grit blasting (Local or Imported garnet / copper slag) for outer surface		<u>M2</u>	900		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

26	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.69	of Tank bottom, shell, roof, underground/above ground pipeline, steel structure to near white metal surface to the satisfaction of PSO Engineer completely stain free surface. Follow the standard of surface preparation to Swedish Standard SIS 055900 Sa-2-1/2 or Steel Structures Painting Council SSPC-SP10 (i.e #near white" blasted finish). Any solvent required clean greasy spots to be supplied by the contractor. <u>Painting Works</u> Coating of tank outer shell / pipeline etc. Coating of Tank outer shell, staircase, platforms, pipeline as per specifications attached in Annexure (PSO-PS-01 Rev-0 dated: 30.08.2019). Notes: 1. Color scheme may change as per PSO requirements. 2. Minimum no. of coats and Drying Time to be provided in accordance with paint manufacturer recommendations. 3. Arrangement of Instrument for measurement of paint thickness is included in contractor scope. 4. Contractor to submit technical literature / brochure of paint and obtain prior approval from PSO before procurement of material.		<u>M2</u>	800		
2.70	<u>Painting Works</u> Coating of Tank outer shell / pipeline etc (Existing paint available) Coating of Tank outer shell, staircase, platforms, pipeline as per specifications attached in Annexure (PSO-PS-01 Rev-0 dated: 30.08.2019). Notes: 1. Color scheme may change as per PSO requirements. 2. Minimum no. of coats and Drying Time to be provided in accordance with paint manufacturer recommendations. 3. Arrangement of Instrument for measurement of paint thickness is included in contractor scope. 4. Contractor to submit technical literature / brochure of paint and obtain prior approval from PSO before procurement of material.		<u>M2</u>	2		
2.71	<u>Application of Epoxy</u> Coal Tar Epoxy Supply and application of three coats of coal tar epoxy each of 125 microns (of PSO's approved make) on the Bottom Plates, underground		<u>M2</u>	100		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

27	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.72	Pipeline / Piping etc. as per instructions of PSO engineer. Job should be done according to applicable codes, standards, as per specifications of Paint manufacturer and as per instructions of PSO Engineer. The job also includes the supply & application of Epoxy Primer to a DFT of 75 microns of the same manufacturer (compatible to coal tar epoxy) before applying coal tar epoxy as per instructions of PSO engineer. <u>Painting Works</u>		<u>M2</u>	2		
2.73	Supply and application of RED LEAD Primer to a DFT of 50 microns in a minimum of two coats on piping / any other steel structures. Surface to be cleaned with non fluffy rugs before applying primer. Job should be done according to applicable codes, standards, as per specifications of Paint manufacturer and as per instructions of PSO Engineer. Contractor to submit Paint manufacturer specification of the specified paint. <u>Painting Works</u>		<u>M2</u>	2		
2.74	Supply and application of Enamel finish coat paint (Matt Finish) compatible to the above red lead primer and should be of the same manufacturer, in specified shade to a DFT of 50 microns in a minimum of two coats on piping / any other steel structures as per relevant specification and instructions of PSO Engineer. Job should be done according to applicable codes, standards and as per specifications of Paint manufacturer. Contractor to submit Paint manufacturer specification of the specified paint. <u>Welding pipe sockets</u>		<u>EA</u>	2		
2.75	Welding pipe sockets or welding outlets in piping to make provisions for tie ins, fittings, instruments, accessories, etc. like pressure gauges, air vents, and drains etc. as per sizes below. The job also includes the cutting of piping as per size and necessary testing which may include DPT / MPI / Radiography as per requirement. 08" <u>Welding pipe sockets</u>		<u>EA</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

28	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.76	DPT / MPI / Radiography as per requirement. 6" <u>Welding pipe sockets</u> Welding pipe sockets or welding outlets in piping to make provisions for tie ins, fittings, instruments, accessories, etc. like pressure gauges, air vents, and drains etc. as per sizes below. The job also includes the cutting of piping as per size and necessary testing which may include DPT / MPI / Radiography as per requirement.		<u>EA</u>	2		
2.77	4" <u>Welding pipe sockets</u> Welding pipe sockets or welding outlets in piping to make provisions for tie ins, fittings, instruments, accessories, etc. like pressure gauges, air vents, and drains etc. as per sizes below. The job also includes the cutting of piping as per size and necessary testing which may include DPT / MPI / Radiography as per requirement.		<u>EA</u>	2		
2.78	3" <u>Welding pipe sockets</u> Welding pipe sockets or welding outlets in piping to make provisions for tie ins, fittings, instruments, accessories, etc. like pressure gauges, air vents, and drains etc. as per sizes below. The job also includes the cutting of piping as per size and necessary testing which may include DPT / MPI / Radiography as per requirement.		<u>EA</u>	2		
2.79	02" <u>Welding pipe sockets 1" dia</u> Welding pipe sockets or welding outlets in piping to make provisions for tie ins, fittings, instruments, accessories, etc. like pressure gauges, air vents, and drains etc. as per sizes below. The job also includes the cutting of piping as per size and necessary testing which may include DPT / MPI / Radiography as per requirement.		<u>EA</u>	2		
2.80	01" <u>Welding pipe sockets 3/4" dia</u> Welding pipe sockets or welding outlets in piping to make provisions for tie ins, fittings, instruments, accessories, etc. like pressure gauges, air vents, and drains etc. as per sizes below. The job also includes the cutting of piping as per size and necessary testing which may include		<u>EA</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

29	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.81	DPT / MPI / Radiography as per requirement. 3/4" <u>Welding pipe sockets 1/2" dia</u> Welding pipe sockets or welding outlets in piping to make provisions for tie ins, fittings, instruments, accessories, etc. like pressure gauges, air vents, and drains etc. as per sizes below. The job also includes the cutting of piping as per size and necessary testing which may include DPT / MPI / Radiography as per requirement.		<u>EA</u>	2		
2.82	1/2" <u>FABRICATION WORKS</u> Fabrication & erection (PIPE SLEEPERS STRUCTURE) of Steel structure pump house, additive shed, pipe supports, anchor supports, spectacle blind, anchor supports, anchor bolts, (repair / replace / modification of) existing supports / steel structure, walkways, platforms, Pipe Bridge, Sheds, railings. fixing of galvanized anchor bolts of required dia and length as per drawings, staircase, Manholes, Covers, Grating and frame for valve pit, shed, grating and cut-off drain for gantry etc. inside Installation using structural steel. The job includes all cutting, welding, grinding and erecting in position complete in all respect as per drawings, specifications and as per instructions of PSO Engineer. The Scope also includes Mechanical Cleaning of the surface and supply and application of Red Lead Primer to a DFT of 50 Microns in a minimum two coats and 2 Coats of Enamel Finish Paint (Matt Finish) compatible to the above red lead primer and should be of the same manufacturer in specified shade to a DFT of 50 microns.		<u>KG</u>	1,000.000		
2.83	<u>Flame Cutting /Cold Cutting of Pipe</u> Cold Cutting by means of standard mechanical tool for cutting of pipeline carrying hazardous product of existing above ground/underground pipeline and pipe fittings etc. within the PSO terminal premises. Contractor will ensure compliance to HSE requirement as per PSO requirements.		<u>EA</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

30 OF 38

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

RFQ No CF-19823AS

DATE 23.07.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.84	12" dia Flame Cutting /Cold Cutting of Pipe Cold Cutting by means of standard mechanical tool for cutting of pipeline carrying hazardous product of existing above ground/underground pipeline and pipe fittings etc. within the PSO terminal premises. Contractor will ensure compliance to HSE requirement as per PSO requirements.		EA	2		
2.85	10" dia Flame Cutting /Cold Cutting of Pipe Cold Cutting by means of standard mechanical tool for cutting of pipeline carrying hazardous product of existing above ground/underground pipeline and pipe fittings etc. within the PSO terminal premises. Contractor will ensure compliance to HSE requirement as per PSO requirements.		EA	10		
2.86	08" dia Flame Cutting /Cold Cutting of Pipe Cold Cutting by means of standard mechanical tool for cutting of pipeline carrying hazardous product of existing above ground/underground pipeline and pipe fittings etc. within the PSO terminal premises. Contractor will ensure compliance to HSE requirement as per PSO requirements.		EA	10		
2.87	06" dia Flame Cutting /Cold Cutting of Pipe Cold Cutting by means of standard mechanical tool for cutting of pipeline carrying hazardous product of existing above ground/underground pipeline and pipe fittings etc. within the PSO terminal premises. Contractor will ensure compliance to HSE requirement as per PSO requirements.		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

31	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
3	04" dia <u>Miscellaneous Steel structure</u> "Supply of steel plates for rehabilitation of Tank including Roof plates, Bottom plates , splash plates,<(>&<)> shell plates, as per inspection report, site requirement and in accordance with relevant codes / standards/ best Engineering practises. Specifications: HR-235/A-36/SS400B,API 5L Gr. B/ ASTM A-53 GR.B ERW, ASTM A-234 Gr. WPB, ASME B16.5, ASTM A-105 or equivalent / superior as per PSO's approval, Suitable size as per site requirement. Note: Quantities for supply would be mutually decided by PSO and Contractor before proceeding with the procurement	<u>Keamari Terminal</u>	<u>KG</u>	500.000		
4	<u>Miscellaneous Steel structure</u> "Supply of steel plates and material for rehabilitation of Tank including Roof supporting structure (column, rafters, girders), railing, staircase, stud bolts, nut bolts, washers, as per inspection report, site requirement and in accordance with relevantcodes / standards/ best Engineering practises. Specifications: HR-235/A-36/SS400B,API 5L Gr. B/ ASTM A-53 GR.B ERW, ASTM A-234 Gr. WPB, ASME B16.5, ASTM A-105 or equivalent / superior as per PSO's approval, Suitable size as per site requirement.	<u>Keamari Terminal</u>	<u>KG</u>	500.000		
5	<u>Deformed Steel Bars</u> "Supply of deformed steel reinforcement bars. All wastage, cuttings, overlaps and chairs are included in the cost and no extra payment will be made in this regard. Only actual laid quantities will be considered for payment. NOTE: Mill test Certificate from the manufacturer will be provided by the contractor. Deformed steel of yield strength	<u>Keamari Terminal</u>	<u>KG</u>	2,000.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

32	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
6	60,000Psi." PIPE CS 8" DIA SCH-40 (ERW) CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List. 2) Manufacturer must be an API certificate holder for the last 5 years minimum. "	Keamari Terminal	M	1,380		
7	08" dia Sch 40 PIPE CS 6" DIA SCH-40 (ERW) "CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List.	Keamari Terminal	M	12		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

33	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
8	2) Manufacturer must be an API certificate holder for the last 5 years minimum. " 06" dia Sch 40 <u>PIPE CS 4" DIA SCH-40 (ERW)</u> "CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List. 2) Manufacturer must be an API certificate holder for the last 5 years minimum. " 04" dia Sch 40	<u>Keamari Terminal</u>	<u>M</u>	6		
9	<u>PIPE CS 3" DIA SCH-40 (ERW)</u> "CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API	<u>Keamari Terminal</u>	<u>M</u>	6		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

34	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List. 2) Manufacturer must be an API certificate holder for the last 5 years minimum. "					
10	<u>PIPE CS 1"dia Sch-80 (Seamless)</u> Supply of CS Pipe, Beveled / Plain / Threaded end, API 5L Gr. B/ ASTM A-53 GR.B ERW as per ANSI B 36.10. 01" dia Sch 80	<u>Keamari Terminal</u>	<u>M</u>	6		
11	<u>PIPE CS 3/4"dia Sch-80 (Seamless)</u> Supply of CS Pipe, Beveled / Plain / Threaded end, API 5L Gr. B/ ASTM A-53 GR.B ERW as per ANSI B 36.10. 3/4" dia Sch 80	<u>Keamari Terminal</u>	<u>M</u>	6		
12	<u>PIPE CS 1/2"dia Sch-80 (Seamless)</u> Supply of CS Pipe, Beveled / Plain / Threaded end, API 5L Gr. B/ ASTM A-53 GR.B ERW as per ANSI B 36.10. 1/2" dia Sch 80	<u>Keamari Terminal</u>	<u>M</u>	6		
13	<u>ELBOW CS 8"dia 90deg (B.W)</u> Supply of Elbow 90 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 08" dia Sch 40	<u>Keamari Terminal</u>	<u>EA</u>	36		
14	<u>ELBOW CS 6"dia 90deg (B.W)</u>	<u>Keamari Terminal</u>	<u>EA</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

35	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
15	Supply of Elbow 90 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 06" dia Sch 40 <u>ELBOW CS 4"dia 90deg (B.W)</u>	<u>Keamari Terminal</u>	<u>EA</u>	2		
16	Supply of Elbow 90 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 04" dia Sch 40 <u>ELBOW CS 8"dia 45deg (B.W)</u>	<u>Keamari Terminal</u>	<u>EA</u>	36		
17	Supply of Elbow 45 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 08" dia Sch 40 <u>ELBOW CS 6"dia 45deg (B.W)</u>	<u>Keamari Terminal</u>	<u>EA</u>	2		
18	Supply of Elbow 45 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 06" dia Sch 40 <u>ELBOW CS 4"dia 45deg (B.W)</u>	<u>Keamari Terminal</u>	<u>EA</u>	2		
19	Supply of Elbow 45 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 04" dia Sch 40 <u>TEE Reducing CS 8" X 6"</u>	<u>Keamari Terminal</u>	<u>EA</u>	4		
20	Reducing Tee B.W ASTM A - 234 Gr WPB as per ANSI 16.9 08"x06" dia Sch 40 <u>FLANGE SORF MS 8"dia Class-150</u>	<u>Keamari Terminal</u>	<u>EA</u>	50		
21	Supply of Slip-on Flanges 150#, R.F. as per ASME B16.5, ASTM A-105. 08" Dia <u>FLANGE SORF MS 6"dia Class-150</u>	<u>Keamari Terminal</u>	<u>EA</u>	2		
	Supply of Slip-on Flanges 150#, R.F. as per ASME B16.5, ASTM A-105.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

36	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
22	06" Dia <u>FLANGE SORF MS 4"dia Class-150</u> Supply of Slip-on Flanges 150#, R.F. as per ASME B16.5, ASTM A-105.	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	2		
23	04" Dia <u>FLANGE Blind MS 8"dia Class-150</u> Supply of Blind Flanges 150 # RF, as per ANSI B 16.5, ASTM A-105.	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	2		
24	08" Dia <u>Weldolet 1"</u> "Supply of Sockolet/Weldolet/Threadolet (as required), ASTM A 105, 3000#, as per ANSI B 16.11 The sizes below indicate outlet size (branch). Main line size may vary."	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	5		
25	Dia 1" <u>Weldolet 3/4"</u> "Supply of Sockolet/Weldolet/Threadolet (as required), ASTM A 105, 3000#, as per ANSI B 16.11 The sizes below indicate outlet size (branch). Main line size may vary."	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	5		
26	Dia 3/4" <u>Weldolet 1/2"</u> "Supply of Sockolet/Weldolet/Threadolet (as required), ASTM A 105, 3000#, as per ANSI B 16.11 The sizes below indicate outlet size (branch). Main line size may vary."	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	5		
27	Dia 1/2" <u>GATE VALVE 8"dia</u> Specifications as mentioned in PSO-GV-007:	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	14		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

37	OF	38
RFQ No	CF-19823AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017525

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)


10.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Receipt Pipelines at KTB

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
28	08" Dia <u>Pressure indicator 0-15 Bar 4" Dia</u> Supply of Pressure Indicator (Simple / Compound). As per Data Sheet / Specs	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	8		
29	<u>U-BOLT CLAMP WITH WASHER.</u> Supply of U-clamps for supporting pipe of tank shell, pipe rack, etc. 08" Dia	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	50		
30	<u>U-BOLT CLAMP WITH WASHER.</u> Supply of U-clamps for supporting pipe of tank shell, pipe rack, etc. 06" Dia	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	2		
31	<u>U-BOLT CLAMP WITH WASHER.</u> Supply of U-clamps for supporting pipe of tank shell, pipe rack, etc. 04" Dia	<u>Keamari</u> <u>Terminal</u>	<u>EA</u>	2		
32	<u>PIPE CS 2"dia (ERW)</u> "CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List. 2) Manufacturer must be an API certificate holder for the last 5 years minimum. "	<u>Keamari</u> <u>Terminal</u>	<u>M</u>	6		



38 OF 38

DATE	23.07.2026
------	------------

SAP No.6100017525

QUOTATION REQUIRED

BY
(Time)

EARNEST MONEY %

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	02" dia Sch 40					