Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Deboxing of 31m dia 14.6m height Tank**	**New Faisalabad (Depot)**				
1.01	**Bolting/Unbolting of pipe joints** The Scope of work includes but not limited to the following Unbolting of Tank Roof Manholes Job includes Unbolting of 24" dia Manholes of Tank Roof. Scope of Work: --- Job includes application of anti-rust spray before unbolting activity and use of non-ferrous tools for unbolting activity. Contractor to arrange non-ferrous tools such as brass tools, etc. The job also includes the lifting of man hole and removing it from tank and placing it nearby.		**EA**	1		
1.02	**Bolting/Unbolting of pipe joints** Removal of sump line valve includes Unbolting of 4" dia line of Tank. Scope of Work: --- Removal of sump line valve after unbolting it. The job includes the unbolting of both valve flanges. Job includes application of anti-rust spray before unbolting activity and use of non-ferrous tools for unbolting activity. Contractor to arrange non-ferrous tools such as brass tools, etc.		**EA**	1		
1.03	**Bolting/Unbolting of pipe joints** Unbolting of Tank Shell Manholes Job includes Unbolting of 24" dia Manholes of Tank Shell. Scope of work as given in item 1.001. The scope of work includes but not limited to the following Vertical tank Cleaning (Dia 31 M, Height 14.6 M)Product stored is HSD		**EA**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	(Tank is being opened first time, i.e after 10 years, commissioned in 2016) Bolting and un bloting, Isolation of valves using Spectacle blind ,Degassing, Removal of product, Removal of Sludge, Internal Cleaning Box up the tank after Integrity Assessment.					
2	**Installation of Blind Plates**	**New Faisalabad (Depot)**				
2.01	**Tank Capacity Plates** Positive Isolation of Tank Pipelines Providing and installation of Spectacle Blinds on Tank's 1 nos x 12" dia Delivery Pipelines. Job to be done prior to degassing and opening of manholes. Scope of Work (for item 2.001 to 2.002): Unbolting of connecting flange joint. Scope of work also includes providing and installation of spectacle blinds, and application of anti-rust spray before unbolting activity and use of non-ferrous tools for unbolting activity.		**EA**	1		
2.02	**Tank Capacity Plates** Positive Isolation of Tank Pipelines Providing and installation of Spectacle Blind on Tank's 1 no.x4" dia Return Pipeline. Job to be done prior to degassing and opening of manholes. Scope of work as given in item 2.001.		**EA**	1		
2.03	**Tank Capacity Plates** Providing and installation of Spectacle Blinds on Tank's 1 nos x 14" dia Receipt Pipelines. Job to be done prior to degassing and opening of manholes. Scope of Work as given in 2.001.		**EA**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
3	**Lighting and Ventilation**	New Faisalabad (Depot)				
3.01	**Installation of LED Lights** **EA = 1 JOB** Explosion Proof Lights in Tank Installation of explosion proof LED Lights (at least 3 Nos) to obtain total 1000 LUX. Vendor will also arrange all the cables, pipes<(>,<)> explosion proof D.B, earthing of DB, lights required for job completion.		EA	1		
3.02	**24 Inch dia Industrial Exhaust Fans** *EA = 1 JOB** Degassing of Tank Job includes degassing of tank of diameter 31.5m with one explosion proof exhaust fans/blowers. 1 No. x 24" explosion proof exhaust fan to be installed on roof manhole.		EA	1		
4	**Retrieval of Product**	New Faisalabad (Depot)				
4.01	**Product Transfer Operation** **MTO = Ltr** Retrieval of product from bottom and center sump with minimum 1" dia Ex-proof pump. Product will be retrieved by suction end of pump into the center sump line and pump outlet to be connected to Receipt pipeline of another tank or tank lorry.		MTO	600,000.000		
5	**Removal of Sludge**	New Faisalabad (Depot)				
5.01	**Supply and Installation of Pump.**		EA	100		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	NOTE: EA= 1 Drum Removal of sludge from the tank. Sludge will be removed from tank and shifted to metallic drums provided against the line item 5.002. if quantity exceeds or not manageable by Drums then contractor will excavate the pit as per requirement and will install and lay two layers of polyethene to prevent contamination of soil. NOTE: Payment is subject to the number of drums filled. In case of excavation of pit, the total item amount will be paid.					
5.02	**Replacement of parts** Supply of metallic drums for storage of sludge Payment will be made as per the actual number of drums provided. *NOTE: 1JOB= EA*		**JOB**	15		
6	**Internal Cleaning of Tank**	**New Faisalabad (Depot)**				
6.01	**Mechanical Cleaning tank** NOTE: EA= Meter Square Manual cleaning to be done using labor and high-pressure water-jet nozzle with independent of source of water and relevant attachments, as needed to remove contaminants. Job is subject to the approval of terminal engineer. Note: Internal Area for cleaning will be including complete Bottom and 1st course of shell.		**EA**	755		
7	**Box-up of Tank**	**New Faisalabad (Depot)**				
7.01	**Bolting/Unbolting of pipe joints**		**EA**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Bolting of Tank Roof Manholes Job includes Bolting of all 24" dia Manholes of Tank Roof after placing them in their original position and after completion of integrity of tank. Job also includes supply and installation of non-asbestos gasket sheet 2mm thick. Scope of Work: Job includes application of anti-rust spray before bolting activity and use of non-ferrous tools for bolting activity. Contractor to arrange nonferrous tools such as brass tools, etc.					
7.02	**Bolting/Unbolting of pipe joints** Bolting of Tank pipeline Job includes Bolting of 4" dia return pipeline and sump pipeline after placing of valve to its original place and removal of blind from return pipeline. Job also includes supply and installation of Flexitallic or equivalent spiral wound gasket (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20). Scope of Work as given in item no. 7.001		**EA**	1		
7.03	**Bolting/Unbolting of pipe joints** Bolting of Tank delivery pipeline Job includes Bolting of 12" dia pipeline of delivery valve after removal of blind, the job should be done after the completion of tank integrity. Job also includes supply and installation of Flexitallic or equivalent spiral wound gasket (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20). Scope of Work as given in		**EA**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	item no. 7.001					
7.04	**Bolting/Unbolting of pipe joints** Bolting of Tank delivery pipeline Job includes Bolting of 14" dia pipeline of Receipt valve after removal of blind, the job should be done after the completion of tank integrity. Job also includes supply and installation of Flexitallic or equivalent spiral wound gasket (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20). Scope of Work as given in item no. 7.001		EA	1		
7.05	**Bolting/Unbolting of pipe joints** Bolting of Tank Shell Manholes Job includes Bolting of all 24" dia Manholes of Tank Shell after placing them in their original position and after completion of integrity of tank. Job also includes supply and installation of non-asbestos gasket sheet 2mm thick. Scope of Work same as given in item no. 7.001.		EA	1		
8	**Mobilization and Demobilization**	New Faisalabad (Depot)				
8.01	**Transportation / Labour Charges** Job includes Mobilization and Demobilization of equipment and personnel to site as per requirement of job / instructions of terminal engineer or in charge. TERMS and CONDITIONS: ========== 1. All services, tools, materials to be provided by the contractor.		JOB	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Non-Ferrous tools to be used for bolting and unbolting works. 2. All the transportation, accommodation is responsibility of contractor paid by the contractor and rates will be inclusive of all taxes. 3. Tank will be handed over to vendor upon its availability. 4. Tank will be handed over to contractor after product level is reached to dead stock, and operations department will confirm it. 5. Contractor will ensure the positive isolation is done before unboxing of tank. 6. Contractor will be providing detailed Work Method Statement<(>,<)> Emergency Response Plan, Risk assessment. Relevant Permit to works will be obtained before start of work. WMS (Work Method Statement should be included but not limited to the following) i. Ventilation Requirements for Confined Spaces: Ventilation is a way of making sure employees have access to enough breathable air. Any obstruction to the flow of oxygen could impact the health of persons inside the confined space in a matter of minutes or less. It may cause dizziness, shortness of breath, increased heart rate, headaches, or restlessness. ii. Under OSHA regulations, you must provide the following safety measures: "Oxygen (O2) levels need to stay between 19.5% and 22%." "Gases and flammable vapours must be kept below 10% of their lower explosive limit (LEL)" "Potentially toxic materials must stay below their personal exposure limit (PEL) levels, or immediate danger to life and health (IDLH) levels if you're using anything less than supplied air respirator protection. Monitoring Workplace Workspace needs to be continuously monitored in order to find out if additional ventilation is needed or if the levels become a hazard. A quality Gas Monitor must be used to test the air at all levels, including at the bottom, middle, and top of the space. Use a 4-Gas Monitor that can measure hydrogen sulphide, carbon monoxide <(>,<)> oxygen, and the lower explosive levels of combustible gases. The					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	attendant / buddy system has specific responsibilities during a confined space entry. These includes: "Attendant should remain outside the space during entry operations - Do Not Leave the space unattended." "The Attendant should have a clear knowledge of hazards-existing <(>&<)> potential and able to use air monitoring equipment to keep a close watch on the atmospheric conditions inside the confined space and communicate changes." "Maintain communications with the entrant" 7.Contractor will ensure availability of PPEs as per Job Hazard Analysis including Third Party Inspected SCBA, Gas Masks, Nitrile and Cotton Gloves, Long Rubber Boots, Safety Shoes, Googles etc. 8.Contractor will depute skilled and qualified Site Supervisor (B.E / D.A.E), HSE Supervisor with HSE certifications (IOSH/NEBOSH), and Confined space entry attendant with specialized certification for each tank. All deputed staff must have experience in relevant job and Oil <(>&<)> Gas industry. 9. Contractor will provide third party certification of equipment to be used where applicable. 10. Contractor will ensure earthing of equipment to be installed. Earthing test will also be carried out for equipment installed and storage tank as well. Work will be carried out if results are satisfactory as per PSO Policy. 11. Contractor will arrange enough F.Es to be placed at site. 12. The contractor will arrange all accessories required for proper cleaning of the tank including saw dust, wipers etc. 13. Any product losses/ contamination due to improper collection pit / polythene sheet shall be borne by the contractor as appropriated by Location In charge. 14. Contractor should maintain housekeeping of the worksite during progress of work and shall clear and remove all surplus materials and rubbish from site after completion of job as per instruction of Engineer In charge.					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018888

RFQ No	OP-20167NZ
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith

EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Vertical Tank 7001 (Dia= 31M, Height= 14.6M, Product= HSD) Cleaning for Internal Inspection as per API 653 at Faisalabad Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	15. Project delivery date is of 1 year from PO issuance date due to uncertainty of tank availability. After intimation from terminal engineer, vendor is to mobilize within 2 day and completion time for all activities will be 15 days after handing over of tanks. 16. If the Contractor fails to complete the work within time stipulated <(>,<)> the Engineer In charge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Work Order per day per the time delayed and subject to maximum 10% Value of P.O. 17. For all explosion proof and intrinsically safe items and also any other safety items, vendor will be required to submit valid certificates.					