Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019031

RFQ No	AD-20194NZ
DATE	16.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	27.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply <(>&<)> Installation of Refrigerant Piping for AC System at 3rd Floor PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Control wire** Control Wire Copper 1.5mm x 3 core CU PVC PVC Flexible Pakistan Cable or Equivalent.	PSO House	EA	400		
2	**Electric Wire** Electric Wire Copper 2.5mm x 3 core CU PVC PVC Flexible Pakistan Cable or Equivalent	PSO House	EA	500		
3	**Providing services**	PSO House				
3.01	**Miscellaneous services** -) Providing services for installation of refrigerant kit (Copper pipe) 5/8" x 3/4" Muller 22 Guage weight: 5kg and 3 kg Separate insulation of both pipes Make Aero Flex. -) Wapping tape. -) control wire 1. 5mm x 3 core Pakistan Cable at 3rd floor PSO House. -) Scope of work includes: Survey the site and provide execution layout for approval. Laying of refrigerant pipe with control wire with using flexible pipe (complete wrap kit) from Indoor unit point through AHU room and then towards cooling tower to outdoor unit point through cable tray and proper conduits with saddles as per drawing. -) Core cutting 15inch in CC roof slab on each floor and walls to AHU room and office walls were installation of indoor unit. -) Electrical connections from outdoor unit to DB at 3rd floor 2.5mm x 3 Core Make Pakistan Cable. -) Channels and conduits to properly encase the pipes. -) Wall cutting for concealed refrigerant pipe and PVC drain pipes.		JOB	980		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019031

RFQ No	AD-20194NZ
DATE	16.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	27.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith

EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply <(>&<)> Installation of Refrigerant Piping for AC System at 3rd Floor PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	-) Plastering and Painting Works to patch the cutting. -) Holding nitrogen pressure for testing of Installed refrigerant pipes. -) 22g Refrigerant Pipe. -) High Quality Insulation (Aero flex or equivalent). -) Separate Insulations for return and suction line. -) Scaffolding platform will be used for work. -) PPEs and Certified Tools for execution of job. Note: Job = RFT					