



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	5
RFQ No	RF20139SI	
DATE	28.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018839

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Complete NVRO Signage Removal, Transportation and Installation of Faisalabad <(>&<) Multan Divisions.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Complete Signage Removal of NVROs</u>	<u>PSO House</u>				
1.01	<u>BVI</u> <u>Installation & Removal</u> Complete Fascia Signage Removal for NVROs of Faisalabad & Multan Divisions, Under BVI Project: Job Includes: Providing services for dismantling and removal of existing ACM Fascia Signage including fascia logo, old blue bars, frames, angles, Z & L section, Lapping Sheet holders /connector, wiring etc. complete in all respect. The job includes transportation of materials from one site to another site. JOB-EA (EA is equivalent to one NVRO station). Note: Quantity of this item represent number of site(s)"		<u>EA</u>	16		
1.02	<u>Supply and Installation of Blue Bar</u> Complete Fascia Signage Installation for NVROs of (Faisalabad & Multan) Divisions, Under BVI Project: Job Includes: Providing and installation of existing MS structure repairing, cutting <(>,<) welding with red oxide primer (Two coats) along with finish paint White oil (two coats) ICI/Burger for proper fixing of ACM sheets as per PSO approved design along with addition of new structure and misc. items where required to complete site signage. Job further includes: 1. Routing, cutting, bending and installation of old ACM sheets with new fascia structure (24 SWG Gauge Precoated) and installation of old fascia logo as per PSO approved design.		<u>ET</u>	2,300		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	5
RFQ No	RF20139SI	
DATE	28.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018839

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Complete NVRO Signage Removal, Transportation and Installation of Faisalabad <(><)> Multan Divisions.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	<p>2. Installation of new holder sheet (22 SWG gauge MS white paint) and new wiring (2 core 2.5sqmm PVC insulated cable) with proper dressing.</p> <p>3. Installation of old blue with acrylic end covers on both sides of the blue bar, applying PSO blue vinyl over the covers from both sides<(><)> making the side covers free from blue taping, and reinstalling them in their original position.</p> <p>Job is in: RFT</p> <p>Removal, re-installation of lights</p> <p>Complete Signage (other than fascia) Removal for NVROs of (Faisalabad & Multan) Divisions, Under BVI Project:</p> <p>Job Includes:</p> <p>Providing services for dismantling and removal of existing Name sign with frame, Wall logo with frame, spreaders with frame, IN & Out sign<(><)> Tyre shop sign, car wash / autocare sign, tank & office area signages as per site requirements complete in all respect. The job includes transportation of materials from one side to another site (designated by concerned Engineer).</p> <p>JOB-EA (EA is equivalent to one NVRO station). Means Quantity of this item represent number of site(s)</p>		JOB	16		
1.04	<p>Signage Miscellaneous</p> <p>Complete Signage (other than fascia) Installation for NVROs of (Faisalabad & Multan) Divisions, Under BVI Project:</p> <p>Job Includes:</p> <p>Providing Services for installation of existing Nameplate with frame<(><)> Wall logo with frame, spreaders with frame, IN & OUT sign, Tyre</p>		JOB	8		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	5
RFQ No	RF20139SI	
DATE	28.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018839

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Complete NVRO Signage Removal, Transportation and Installation of Faisalabad <(><)> Multan Divisions.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	shop sign, carwash / autocare sign, tank area and office area signages as per site requirements complete in all respect. JOB-EA (EA is equivalent to one NVRO station). Means Quantity of this item represent number of site(s) SHOP STOP SIGN Complete Shopstop Signage Removal, Transportation and Installation for NVROs of (Faisalabad & Multan) Divisions, Under BVI Project: Job Includes: Complete Shop Stop Signage (including Aluminum Louvers, Letters and mics. electrical supplies, removal/installation and transportation (to another site designated by concerned Engineer) complete in all respect to maintain the proper working after installation.		EA	7		
1.06	Signage and Graphics work Providing and pasting of vinyl (3M or equivalent) of outlet Name plates , Spreaders, Blue bars. The scope of work includes removal of vinyl and pasting of lamination and new approved vinyl on the existing spreaders/name plate/bluebars as per PSO approved specifications The job includes printing/plotting and pasting of new brand name with approved vinyl (3M or equivalent) as per site requirement of approved PSO color complete in all respects. Job also includes transportation and installation: Terms and Condition: 1. All material labor and tools are included in the scope. 2. Job to be completed with-in deadline as per Engineer Per site (2		ALI	1,300		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	5
RFQ No	RF20139SI	
DATE	28.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018839

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Complete NVRO Signage Removal, Transportation and Installation of Faisalabad <(>&<)> Multan Divisions.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>days) from the date of Site handover date to the Contractor. If the Contractor fails to complete the work with in stipulated time, the Engineer In charge will be entitled to deduct from his bills for work given in this order or other payments due to him by PSO, a value of 0.1% of Service Order per day and subject to maximum 10% Value of Work Order/per site, Housekeeping of the workplace is sole responsibility of contractor, removal of scrap/debris and other waste material to be done on daily basis after completion of daily job. In any case the waste material/debris or any material reporting lying at sit<(> ,<)> the contractor will be liable to pay penalty amounting Rs.50000/- per site.</p> <p>3. Contractor to submit before and after pics. of each activity (i.e. Numbers wise for each activity mentioned in item 01 TO 06 respectively) with the submission of bill.</p> <p>4. Any damages occurred while uninstalling and re-installing any item (i.e. signage items, ACM sheet, Blue-bars, LED rods, holders and others) any other signage item will be reimbursed by the contractor without any extra charges.</p> <p>5. SOP for Structure replacement Dated; 19-10-2020 to be strictly followed throughout the all the jobs.</p> <p>6. Frame pipe to be presented to concern DE for sample and gauge measurement before execution of work.</p> <p>7. The contractor needs to ensure all necessary HSE precautionary measures (i.e. JHAs and as instructed by Divisional Engineer as per PSO policy) before executing the job. 8. Cleaning of the site and removal of waste recovered from the job is the sole responsibility of contractor. Neat and clean area of work must be ensured before submitting the bill.</p> <p>9.The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers.</p> <p>10. All tools, equipment used by the contractor must be properly maintained and remain HSE compliant.</p> <p>11. Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	5
RFQ No	RF20139SI	
DATE	28.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018839

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Complete NVRO Signage Removal, Transportation and Installation of Faisalabad <(><)> Multan Divisions.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	License/certification of it. 12. Wherever applicable, contractor is bound to engage certified licensed electrician for electrical works. 13. Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm, etc.) For any special case, approval from DE will be required and work will be performed under supervision of DE. 14. The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure<(><)> proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment.					