Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**SMOKE DETECTOR** Supply Addressable Smoke Detector with base. Supply of a complete Addressable smoke Detector with base and built-in Fault isolator<(>,<)> Gent by Honeywell or equivalent which is Compatible with our Fire Alarm Control Panel. - General specifications: 1. Sensor base: part no. S4-700, Gent by Honeywell or equivalent<(>,<)> which must be compatible with the existing system 2. Sensor: part no. S4-715(White), EN54-7, made by Honeywell or equivalent<(>,<)> which must be compatible with the existing system 3. OPERATING TEMPERATURE: -10 to +50°C 4. WEIGHT: - 0.11kg (0.17kg inc. base) 5. DEVICE / LOOP LOADING: -200 devices per Loop (Assumes 6. 800mA Loop Card) 7. COLOUR: - White RAL 9010 8. Dimensions (mm): Height: 49.6 (63.8 with base) & Width:117.	**PSO House**	**EA**	110		
2	**HEAT DETECTOR** Supply Addressable Heat Detector with base: Supply of a complete Addressable heat Detector with base and built-in Fault Isolator<(>,<)> Gent by Honeywell or equivalent<(>,<)> which is Compatible with our Fire Alarm Control Panel. - General specifications: 1. Gent by Honeywell or equivalent, nt which must be compatible with the existing system. 2. Gent by Honeywell or equivalent<(>,<)> which must be compatible with the existing system 3. OPERATING TEMPERATURE: -10 to +50°C 4. WEIGHT: - 0.11kg (0.17kg inc. base)	**PSO House**	**EA**	4		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	5. DEVICE / LOOP LOADING: -200 devices per Loop (Assumes 6. 800mA Loop Card) 7. COLOUR: - White RAL 9010 8. Dimensions (mm): - Height: 49.6 (63.8 with base) & Width: 117					
3	**Sounder with Flasher** Addressable Sounder Flasher TECHNICAL SPECIFICATION -1.0 TONE AND VOICE SOUNDERS: Supply of Addressable Electronic Sounder Flasher<(>,<)> Red Body 100dBAandbuilt-in Fault Isolator Gent by Honeywell or equivalent<(>,<)> which is Compatible with our Fire Alarm Control Panel. Part No. S3-S-VAD HPR-R Sounder with flasher. - General Specifications: Type: Sounder for fire alarm system Approx. max quantity per Loop (dependent on loop load): 1. Standard Tone 200 2. Voice Enhanced 200 3. Inc. Bell Sound 160 4. Approx. Weight: 0.3Kg 5. Operating Temperature: 100 C to +500 C 6. Sound Output: 103 dB(A) + 3dB(A) @im 7.1R Control Operating Distance: 3m 8. Approvals: LPCB approved to EN54-3, EN54-23 and EN54-17.	**PSO House**	**EA**	10		
4	**Manual Call Point (fire alarm system)** Part No.: Manual call point with resettable element and protective cover #(S4-34845) with back box Or Equivalent with the same specifications, which is compatible with the existing fire alarm system and control panel. - General Specifications: Required Item: Manual call point with resettable element and protective cover and back box 4. MAX QUANTITY PER LOOP: 200 2. OPERATING TEMPERATURE: -25°C to 70°C	**PSO House**	**EA**	10		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	3. INGRESS PROTECTION Standard: IP43					
	4. APPROX WEIGHT: 0.11Kg					
	5. DEVICE LOAD FACTOR:1					
	6. Square Area: 8100 mm*2					
	7. Relevant Standards: EN54 part11 and 17					
	8. Connection terminal: Removable terminal block					
5	**2 core 1.5 mm power cable**	**PSO House**	**EA**	2,000		
	2 Core 1.5mm Fire Retardant Cable 2000 Meter(500Meter Coil # 4nos)					
	Note: EA = Meter					
	2C+E x 1.5mm? Prysmian FP200 Gold Fire Alarm Cable Red					
	LSHF - 500m Reel or Equivalent with same specification and meet all NFPA					
	standards.					
	General Specifications:					
	1. Color-Red					
	2. Core- 2-core and earth wire					
	3. One Conductor size-1.5mm2					
	4. Sheath-LSHF					
	5. One pack size-500m					
	6. Conductor Material-Copper					
	7. Conductor Surface-Bare					
	8. Core insulation material- Cross-linked polymer					
	9. Screen Construction-Metallized foil					
	10. Material-Aluminum					
	11. Cable Shape-Round					
	42. Conductor temperature: +70 to -25 degrees Celsius					
	13. Insulation temperature: +0 to +60 degrees centigrade					
	14. Bending radius-6D					
	15. Core insulation color- blue and brown					
	16. Sheath Color-Main sheath red					
	17. Conductor category # Class 1 solid					
	18. Nominal outer diameter- 7.9mm					
	19. Cable weight (kg/km)- 140					
	20. Conductor Resistance at 20 degrees centigrade (Ohm/km)-7.41.					
6	**uPVC Pipe 1_1/4" dia**	**PSO House**	**M**	2,000		
	Note: Measuring Unit M=RFT length of PVC Pipe					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	1" Conduit/Flexible. - General Specifications: 1. Material: Rigid, impact-resistant plastic 2. Standard: UL 94 flame retardancy 3. Color: Grey 4. Size: 1 inch. With complete hardware fittings like J-clamp, saddle<(>,<)> and other required items. - Also, ensure the conduit complies with the recommended NFPA standards for conduiting of fire alarm wire.					
7	**Miscellanious Services**	**PSO House**				
7.01	**Miscellaneous services** Laying, installation<(>,<)> and fitting services for PVC conduits, fire alarm wiring<(>,<)> and Fire Alarm hardware equipment: Proper Laying/fixing/installation of PVC conduits at any height and subsequent laying and termination of 2-core fire alarm wiring, including manual tagging. (as mentioned in supply line items) along with all necessary fittings, accessories, and civil works; complete in all respects. Job also includes installation/fixing, testing<(>,<)> and commissioning of all required hardware items (as mentioned in supply line items) such as smoke detectors, heat detectors, sounders<(>,<)> flashers, and manual call points. Note: Smoke detectors, heat detectors, sounders flesher, flashers, and MCPs shall be installed at the specified heights and locations in accordance with applicable NFPA standards. All installed devices and accessories shall be compatible with the existing fire alarm system and control panel.		**JOB**	1		
7.02	**Miscellaneous services** Installation, Testing, Commissioning, Software Programming<(>,<)>		**JOB**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Addressing and Completion of all work. Health report, Integration of the floor, Manual Tagging of all devices. 1. Program the fire alarm control panel to ensure the proper operation of all devices. 2. Configure zones, device addresses, and notification settings according to the design specifications or client requirements. 3. After the installation of all devices, integration, and programming <(>,<)> the vendor must ensure that there are no errors (e.g., high resistance<(>,<)> missing or replaced devices) indicated on the main control fire panel. The vendor must also ensure that the panel is in healthy condition and operates correctly after the work is completed. - A- Testing: Conduct thorough testing of the entire fire alarm system including: 1. Functional testing of all devices (smoke detectors, heat detectors<(> ,<)> manual call points, sounders flesher, and other devices). 2. The vendor must verify that the alarm signals are displayed correctly on the fire control panel. 3. After completing the entire work, the vendor must provide the testing results documentation to the PSO representative and ensure compliance with local codes and NFPA standards or their respective standards. - B- Handover and Documentation: After completing the project, the vendor shall hand over the system to the PSO concerned officer and submit all necessary documents for the handover, including. 1. Operation and Maintenance manual. 2. Unload and load testing reports. 3. Addressing reports. 4. Health reports for all installed devices, such as smoke detectors<(>					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	,<)> heat detectors, sounders, flashers, and manual call points. The vendor must ensure that the age of all devices is less than one year. If the health report indicates that any device is older than one year<(>,<)> it must be returned to the vendor for replacement with a new one<(>,<)> which should be less than one year old.					
7.03	**Demolition Work (JOB)** Before dismantling the devices, extract and save the Health Report from the panel. Once the report has been successfully collected, carefully remove the devices and wiring. Approximate number of devices: 70 to 80 Nos. Note: A - Defects Liability Period: The defects liability period for this project will be 12 months, starting from the date of formal handover. During this period, the vendor is obligated to remedy any defects or malfunctions related to the installation and performance of the fire alarm devices and wiring, at no additional cost to PSO. Note: The vendor must visit the site to assess the technicalities of the required equipment. and the existing equipment and fire alarm system; also<(>,<)> his bidding equipment must be compatible with our existing fire alarm system and control panel. The vendor must ensure that the age of all devices is less than one year. If the health report indicates that any device is older than one year, it must be returned to the vendor for replacement with a new one, which should be less than one year old. General Terms and Conditions: The vendor must provide the certifications of the product.		**JOB**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	- The Vendor must provide OEM items along with a Letter of Authorization for each item(s). - The Vendor must provide the part number of each item(s). - Any ODM-manufactured product will not be allowed. - The job includes labor, transportation<(>,<)> and all material charges. - All Govt. taxes and GST are included in the above-mentioned rates. - As the quantities may vary (increase or decrease according to the job requirements), therefore, payment will be made as per the actual quantity of work done. - Quality is the prime concern of PSO; no compromise shall be made in this regard. Only first-class approved quality material, workmanship and supervision will be utilized by the contractor<(>,<)> which shall strictly conform to the WO/PO specification. The above job is subject to the entire satisfaction and inspection /acceptance by the consignee. - Contractor should strictly follow the safety and security rules of PSO. Contractor to follow Company's rules and procedures as well as HSE guidelines and safety procedures. Contractor will provide and ensure usage of PPEs<(>,<)> i.e.<(>,<)> Safety Shoes<(>,<)> Gloves, Helmets, Goggles, Safety Harness, Safety Belts<(>,<)> etc.<(>,<)> during execution of work. HSE Manual & Instructions are provided for information <(>&<)> compliance. - All services, tools, first aid box, ladder, materials and transportation required for execution of work to be arranged and provided by the contractor. - PSO may take action that may include but not be limited to restriction on participation in the procurement process, cancelation of Work Order/Service Order/Purchase Order or Letter of Intent or forfeiture of the earnest money/performance guarantee/security against the					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018831

RFQ No	AD-20149MS
DATE	28.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	12.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply and Installation of a Fire Alarm System at the 4th Floor, PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	bidder/supplier/contractor on the following grounds: a- Unsatisfactory general conduct; b- Misrepresentation of facts in bid documents; c- Refusal to replace defective material. d- Failure to meet the delivery schedule without giving any satisfactory justification<(>,<)> resulting in loss to the Company or having an adverse effect on the operations of the Company. e- Violating the terms and conditions of the Purchase/service Order. f- Refusal or denial of accepting WO/SO/PO/LOI issued by the Company. Delivery Timeline Material Delivery: All materials for the 4th floor shall be delivered within 45 days after issuance of the Purchase or Service Order. PENALTY: In the event of Contractor's/Supplier failure to deliver the Services/Goods within the time mentioned in purchase order/service order, in that event PSO shall be entitled to deduct from his bills/outstanding payments or other works done by him for PSO or from any amount due to him by PSO a sum of Rs.0.1% of Purchase Order/Service Order value per day as liquidated damages for the period during which the said services/material remains incomplete or fails to pass the quality tests, subject to a maximum of 10% of the work order amount to be recovered from the contractor on his default. Miscellaneous services.					