Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019100

RFQ No	AD-20221SJ
DATE	23.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	04.12.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Providing services for the replacement of the existing overhead water tank filling and discharge pipelines at PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Overhead Tank Pipe line**	**PSO House**				
1.01	**PVC Piping Work (4 inch Dia)**		**RFT**	1,150,000		
	1.Removal and Replacement Pipeline Work Providing services for the replacement of the existing overhead water tank filling and discharge pipelines at PSO House. The scope of work includes the safe removal of the existing GI pipelines, demolition of masonry walls wherever required, and installation of new Hydroplast UPVC Schedule 80 pipelines from the basement to the overhead water tank. Upon completion of the piping work <(>,<)> all demolished masonry walls shall be reconstructed and restored to their original condition. The contractor shall supply and install all required pipes, sockets<(> ,<)> elbows, tees, fittings, and accessories, ensuring proper alignment<(> ,<)> jointing, support, and leak-proof connections. The entire job shall be completed in all respects to the satisfaction of the PSO Engineer-in-Charge. The work shall be inspected and tested, and the site shall be cleaned and handed over in a safe and satisfactory condition upon completion. RFT=Job Quantities 1 UPVC Pipe, 4-inch, Hydroplast 80 Schedule 250,,Rft,, 2 UPVC Pipe, 3-inch, Hydroplast 80 Schedule 80,,Rft,, 3 UPVC Pipe, 2-inch, Hydroplast 80 Schedule 60,,Rft,, 4 UPVC Socket, 4-inch, Hydroplast,,16,,Nos.,, 5 UPVC Socket, 3-inch, Hydroplast,,5,,Nos.,, 6 UPVC Socket, 2-inch, Hydroplast,,5,,Nos.,, 7 UPVC Elbow, 4-inch, Schedule 80<(>,<)> Hydroplast,,6,,Nos.,,					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019100

RFQ No	AD-20221SJ
DATE	23.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	04.12.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Providing services for the replacement of the existing overhead water tank filling and discharge pipelines at PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	8 UPVC Elbow, 2-inch, Schedule 80, Hydroplast,,2,,Nos.,, 9 UPVC Elbow, 3-inch, Schedule 80, Hydroplast,,6,,Nos.,, 10 UPVC Elbows, 4-inch<(>,<)> Schedule 06 11 UPVC Elbows, 3-inch,,04 Nos 80,Hydroplast 12 UPVC Elbows, 2-inch,,04 Nos 13 UPVC Elbows, 1.5-inch 04 Nos 14 UPVC Elbow, 45-degree<(>,<)> 4-inch, Hydroplast Schedule 80 6,,Nos,, 15 UPVC Tee, 2.5-inch, Schedule 80 15,,Nos.,, Terms and Conditions 1.,,All materials shall be new, genuine, and of the specified make<(> ,<)> type, and pressure rating. 2.,,The contractor shall take all necessary precautions to protect existing utilities, building structures, and surrounding areas during execution. 3.,,The work shall include dismantling, removal, and disposal of the old GI pipelines and associated debris. 4.,,All masonry walls damaged or demolished during the work shall be reconstructed and finished to match the existing condition. 5.,,The newly installed pipeline system shall be properly supported and tested for leakage and satisfactory operation before being put into service. 6.,,All work shall be carried out in accordance with applicable safety requirements and the instructions of the PSO Engineer-in-Charge. 7.,,The contractor shall arrange all necessary tools, equipment, labour <(>,<)> transportation, fittings, and consumables required to complete the job. 8.,,The contractor shall carry out the demolition and reconstruction of masonry walls wherever required for pipeline installation. 9. The new pipelines shall be installed with proper alignment, supports <(>,<)>					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019100

RFQ No	AD-20221SJ
DATE	23.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	04.12.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Providing services for the replacement of the existing overhead water tank filling and discharge pipelines at PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	jointing, and connections to ensure leak-proof operation. 10. The contractor shall conduct leakage and operational tests of the complete pipeline system before handing over the work. 11. All necessary safety precautions shall be observed during execution. The contractor shall obtain the required work permits and ensure the use of appropriate personal protective equipment (PPE). 12. The contractor shall protect existing structures, utilities<(>,<)> equipment, and surrounding areas from damage during the work. Any damage caused to the existing property due to the contractor's negligence shall be repaired at the contractor's own cost. 13. The work area shall be kept clean, and all debris and waste materials shall be removed upon completion. 14.The contractor shall coordinate with the PSO representative before shutting down or reconnecting the water supply. 15. Payment shall be processed upon satisfactory completion, inspection <(>,<)> and certification of the work in accordance with the approved terms of the purchase order. 16.The entire job shall be completed within the agreed timeframe and to the satisfaction of the PSO Engineer-in-Charge.					