



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	2
RFQ No	AD-19941NZ	
DATE	25.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017980

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services for Installing Refrigerant Pipes at 6th floor CCO room and New AC Installing in Call Center PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Refrigerant Kit</u> Refrigerant Kit (Copper pipe 5/8" x 3/4" , separate Insulation aero flex 5/8" <(>&<) 3/4" , wrapping tape , Cable ties Etc...) for 6th floor PSO House.	<u>PSO House</u>	<u>EA</u>	100		
2	<u>Control Wire</u> Control Wire Copper 1.5mm x 3 core CU PVC PVC Flexible Pakistan Cable or Equivalent for 6th floor PSO House.	<u>PSO House</u>	<u>M</u>	30		
3	<u>Services for Installing Refrigerant Kit</u>	<u>PSO House</u>				
3.01	<u>Miscellaneous services</u> -Providing services for Installation of air conditioner at 6th floor PSO House. -Scope of work includes installation of air conditioner with concealed wiring of refrigerant pipe and drain pipe. -Also cutting of concrete wall with electrical grinder 2" x 2" x 3' and 1.5" x 1.5" x 8'. includes 70rft refrigerant kit with copper pipe 5/8" x 3/4" 22-gauge muller (5kg and 3kg) aero flex insulation with wrapping tape and control wire. -Complete job in all respect with electrical connection and laying power cables, repairing of wall, painting and all other misc. works includes.		<u>JOB</u>	2		
4	<u>Refrigerant Kit</u> Refrigerant Kit (Copper pipe 5/8" x 3/4" , separate Insulation aero flex 5/8" <(>&<) 3/4" , wrapping tape , Cable ties Etc...)	<u>PSO House</u>	<u>EA</u>	125		
5	<u>Air Conditioner 2 ton</u> Cooling Capacity: 2.0 Ton (24,000 BTU) Heating Capacity: 25,500 BTU (Heat Pump) Extreme Performance: Stable Operation up to 65°C (T3 Technology) Key Technologies: Consumption Control Expert, 15s Instant Cooling, 1.2A Energy Save	<u>PSO House</u>	<u>EA</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	2
RFQ No	AD-19941NZ	
DATE	25.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017980

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services for Installing Refrigerant Pipes at 6th floor CCO room and New AC Installing in Call Center PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
6	Air Flow: 1150 m ³ /h Refrigerant: R32 (1300g) Power Supply: 1 Phase, 230V, 50Hz Smart Features: WiFi, Self-Clean, Turbo, Eco, 4-Way Auto Swing <u>Services for Installing Refrigerant Kit</u> <u>PSO House</u>					
6.01	<u>Miscellaneous services</u> <u>JOB</u> -Providing services for installation of concealed refrigerant kit Copper pipe 5/8" x 3/4", Muller, 22 Gauge weighing: 5kg and 3 kg Insulation Make Aero Flex, Rapping tape, control wire 1.5mm x 3 core Pakistan Cable at 1st floor customer services at PSO House. -Scope of work includes: Survey the site and provide execution layout for approval. -Laying of refrigerant pipe with control wire (complete wrap kit) from Indoor unit point to outdoor unit point through cable tray and proper conduits with saddles as per drawing. -Core cutting 15inch in CC roof slab on each floor Electrical connections from outdoor unit to DB 2.5mm x 3 Core Make Pakistan Cable. -Channels and conduits to properly encase the pipes. -Dissenting and re fabrication of wooden panels at dispensary area. -Wall repairing and painting Holding nitrogen pressure for testing of Installed refrigerant pipes. -22g Refrigerant Pipe. -High Quality Insulation (Aero flex or equivalent) Separate Insulations for return and suction line. Scaffolding platform will be used for work. -PPEs and Certified Tools for execution of job.			125		