



SAP No 6100018380

QUOTATION REQUIRED

BY
(Time)

Title: Services required for replacement of ACB in LT panel at Chakpirana Depot.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Replacement Charges</u>	<u>Chakpirana (Depot)</u>				
1.01	<u>Bolting/Unbolting of pipe joints</u> Installation, testing and commissioning of 1250 A TP ACB 65 KA in the existing panel complete in all respect and to the entire satisfaction of Engineer Incharge. The work includes but no limited to: Replacement and modification of Control Wiring for installation of ACB as per requirement. Dismantling and Removal of old ACB safely complete in all respect and shifting the same to site store as per instructions of Engineer Incharge.Necessary modifications in panel for fixing of ACB (if required). It is a turn key replacement job and contractor all provide all material and means, tools and tackles for successful replacement of the ACB as per site requirement. Transportation Mobilization and demobilization are included.		<u>EA</u>	1		
2	<u>ELEC CIRCUIT BREAKER 25A FOUR POLE</u> Supply and installation of 1) Air Circuit Breaker 3 Pole, 65K, 1250 ampere. 2) UVT 220V 3) Shunt 220V with complete accessories UVT and Shunt should be compatible to operate with supplied Air circuit breaker. Approved make and Model suitable to fix in existing LT panel at Chakpirana Depot. ===== NOTE: Bidder to submit technical brochure of ACB etc. along with the tender. Bidders are advised to visit	<u>Chakpirana (Depot)</u>	<u>EA</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	2
RFQ No	OP-20045NZ	
DATE	25.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018380

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services required for replacement of ACB in LT panel at Chakpirana Depot.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	site to see the existing ACB/panel before quoting to understand exact scope of work and if any modification is required it will be responsibility of the contractor. Work Completion time is 30 days after issuance of work Order. ===== Terms and conditions: a) All rates shall include duties, taxes, levies and transportation charges. b) Sales Tax Invoice shall be provided by contractor for supplied material. c) All installation shall be done as per satisfaction of Engineer Incharge. d) Contractor shall provide 1 year warrantee of the supplied material. e) Contractor shall restore the site at its original condition after completion of respective jobs. Clearing of debris would also be the responsibility of contractor. f) Contractor shall rectify any damage caused during work to PSO property. g) Contractor shall strictly adhere and comply with the HSE policy. No compromise would be allowed on HSE during works. Contractor shall arrange PPEs (Personal Protective Equipment) and ensure that staff wear the PPEs during execution of work. h) Prior Approval must be taken for all material to be supplied before commencement of works. Sample to be provided if required / asked by the concerned Engineer. i) If contractor fails to complete work within time, a penalty of 0.01% per day to max 10 % of work order amount will be deducted from his bill.					