



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	AD20124SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018777

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services required for waterproofing for stopping water seepages at PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Water Proofing</u>	<u>PSO House</u>				
1.01	<u>Water Proofing Works (Sft)</u> Services required for chemical water proofing and heat resistance at CEO side and Cooling tower side with following services: 1 Mega Water Guard # Primer Mega Water Guard polyurethane based elastomeric liquid water proofing coating used for sealing and protecting concrete and masonry substrates against water, dampness and seepage with a long-lasting, semi-smooth, decorative Blue finish. . 2 Mega Water Guard # Base Mega Water Guard polyurethane based elastomeric liquid water proofing coating used for sealing and protecting concrete and masonry substrates against water, dampness and seepage with a long-lasting, semi-smooth, decorative Blue finish. 3 Mega Water Seal Pro MEGA WATER SEAL Pro is a complete user friendly cementations waterproofing system, consisting of two component factory blended package in a strict quality control environment, to ensure optimum results after use. The two components are `mortar based on cements, fine- grain aggregates with special additives and synthetic polymers in water dispersion. After curing it forms a flexible layer impermeable to CO2 S02/ Equivalent chlorides and sulphates. 4 Mega Mesh Np-721/ Equivalent 5 Mega Mesh FG-720/ Equivalent Surface cleaning with brush. Apply mega water seal pro on critical areas. 1st coat of Mega water guard base. Apply Mega Mesh Np-721/	<u>SFT</u>	5,100			



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	AD20124SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018777

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services required for waterproofing for stopping water seepages at PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Equivalent. Apply will Critical area along with Mega water guard Base. Apply Mega Mesh FG-720/ Equivalent on complete Surface. Final top coat of Mega water guard Bas. Job includes: 1. Application of polyurethane based primer. 2. Application of fiber glass mesh (same as sample in PSOH). 3. Final coating of polyurethane based waterproofing. Job includes: - Removal of bitumen from old joints and Scrapping on Surface. Grinding on Surface. Surface cleaning with brush. - Scrapping of coating to reveal base concrete/screed free from loose substrate. - Insertion of backer rod in the joint. - Filling of expansion joint with elastomeric bond using sealant application gun. (as per sample) TERMS AND CONDITIONS: 1) All direct/indirect cost of material, services, transportation required to carry out the activity is included in this item 2) Contractor will provide Sales & Service Tax Invoices with Annex-C form with the bill. 3) Acceptance of the equipment / materials is subjected to inspection by PSO representatives. 4) All materials should be brand new, box packed and from fresh stock. 5) Contractor will utilize skilled manpower for the execution of complete Project. Manpower should be provided with required PPEs, overalls, and identification by the contractor. 6) Contractor to submit work execution methodology for PSO approval before start of job. 7) Scope of work and/or Quantity(is) of any items can be changed according to requirement of PSO. (As per sample)					



3	OF	3
RFQ No	AD20124SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018777

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	03.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: Services required for waterproofing for stopping water seepages at PSO House.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	8) The quantity and area might be changed as per PSO requirement. The job includes material and service charges. 9) Contractor to submit work execution methodology for PSO approval before start of job. 10) Contractor shall be responsible to rectify any damage occurred to PSO property during execution of work without charging any cost to Pakistan State Oil House. 11) The timeline of execution of the complete job is 30 days after the issuance of Purchase Order					