



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	OP-20151NZ	
DATE	27.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018807

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)


06.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Existing Radiator of 500 kVA DG Set with Heavy-Duty Copper Radiator at PSO Depot Tarujabba

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>S/I of radiator for 500KVA DG set</u>	<u>Tarujabba</u>				
		<u>(Depot)</u>				
1.01	<u>DG SET SERVICES</u> Supply, Installation, Testing & Commissioning of complete Heavy-Duty Copper Radiator Assembly, including top and bottom tanks, radiator core of 48" x 26" x 6 Rows, manufactured using heavy-duty copper tubing and copper fins, suitable for Cummins QSX 15-G8 engine of 500 kVA DG Set, coupled with Siemens 1-FC2 355-4 alternator. The scope shall include removal of existing radiator, installation of new radiator, necessary fittings/mountings, coolant connections, flushing/descaling of the cooling system, coolant filling, testing for leakage, and trial operation of the DG set to ensure satisfactory cooling performance. NOTE: The Radiator must be fully compatible with the Cummins QSX 15-G8 engine of 500 kVA DG Set, coupled with Siemens 1-FC2 355-4 alternator in all aspects.		<u>JOB</u>	1		
1.02	<u>Transportation / Labour Charges</u> Transportation and Labour Charges for shifting/transportation of the new radiator assembly to site and installation of front-mounted radiator after dismantling of the existing radiator assembly and allied accessories, including all required rigging/rigger activities, lifting, handling and positioning. Scope shall also include reassembling and refitting of all dismantled parts, accessories, connections and fittings after replacement of the radiator assembly, filling/connection of coolant, necessary adjustments, testing and re-commissioning of the DG Set with and without load, and ensuring satisfactory operation of the unit to the satisfaction of the Site Engineer. Warranty: The supplied and installed Heavy-Duty Copper Radiator Assembly shall be warranted for a minimum period of 12 (Twelve) months from the date of successful installation and commissioning against any defects in material, workmanship, manufacturing, leakage, tube/fin failure, soldering/brazing defects, or any other defect attributable to the supplier/manufacturer or installation. During the warranty period, the Contractor/Supplier shall, at no		<u>JOB</u>	1		



SAP No 6100018807

[illegible]



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	OP-20151NZ	
DATE	27.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018807

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

06.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Existing Radiator of 500 kVA DG Set with Heavy-Duty Copper Radiator at PSO Depot Tarujabba

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	09) Penalty Clause: Penalty in case of late delivery will be imposed as a. A penalty at the rate of 0.1% of the total value of the undelivered quantity per day of delay shall be levied, subject to a maximum of 10 % of the value of the work order. b. Calculation: Penalty = (Value of Undelivered Quantity) × (Penalty Rate per day) × Number of days delayed).					