



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 1      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Location                | Unit              | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-------------------|-----|-------------------|---------------|
| 1     | <b><u>Demolition</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | <b><u>PSO House</u></b> |                   |     |                   |               |
| 1.01  | <b><u>Demolition Work (JOB)</u></b><br>Demolition and dismantling of existing infrastructure including: 1.<br>Masonry walls<br>2. Doors<br>3. False ceiling<br>4. All kind of wiring<br>5. Roller blinds.<br>6. Ceiling accessories etc.<br>7. Reinstalling of fire alarm and public address system equipment on the roof with appropriate anchoring wherever needed.<br>Covered area : 1770 sft approx.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |                         | <b><u>JOB</u></b> | 1   |                   |               |
| 2     | <b><u>Partition Works</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <b><u>PSO House</u></b> |                   |     |                   |               |
| 2.01  | <b><u>Cement Board Partition Work (Sft)</u></b><br>Cement board partition wall with 100mm thick stud partition, consisting of GI sheet (22 swg) internal framing of approved section, 12mm thick cement board fixed on both sides of frame, including all hardware, fiber tape on sheet joints, metal tape on edges, etc. including making openings for HVAC ducts and cable trays etc. above 9' height. The framing will made in 2 ft x 2 ft grid, and cement board will be screwed. Complete in all respect as per drawing and instruction of PSO Admin team. The partition will be made mostly of full floor height and will include filling of sound proofing material (PU Foam sprayed) between the cement boards. Areas where such partitioning is made above block masonry, proper alignment is to be ensured with both sides of masonry (plaster level). The job includes creating grooves wherever required as per design attached with the bid. |                         | <b><u>SFT</u></b> | 422 |                   |               |
| 2.02  | <b><u>Glass Partition Works (Sft)</u></b><br>Wooden Glass Partition:<br>Providing and fixing custom composite partition walls strictly as per the provided 3D reference, featuring a structural framework of 2" x 3" solid Teak Wood dividers running both vertically and horizontally. The work entails the integration of premium Teak Wood ply pressed on both sides on a 12 mm thick MDF sheet within the designated solid grid                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                         | <b><u>SFT</u></b> | 171 |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 2      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Location                | Unit              | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-------------------|-----|-------------------|---------------|
| 2.03  | sections and 13.14 mm thick double-glazed laminated glass partitions (comprising 6 mm clear tempered glass, a 1.14 mm PVB interlayer, and 6 mm clear tempered glass) within the transparent sections, secured with matching solid teak wood beading. The item rate shall encompass complete surface preparation, the application of a high-quality Polyurethane (PU) based polish finish on all exposed wooden surfaces, and all necessary concealed hardware, adhesives, sealants, and skilled labor required to ensure absolute verticality, structural rigidity, and seamless joinery, complete in all respects to the full satisfaction and approval of the Admin Team.<br><b><u>Glass Partition Works (Sft)</u></b>                                                                                  |                         | <b><u>SFT</u></b> | 90  |                   |               |
| 3     | Providing and fixing glass partition walls featuring a structural framework of solid Teak Wood dividers arranged both horizontally and vertically. The work entails the supply and installation of 12 mm thick tempered glass partitions securely integrated within the wooden grid using matching teak wood beading. The item rate shall cover complete surface preparation, the application of a premium Polyurethane (PU) based polish finish on all exposed wooden framework, along with all necessary concealed hardware, vibration-dampening padding, architectural sealants, and skilled labor required to ensure exact verticality, structural rigidity, and seamless joinery, complete in all respects to the full satisfaction and approval of the Admin Team.<br><b><u>Carpentry Works</u></b> | <b><u>PSO House</u></b> |                   |     |                   |               |
| 3.01  | <b><u>Furniture Polishing Works (EA)</u></b><br>Polishing of existing door in place in lobby area, stores, AHU rooms, washrooms, pantry and janitor closets. The rates should be quoted for polishing of one door panel of 3.5 ft x 8ft on both sides. Qty will be double for double doors of AHU room. The rates also include replacement of wooden beading where required with matching polish.                                                                                                                                                                                                                                                                                                                                                                                                         |                         | <b><u>EA</u></b>  | 1   |                   |               |
| 3.02  | <b><u>Wall Cladding Works (Sft)</u></b><br>HIGH PERFORMANCE BAMBOO WALL PANELS 1.2m*3.1m*8mm, density 0.8 HAVING PROVISION FOR LIGHT FIXTURE; WITH an offset of 3" from the wall. To be hoisted using a 1" by 2" rough wood frame with 1/2 in the Marine Ply at the back to make the core; Bamboo wall panel shall be pasted on top of                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                         | <b><u>SFT</u></b> | 400 |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 3      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Location                | Unit              | Qty   | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-------------------|-------|-------------------|---------------|
| 4     | it With appropriate certified cladding system. Complete in All Respect.<br><b><u>Flooring Works</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <b><u>PSO House</u></b> |                   |       |                   |               |
| 4.01  | <b><u>Rigid Core Flooring</u></b><br>Providing and laying best quality approved rigid core flooring of matt finish, anti-slip to be laid over existing floor as specified by architect/ engineer on-site including floor preparation, finishing and cleaning etc laid in a pattern. Samples & tile-cutting drawings are to be approved by engineer/ architect. Complete in all respects as shown in drawings and as directed by PSO Admin team.                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                         | <b><u>SFT</u></b> | 750   |                   |               |
| 4.02  | <b><u>UPVC Skirting (Rft)</u></b><br>P/f of high-quality PVC skirting 4" high & 1/2" thick complete in all respects approved color/texture, as per drawings, specifications, and as directed by the engineer/ architect. Job includes installation of GI angles along the façade for skirting support.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                         | <b><u>RFT</u></b> | 200   |                   |               |
| 4.03  | <b><u>Rigid Core Flooring</u></b><br>Carefully remove the existing wooden flooring without causing any damage so that it can be refixed later. The work includes providing and laying a 2mm Jumbolon sheet beneath the flooring, complete with refixing, alignment, finishing, and cleaning, in accordance with the drawings and as directed by the PSO Admin team. Complete in all respects.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                         | <b><u>SFT</u></b> | 900   |                   |               |
| 5     | <b><u>Ceiling Works</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | <b><u>PSO House</u></b> |                   |       |                   |               |
| 5.01  | <b><u>Gypsum Ceiling Works (Sft)</u></b><br>Providing and installing a 12 mm thick gypsum board false ceiling as per the approved ceiling layout. The scope of work includes supplying and fixing a concealed galvanized iron (GI) suspension system comprising adjustable hangers, primary main runners, and secondary furring channels securely anchored to the structural soffit. The 12 mm gypsum ceiling boards shall be secured to the metal framework using appropriate drywall screws. The quoted rate shall encompass all jointing, taping, and the application of joint filler compound to achieve a perfectly flush, level, and seamless surface ready for final painting. The rate is strictly inclusive of making all necessary cutouts for light fittings, AC diffusers, smoke detectors, and access panels, along with all hardware, scaffolding, and skilled labor required to complete the |                         | <b><u>SFT</u></b> | 1,770 |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 4      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Location                | Unit              | Qty   | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-------------------|-------|-------------------|---------------|
| 5.02  | installation in all respects to the full satisfaction and approval of the Admin Team.<br><b><u>Gypsum Ceiling Works (Sft)</u></b><br>Wooden Veneer Ceiling Works:<br>P/F in position suspended ceiling consisting of approved wooden framework with wooden hangers and 12mm MDF sheets laminated with natural wood veneer, fixed to the framework with all necessary hardware and accessories. Ceiling shall be finished with approved clear polish/melamine finish, including surface preparation, edge finishing, groove detailing (where required), cutting of openings for light fixtures, AC diffusers/cassettes, access panels, scaffolding, wastage, and all ancillary works complete in all respects. |                         | <b><u>SFT</u></b> | 150   |                   |               |
| 5.03  | <b><u>Access Panels on Gypsum Ceiling</u></b><br>Providing and fixing of access panels in gypsum ceiling of approved quality and finish.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                         | <b><u>EA</u></b>  | 5     |                   |               |
| 5.04  | <b><u>Corian Works (Sft)</u></b><br>Supply of customized planter made of corian with smooth finish approved color and design as per drawings. Complete in all respect.<br>Size: width 4'-6" x 2'-6" (2'-4" depth)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                         | <b><u>SFT</u></b> | 22    |                   |               |
| 6     | <b><u>Paint Works</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <b><u>PSO House</u></b> |                   |       |                   |               |
| 6.01  | <b><u>Paint Works (Sft)</u></b><br>Plastic emulsion paint (on ceiling) 3 coats (washable paint)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                         | <b><u>SFT</u></b> | 2,820 |                   |               |
| 6.02  | <b><u>Paint Works (Sft)</u></b><br>Deco paint on internal facade with approved color and brand.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                         | <b><u>SFT</u></b> | 1,000 |                   |               |
| 7     | <b><u>HVAC Works</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | <b><u>PSO House</u></b> |                   |       |                   |               |
| 7.01  | <b><u>HVAC Ducting Works (Sft)</u></b><br>HVAC Ducting Works (24 swg):<br>Supply, fabrication, installation of machine-GI sheet metal duct work (galvanized 24 swg) for supply, return, fresh & exhaust air complete in all respects including plenums, splitter dampers, guide vanes, flexible duct connector, access door, transformation, plenums chambers<(>,<(>)> wooden frame, anchors as per SMANCA standards along with supports <(>)> hangers and sound liners complete in all respects ready to                                                                                                                                                                                                     |                         | <b><u>SFT</u></b> | 200   |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 5      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Location                | Unit              | Qty   | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-------------------|-------|-------------------|---------------|
| 7.02  | operate as per drawings, instruction and approval of PSO Admin Team.<br><b><u>HVAC Insulation Works (Sft)</u></b><br>Supply and installation of 2inch thick, Rockwool insulation of 50KG/m3 with wire mesh reinforcement for MS sheet metal ducts of kitchen exhaust air.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                         | <b><u>SFT</u></b> | 250   |                   |               |
| 7.03  | <b><u>Installation of Air Devices</u></b><br>SUPPLY, INSTALLATION OF ALUMINUM FABRICATED, POWDER COATED AIR DEVICES FOR SUPPLY, RETURN, EXHAUST & FRESH AIR. INCLUDING FRAMING, HANGERS SUPPORTS AND OTHER ACCESSORIES ETC. COMPLETE IN ALL RESPECTS READY TO OPERATE AS PER INSTRUCTION OF CONSULTANT. NOTE: SFT = SQ IN.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                         | <b><u>SFT</u></b> | 1,700 |                   |               |
| 8     | <b><u>Electric Works</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | <b><u>PSO House</u></b> |                   |       |                   |               |
| 8.01  | <b><u>Wiring (DB to Workstation) (EA)</u></b><br>Wiring form DB to Workstation Technology Box - 3 x 2.5 mm Circuit wiring from respective distribution board to Technology Box (first outlet) using following Stranded/flexible Copper Conductor, color coded wire in 25 mm dia. PVC conduit under floor. Complete with all accessories as shown in the drawings. Item include floor/wall cutting if required as per site conditions. The first point will have a dedicated pull box installed in floor for connection to adjacent set of work station via connector strips. Junction boxes will be installed on workstation modesties for concealing connector strips for parallel workstation connections. Connections for switch socket to switch socket on a single workstation is included in this rate. |                         | <b><u>EA</u></b>  | 4     |                   |               |
| 8.02  | <b><u>Point Wiring (2.5mm) (EA)</u></b><br>Wiring for Socket Point to Point - 3 x 2.5 mm - Wiring for 13A Multi Pin / 15A 3-Pin Switch Socket units from outlet to outlet using following Stranded/Flexible Copper Conductor, color coded wires in 25 mm dia. PVC conduit under floor. Complete with all accessories as shown in the drawings. Wiring on same workstation shall be counted as one. Item include floor/wall cutting if required as per site conditions.                                                                                                                                                                                                                                                                                                                                        |                         | <b><u>EA</u></b>  | 15    |                   |               |
| 8.03  | <b><u>Wiring (Gangswitch to First Light Point)</u></b><br>Gang Switch to first light point - 1 x 2.5mm, 2 x 1.5mm Wiring for light point from switch board to first light point using single core PVC insulated, Stranded Copper Conductor, color coded wires of 1.5 Sq.mm for                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                         | <b><u>EA</u></b>  | 10    |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 6      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)


10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Location                | Unit             | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------------|-----|-------------------|---------------|
| 8.04  | phase, 2.5 Sq.mm for common neutral and 1.5 Sq.mm for common earth in 25mm of PVC conduit / channel / cable tray including complete with all accessories as shown in the drawings.<br><b><u>Wiring (Light Point to Point) (EA)</u></b>                                                                                                                                                                                                                                                                                                                                                                   |                         | <b><u>EA</u></b> | 20  |                   |               |
| 8.05  | Light point to point wiring - 1 x 2.5mm, 2 x 1.5mm - Wiring for light point to point using single core PVC insulated, Stranded Copper Conductor, color coded wires of 1.5 Sq.mm for phase, 2.5 Sq.mm for common neutral and 1.5 Sq.mm for common earth in 25mm size of PVC conduit / channel / cable tray complete with all accessories as shown in the drawings.<br><b><u>CAT6 Wiring (Point Wiring) (EA)</u></b>                                                                                                                                                                                       |                         | <b><u>EA</u></b> | 14  |                   |               |
| 8.06  | Category 6, UTP Cables (3M Certified), for data communication system at local workstations in 25mm dia. PVC conduits under floor as shown in the layout plan and schematic diagrams. Work includes all terminations <>, <> management and tagging at both ends. The vendor will leave additional 3 M cable on each point for future extension. The payment will be made on number of points for workstation, Wifi, Printers, IP phones etc. Contractor should take the average length for rates based on drawings attached.<br><b><u>Access Point Installation Works (EA)</u></b>                        |                         | <b><u>EA</u></b> | 2   |                   |               |
| 9     | <b><u>Furniture Works</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | <b><u>PSO House</u></b> |                  |     |                   |               |
| 9.01  | <b><u>Furniture Polishing Works (EA)</u></b><br>The work includes removing the existing upholstery from the wooden 2-seater sofa and replacing it with new, high-quality upholstery fabric. New foam padding and cushioning will be installed. The wooden frame will be inspected, cleaned, and polished with a premium wood finish to restore its appearance, protect the surface, and enhance its durability. The completed work will provide the sofa with a refreshed look, improved comfort, and a polished, long-lasting finish. The fabric and polish will be as per the choice of PSO Admin team |                         | <b><u>EA</u></b> | 2   |                   |               |
| 9.02  | <b><u>Furniture Polishing Works (EA)</u></b><br>The work includes removing the existing upholstery from the wooden                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                         | <b><u>EA</u></b> | 4   |                   |               |



SAP No 6100017505

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Location                | Unit             | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------------|-----|-------------------|---------------|
|       | 2-seater sofa and replacing it with new, high-quality upholstery fabric.<br>New foam padding and cushioning will be installed. The wooden frame will be inspected, cleaned, and polished with a premium wood finish to restore its appearance, protect the surface, and enhance its durability.<br>The completed work will provide the sofa with a refreshed look, improved comfort, and a polished, long-lasting finish. The fabric and polish will be as per the choice of PSO Admin team. |                         |                  |     |                   |               |
| 10    | <b><u>Light</u></b><br>DOWN LIGHTS<br>Down Light with 10W , as approved by architect, As approved by architect. - Supply, Installation, testing and commissioning of the lighting fixture including all accessories like electronic ballast, lamps<(>, <(> mounting arrangements etc. Complete in all respects.<br>Mounting accessories shall be provided by contractor like mdf wooden box (where needed), screws, nuts, bolts, strings etc.                                                | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 31  |                   |               |
| 11    | <b><u>Light</u></b><br>PENDENT LIGHT<br>Pandent Light With 20W LED Light As approved by architect. Supply, Installation, testing and commissioning of the lighting fixture including all accessories like electronic ballast, lamps, mounting arrangements etc. Complete in all respects. Mounting accessories shall be provided by contractor like screws, nuts, bolts, strings etc.                                                                                                        | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 1   |                   |               |
| 12    | <b><u>Light</u></b><br>FANCY LIGHT<br>As per 3D given.                                                                                                                                                                                                                                                                                                                                                                                                                                       | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 2   |                   |               |
| 13    | <b><u>Light</u></b><br>CONSEALED PROFILE LIGHTS Profile lights 1 inch wide As approved by PSO Admin Team.<br>- Supply, Installation, testing and commissioning of the lighting fixture including all accessories like electronic ballast, lamps, mounting arrangements etc. Complete in all respects. Mounting accessories shall be provided by contractor like screws, nuts, bolts, strings etc.                                                                                            | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 62  |                   |               |
|       | Note: EA = RFT                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                         |                  |     |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 8      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                   | Location         | Unit      | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|-----------|-----|-------------------|---------------|
| 14    | <u>Light</u><br>CONSEALED PROFILE LIGHTS Profile lights 2 inch wide As approved by PSO Admin Team.<br>- Supply, Installation, testing and commissioning of the lighting fixture including all accessories like electronic ballast, lamps, mounting arrangements etc. Complete in all respects. Mounting accessories shall be provided by contractor like screws, nuts, bolts, strings etc.<br>Note: EA = RFT | <u>PSO House</u> | <u>EA</u> | 85  |                   |               |
| 15    | <u>Light</u><br>LINEAR LED LIGHT<br>Linear Led Light with 40W LED LIGHT As approved by architect.<br>- Supply, Installation, testing and commissioning of the lighting fixture including all accessories like electronic ballast, lamps, mounting arrangements etc. Complete in all respects. Mounting accessories shall be provided by contractor like screws, nuts, bolts, strings etc.                    | <u>PSO House</u> | <u>EA</u> | 4   |                   |               |
| 16    | <u>Light</u><br>CUSTOMIZED LED<br>LIGHT Customize LED Light With 80W LED Light for Rooms As present at PSO House.<br>- Supply, Installation, testing and commissioning of the lighting fixture including all accessories like electronic ballast, lamps, mounting arrangements etc. Complete in all respects. Mounting accessories shall be provided by contractor like screws, nuts, bolts, strings etc     | <u>PSO House</u> | <u>EA</u> | 2   |                   |               |
| 17    | <u>LOUVER FAN 14"</u><br>Supply and installation of 2'x2' false ceiling louver fan (Royal or equ.) operated via remote control. Rate is inclusive of all concealed wiring, mounting within the ceiling grid, and testing, complete in all respects.                                                                                                                                                          | <u>PSO House</u> | <u>EA</u> | 2   |                   |               |
| 18    | <u>Gang Switch</u><br>Two Gang one way 10A Switch , including 16 SWG MS Powder Coated back boxes, flush with wall as shown in drawings and details.                                                                                                                                                                                                                                                          | <u>PSO House</u> | <u>EA</u> | 3   |                   |               |
| 19    | <u>Gang Switch</u>                                                                                                                                                                                                                                                                                                                                                                                           | <u>PSO House</u> | <u>EA</u> | 3   |                   |               |





# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 9      | OF         | * |
| RFQ No | AD-19822AS |   |
| DATE   | 24.07.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Location                | Unit             | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------------|-----|-------------------|---------------|
| 20    | Four Gang one way 10A Switch , including 16 SWG MS Powder Coated back boxes, flush with wall as shown in drawings and details.<br><b><u>Switch socket outlet</u></b>                                                                                                                                                                                                                                                                                                        | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 14  |                   |               |
| 21    | 13A, Simplex multi-pin switch Socket Unit, including 16 SWG MS Powder Coated back boxes, flush with wall as shown in drawings and details.<br><b><u>ELECTRIC BOARD W/BOX</u></b><br>Technology Box<br><br>Supply and installation of large size techology box with space of 4 face plates.<br>The box should include:<br>1x Multi Light Plug 13A USB & Type C Slots 2x 6 in 1 universal power sockets 1x Information Duplex outlet Face plate with 2No. CAT-6 RJ-45 socket. | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 8   |                   |               |
| 22    | <b><u>Face Plate</u></b><br>Information Duplex outlet Face plate with 2No. CAT-6 RJ-45 socket for Data communication system / Voice including shuttered click-ins, labels, jacks etc. Complete in all respects with cable identification tags.                                                                                                                                                                                                                              | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 2   |                   |               |
| 23    | <b><u>Sofa 2 seater</u></b><br>2-Seater Size: 1719W x 902D x 881H (mm)<br>Upholstery: Brown Air Leatherette Finish<br>Structure: Plywood<br>Legs: Black Chrome Finish                                                                                                                                                                                                                                                                                                       | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 1   |                   |               |
| 24    | <b><u>Sofa Single Seater</u></b><br>1-Seater Size: 1125W x 902D x 881H (mm)<br>Upholstery: Brown Air Leatherette Finish<br>Structure: Plywood<br>Legs: Black Chrome Finish                                                                                                                                                                                                                                                                                                  | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 2   |                   |               |
| 25    | <b><u>Office Visitor Chair</u></b><br>Chair Size: 23W x 23D x 37H (inches)<br>Inner Upholstery<br>Foam: Supreme<br>Outer Back: Waffle Fabric<br>Base: wooden legs                                                                                                                                                                                                                                                                                                           | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 6   |                   |               |
| 26    | <b><u>Double Leaf Door</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                              | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 2   |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |    |
|--------|------------|----|
| 10     | OF         | 11 |
| RFQ No | AD-19822AS |    |
| DATE   | 24.07.2026 |    |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Location                | Unit             | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------------|-----|-------------------|---------------|
| 27    | <p>Providing and fixing a 9' x 9' main entrance assembly featuring a frameless glass door and fixed glass partitions integrated with solid teak wood framing. The scope of work encompasses the supply and installation of a 5' x 8' frameless glass door, equipped with complete premium hardware including a concealed floor spring machine, stainless steel patch fittings, door lock, and a 3.5 ft long door handle. The surrounding side and top areas shall consist of fixed glass partitions secured within a framework of solid Teak Wood dividers arranged horizontally and vertically. The quoted rate shall cover complete surface preparation and the application of a high-quality Polyurethane (PU) based polish finish on all exposed wooden dividers, along with all necessary sealants, adhesives, and skilled labor required to ensure smooth door operation, absolute verticality, and structural rigidity, complete in all respects to the full satisfaction and approval of the Admin Team</p> <p><b><u>Single Leaf Door</u></b></p> <p>SIZE: 3' x 8'</p> <p>LOCATION:<br/>Rooms.<br/>-</p> <p>P/f tempered swing glass door using 12mm clear glass with frosting film pasted without bubbles or anomalies, imported concealed floor door closers lg/new star or equivalent, 3 feet long S.S door handle on both side, door locks. Complete in all respects as per drawings, specifications and to the satisfaction of the consultant and engineer in charge. The specifications of door lock and handle is as per compliance sheet attached.</p> | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 2   |                   |               |
| 28    | <p><b><u>Sofa 2 seater</u></b></p> <p>2-Seater Size: 57.5W x 30D x 32H (inches)<br/>Upholstery: Sleek black leatherette Finish<br/>Frame: Wooden Frame</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 1   |                   |               |
| 29    | <p><b><u>Sofa Single Seater</u></b></p> <p>1-Seater Size: 35W x 30D x 32H (inches)<br/>Upholstery: Sleek black leatherette Finish<br/>Frame: Wooden Frame</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | <b><u>PSO House</u></b> | <b><u>EA</u></b> | 2   |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |    |
|--------|------------|----|
| 11     | OF         | 11 |
| RFQ No | AD-19822AS |    |
| DATE   | 24.07.2026 |    |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017505

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

10.08.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Renovation of CEO Secretariat, 9th floor, PSO House

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Location                | Unit              | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-------------------|-----|-------------------|---------------|
| 30    | <b><u>PLANTERS 24"</u></b><br>Round planters pots as per approved color and design as per drawing.<br>Material: Terrazo<br>Size: 16" dia & 14" height                                                                                                                                                                                                                                                                                                                                                    | <b><u>PSO House</u></b> | <b><u>EA</u></b>  | 13  |                   |               |
| 31    | <b><u>Large Dustbins</u></b><br>Supply of SS paper bins as per approved sample                                                                                                                                                                                                                                                                                                                                                                                                                           | <b><u>PSO House</u></b> | <b><u>EA</u></b>  | 10  |                   |               |
| 32    | <b><u>WINDOW ROLL-UP BLINDS</u></b><br>Provide and install in position roll-up window blinds of approved color and specifications, chain operated roller blind (protector or approved equivalent) with approved fabric screw on walls, including all hardware, wastage, lifting, cutting, fixing, scaffolding etc., complete as per drawing & instruction of the engineer.<br><br>Terms & Conditions:<br>Note: All the work done and task completed within 70 days, after the issuance of Service Order. | <b><u>PSO House</u></b> | <b><u>FT2</u></b> | 840 |                   |               |