



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	AM-19422AM	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018140

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: CONSTRUCTION OF PORTA CABIN FOUNDATION AT PSO AVIATION STATION NAWABSHAH AIRPORT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Contruction of Foundation</u>	<u>Nawab Shah</u>				
		<u>(Aviation)</u>				
1.01	<u>Demolition Work (JOB)</u> Dismantling of Floor, Wall, Tiles Etc. Dismantling / excavation of existing floor of any type (hard standing /pavers /cc floor/stone/bricks etc.) of max 1 ft thick as per site requirement and as per instruction of site engineer. Job includes removal, shiting of debris & surplus material to a suitable place outside the Station premises; shifting <(>&<) stacking of usable material (On proposed location) within the station premises and general cleaning of the site as per instruction of PSO's site engineer.		<u>JOB</u>	1		
1.02	<u>Stone Soling</u> "Providing and laying stone soling of approved quality and under floor including compacting, watering, levelling etc. Complete as per drawings and specification."		<u>M3</u>	12.000		
1.03	<u>Laying of CC 1:4:8 S.R. Cement</u> Providing/Laying of Lean Concrete CC 1:4:8 with SR cement for construction of hard standing and foundation of pumps and pipe supports using graded material including cost of work<(>,<) vibrating, leveling and curing as per PSO drawings / specifications (Cost of reinforcement is not included)		<u>M3</u>	6.000		
1.04	<u>Providing and laying 1:2:4 with SR cemen</u> "Providing and laying 1:2:4 with SR cement for construction of hard standing and foundation of pumps and pipe supports using graded material including cost of work, vibrating, leveling and curing as per PSO drawings / specifications (Cost of reinforcement is not included)"		<u>M3</u>	10.000		
1.05	<u>Providing and laying Tor steel reinforce</u>		<u>KG</u>	950.000		
1.06	<u>Providing and laying pavers</u> "Providing and laying precast concrete pavers of "TUFF LTD /ENVICRETE LTD" make and city type of size 200 mm x 100 mm x 80 mm thick laid in herring bone pattern and should have minimum compressive strength of 42 N/mm2 (7000psi minimum), to be laid over " thick compacted sand graded to BS-882 and voids to be filled by sand and finally pavers to be compacted with plate compactors. Above pavers to be laid in Drive way		<u>M2</u>	120		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	AM-19422AM	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018140

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: CONSTRUCTION OF PORTA CABIN FOUNDATION AT PSO AVIATION STATION NAWABSHAH AIRPORT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.07	and Parking area with voids to be filled with "khaka" properly watered and compacted by 10ton Roller. Red colour pavers shall be used to demarcate the lines for truck parking area for vehicles and around islands. " <u>Crane Services on Rental Basis</u> Providing Services of crane for removing of existing porta cabin. TERMS AND CONDITIONS: - Contractor should strictly follow the safety and security rules of PSO - Contractor's labour to follow Company's rules and procedures as well as HSE guidelines and safety procedures. - Contractor will provide Equipment and PPEs i.e., Safety Shoes, Gloves, Helmets, Goggles, Safety Harness, Safety Belts etc to his labour during execution of work. - All service, tools (nonferrous if required), first aid box, materials and transportation to be provided by contractor. - Payment will be made as per actual quantity of work done. - If the Contractor fails to complete the work within time stipulated, the Engineer Incharge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Work Order per day and subject to minimum 10% Value of P.O. - Contractor should maintain housekeeping of the worksite during progress of work and shall clear and remove all surplus materials and rubbish from site after completion of job as per instruction of Engineer Incharge. - The work will only be accepted after inspection and approval by the Engineer Incharge. - Work should be completed within 60 days of issuance of work order. - Quality is the prime concern of PSO, no compromise shall be made in this regard. Only first class approved quality material, workmanship and supervision will be utilized by the contractor which shall strictly conform to the WO/SO specification. - Only certified and trained operators and riggers are allowed to operate or assist with crane lifting. - Crane, lifting gear, and site conditions must be inspected and		<u>JOB</u>	1		



3	OF	3
RFQ No	AM-19422AM	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018140

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	22.09.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: CONSTRUCTION OF PORTA CABIN FOUNDATION AT PSO AVIATION STATION NAWABSHAH AIRPORT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	approved before use. - Lifting must not exceed the crane#s rated capacity. - A clear exclusion zone must be maintained; unauthorized personnel are not allowed near the lifting area. - Lifting shall be suspended during high winds, storms, or unsafe weather. - The contractor is responsible for damage or injury resulting from misuse, negligence, or violation of safety procedures. **All the work done and task completed within 60 days, after the issuance of SO**					