



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Rehabilitation of Washrooms & Pantries</u>	<u>Mehmood Kot (Inst.)</u>				
1.01	<u>Dismantling of Existing Civil Structure</u> Dismantling work of P.C.C / R.C.C kerb wall / floor/ pavement or any other structure unto the required level/ depth height. This job includes concrete cutting, dismantling of masonry/ concrete as per site requirements with required tools, stacking of useful material at site, removal of dismantled stuff and disposal of only unserviceable material outside of depot and housekeeping of the site complete in all respect and as directed by Engineer Incharge.		<u>M3</u>	10.000		
1.02	<u>Providing and laying 1:2:4 with SR cemen</u> P/L CONCRETE 1:2:4 Providing and laying 1:2:4 with S.R Cement specified strength approved quality 3/4" max: size graded crushed stone and fine aggregate sand of required properties including form work (installation <(>&<)> removal) mixing, transporting, placing<(>,<)> compacting, finishing and curing etc., complete in all respects as specified.		<u>M3</u>	18.000		
1.03	<u>Plain Plaster 3/4" thick</u> Providing and applying cement plaster 1/2" to 3/4" thick in 1:4 cement sand mortar beams, columns, ceiling, walls at any height i/c all corners, recesses, jams and joints of masonry, roughing the surfaces and cement slurry backing to all surfaces. on walls as directed by Engineer Incharge. This job also includes 6" wide heavy duty metal lath strip nailed at the joints of masonry and concrete structure and curing in all respect and as directed by Engineer incharge.		<u>M2</u>	40		
1.04	<u>Providing & Laying Matt Finish tiles</u> Providing & Laying Matt Finish tiles: Providing and laying matt finish porcelain/granite tiles as per approved size and shape and color by location incharge, of PRIME QUALITY in cement mortar 1:3 floor. The color of the floor tiles will be as decided by location incharge and final shade to be approved at time of installation. Job includes cutting of wall & floor as per site requirement, laying of tiles with dry bond filling joints with matching color grout / over 1:3 cement mortar upto required thickness and cutting tiles. including all leads and lifts, removal/stacking of surplus		<u>M2</u>	55		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	excavated stuff outside the Terminal as per site requirements. Note The slope of tiles to be maintained so that the water to be drained off in nearest drain. Dismantling of existing should also be done. <u>Providing & Laying Matt Finish tiles</u> Providing and laying glazed tiles color and size 24" x 12" Or as per approved size and shade by location incharge, of PRIME QUALITY in cement mortar 1:3 floor. The color of the floor tiles will be as decided by location incharge and final shade to be approved at time of installation. Job includes cutting of wall & floor as per site requirement, laying of tiles with dry bond filling joints with matching color grout / over 1:3 cement mortar upto required thickness and cutting tiles including all leads and lifts, removal/stacking of urplus		M2	110		
1.06	excavated stuff outside the Terminal as per site requirements. Note: Dismantling of existing should also be done. <u>Application of Emulsion destumper paint</u> Providing and applying 3 coats of polyvinyl distemper of approved make of required colour and shade including preparation of the base by rubbing the surface with carborundum stone of approved make paints on the entire surface, filling depressions with putty, cutting smooth finally with sand paper complete as per specification and as per instructions of Engineer Incharge.		M2	300		
1.07	Note: In all painting activities, old paint will be removed completely. <u>Applying two coats of weather shield pai</u> Providing and applying 2 coats of Weather Shield Paint of approved make paints of required colour and shade on plastered surfaces including preparation of the base by rubbing the surfaces applying primer coat of approved make on the entire surface, filling the depressions with putty, cutting the surface and rubbing smooth finally with sand paper complete as per specification.		M2	230		
1.08	Note: In all painting activities, old paint will be removed completely <u>Providing and laying solid brick masonry</u> Providing and laying 1st Class standard size brick masnoary of specified thickness set in 1:4 cement sand mortar. The job Include cleaning <(>&<)> provision of expansion joints and at least 7 days water curing		M3	2.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017049

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	07.07.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY %
Rs. _____ PO/DD NO. _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.09	of masnory to the satisfaction of Engineer incharge. Installation of UPVC Pipe Class D 4" PIPE UPVC 4" DIA Supply and installation of class B (6 bar or 87 lbs)4" dia uPVC pipe sleeves of approved make complete in all respect like joints<(>,<(> sealant<(>,<(> joints, Tees etc as per requirement embedded in floor or wall or cloned to walls or suspended from slab, cutting and fixing of pipe, provided of clamps, hangers, collars and supports, making requisite number of holes in walls, plinth and floor, cutting chases and embedding the pipe where directed etc. making good the same in C.C. 1:2:4 including the cost of cement mortar joints and providing pipes sleeves in walls, slabs, any excavation and backfilling if required and to the entire satisfaction of Engineer in-charge. Note: Dismantling of existing should also be done.		<u>M</u>	60		
1.10	3/4" PVC PLUMBING PIPE Providing & Fixing of Polypropylene Random (PPRC) of pipes of approved make for Cold and Hot Water Supply/Return Piping System includes the cost of all approved make fitting such as elbow, tee, union, adopter<(>,<(> etc., and all necessary accessories making system operational. The scope of works also include excavation, chiseling in wall, embedding, etc. and making good, including all HANGERS and Supports GALVANIZED (30MICRON) Laying of pipes as per site requirement and making connection of water supply pipes from exiting water supply main connections. Pressure Testing of all pipes up to 150 PSI All pipes to be jointed at site as per manufacturer recommendations etc. complete in all respect for satisfactory Operation at site as per approval and instructions of PSO Note: Dismantling of existing should also be done.		<u>M</u>	80		
1.11	1" PVC PLUMBING PIPE Providing & Fixing of 1"Dia Poly Propylene Random (PPRC) Pipe of approved make for Cold Water Supply/Return Piping System including the cost of all approved make fittings such as elbow, tee <(>,<(> union, adopter, etc, and all necessary accessories make system operational. The scope of works also include excavation, chiselling in wall<(>,<(> embedding etc and making good, including all HANGERS and Supports		<u>M</u>	80		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.12	GALVANIZED (30MICRON) Laying of pipes as per site requirement and making connection of water supply pipes from existing water supply main connections. Pressure Testing of all pipes upto 150 PSI All pipes to be jointed at site as per manufacturer recommendations etc. complete in all respect for satisfactory operation at site as per approval and instructions of PSO Engineer. Note: Dismantling of existing should also be done. Providing and fixing C.P. soap dishes		<u>EA</u>	7		
1.13	Providing & Fixing Soap dishes of approved design and make including all fixing material (Stainless steel). Providing and fixing Towel rail		<u>EA</u>	2		
1.14	Providing and Fixing of Towel Rail And Hangers of approved quality. Beveled edge mirror 5'-0 x 2'-0		<u>EA</u>	2		
1.15	Providing & Fixing Beveled edge mirror of approved make glass 6mm thickness of specified size and shape, Lasani wood back, brass clips, C.P screws fixed to wooden cleats. mounted on 1/8" thick plain asbestos sheet with C.P. brass screws 1" long. Providing and Fixing of Mirror Tray with 1" C.P brass screws and Rawal plug. Note: Dismantling of existing should also be done. Flush door with frame 2" x 5"		<u>M2</u>	25		
1.16	Providing and fixing of UPVC doors with frames, hooks<(>,<(>)> hinges, including all hardware and appropriate locking mechanism etc. compete in all respect as per satisfaction of engineer/location incharge. Note: Dismantling of existing should also be done. INSTALLATION FALSE CEILING		<u>SFT</u>	322.910		
1.17	Providing & Fixing with Plaster of Paris conventional FALSE CEILING of 1/2" thick slabs of approved design & pattern with all accessories i-e 14 SWG SS wire/Jute rops hangers, 12 SWG GI Hooks, clamps etc. Complete in all respects. Job also includes<(>,<(>)> filling of joints, finishing of surface with the provision of 1 to 2ft side border, as per PSO approved design etc with finishing of corners edges complete in all respects as per instructions of Location engineers. Providing and fixing Wash basin		<u>EA</u>	4		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	07.07.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ **PO/DD NO.** _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.18	<p>Providing and fixing Wash basin (Porcelain)</p> <p>Providing & Fixing white glazed Wash Basin of full size with all fittings and fixture a chrome plated waste,1-1/2" dia rubble plug with chain,1-1/2" dia bottle point trap with union, C.P. Brass tube connection ,1-1/2" dia C.P. Deluxe stop cock, basin mixer and brass nut complete with lining, jointing, etc. making requisite number of holes in floor and all for pipe connection and making good in cement Concrete (1:2:4:)as per directed by the Engineer Incharge.</p> <p>Note: Dismantling of existing should also be done.</p> <p><u>Providing and fixing Wash basin</u></p>		EA	4		
1.19	<p>Supply and installation of stainless-steel kitchen sink, single bowl type, manufactured from high-quality corrosion-resistant SS with matte finish with all fittings and fixture a chrome plated waste,1-1/2" dia rubble plug with chain,1-1/2" dia bottle point trap with union, C.P.Brass tube connection ,1-1/2" dia C.P. Deluxe stop cock, basin mixer and brass nut complete with lining, jointing, etc. making requisite number of holes in floor and all for pipe connection and making good in cement Concrete (1:2:4:)as per directed by the Engineer Incharge.</p> <p>Note: Dismantling of existing should also be done.</p> <p><u>Washroom Comode</u></p>		EA	2		
1.20	<p>"PROVIDING & FIXING WC Approved make best Quality with integral tread 19" clear opening as measured between flushing rims, C.I.Trap 4"dia 3 Gallons capacity low flushing cistern of same manufacturers Siphon fittings 1-1/2" dia C.I. warring pipe carried outside and bent vertically down ward, chrome plated brass tube connection 1/2" dia C.P. Brass stop cock, brass nut, lining jointing etc, complete with all fixture and including making requisite number of holes in walls and floor for pipe connection etc, and making good in cement concrete (1:2:4:) as per directed and approved of the Engineer Incharge.</p> <p>Providing and fixing Traps 4"dia of approved make including floor cutting, excavation and backfilling with PCC 1:2:4, joints formation including leak proof sealant as per requirement complete in all respect and as directed by Engineer Incharge. Note: Dismantling of existing should also be done."</p> <p><u>Washroom Comode</u></p>		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	07.07.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ **PO/DD NO.** _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>PROVIDING & FIXING INDIAN COMMODE</p> <p>The scope includes providing and fixing a high-quality Indian Type Squatting Pan (Orissa Pattern) of an approved make, complete with integrated footrests and a matching 4" diameter ceramic or C.I./P/S trap. The system shall be equipped with a high-level or low-level 3 Gallon flushing cistern, including all necessary siphon fittings, flush pipes, and 1/2" diameter C.P. brass stop cocks. Proper installation requires setting the pan at the correct floor level, ensuring a watertight seal within the sunken slab, and finishing the surrounding area with cement concrete (1:2:4) to meet the satisfaction and specifications of the Engineer In-charge. Providing and fixing-Traps 4"dia of approved make including floor cutting, excavation and backfilling with PCC 1:2:4, joints formation including leak proof sealant as per requirement complete in all respect and as directed by Engineer Incharge.</p>					
1.21	<p><u>Providing & Fixing of Exhaust fans</u></p> <p>Providing and fixing of 12" Dia Exhaust fans steel body with Louvers complete with making holes as may be required and to finish the surface suitable after installation and with all necessary connections complete in all respect.</p> <p>Note: Dismantling of existing should also be done.</p>		EA	8		
1.22	<p><u>Electrical Miscellaneous</u></p> <p>Supply and installation of instant electric geyser including all supports, pipes, fittings etc. of approved make, and specifications given below</p> <p>Wattage: 2 KW</p> <p>Maximum Voltage: 220V~50Hz</p> <p>Inner Tank: Enameled Coated Steel</p> <p>Capacity: 20 gallons</p> <p>Mounting: Vertical</p> <p>Automatic IC Ignition System, Over Heating Safety Device</p>		EA	2		
1.23	<p><u>Fixing of glazed Tiles / Marble tiles</u></p> <p>P<(>&<)>F of Marble</p> <p>Galaxy Granite Marble P/A 3/4"thick Granite Marble of Good quality <(> ,<)> with finishing surface for pantry, vanity area etc planter. Job</p>		FT2	140		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	07.07.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY % PO/DD NO. _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.24	includes cutting of wall & floor (existing tiles) as per site requirement. The job also includes filling joints with matching colour grout /over 2"th 1:3 cement: sand mortar up to required thickness <>&<> slopes, Dumping/stacking of Surplus excavated materials within a lead 02 km as per instructions. Electrical Miscellaneous		EA	2		
1.25	Supply, installation, and commissioning of an automatic hand dryer suitable for the washroom. The work covers electrical connection as per manufacturer specifications, proper mounting on the wall at standard height, and ensuring safe and efficient operation. All necessary fittings, fasteners, and supports required for secure installation are included. The hand dryer should comply with safety standards, provide adequate drying efficiency, and be durable for high-usage washroom environments. MUSLIM SHOWER WITH STOPCOCK		EA	4		
1.26	Providing and fixing of Muslim showers with stop cock of approved quality (SS). Civil Miscellaneous		SFT	430.500		
1.27	Supply, fabrication, and installation of modular wooden kitchen cabinets (Wall-mounted and floor-mounted units), manufactured from high-quality moisture-resistant MDF/plywood (minimum 16#18 mm thickness) with approved laminate finish, including complete carcass structure, internal adjustable shelves, drawers (where applicable), 6#8 mm back panel, PVC edge banding on all exposed edges, soft-close hinges and drawer channels, stainless steel/aluminum handles, catchers plinth/skirting for base units, and heavy-duty wall mounting brackets. Scope includes necessary cutouts for hob, plumbing, and electrical points; proper alignment, leveling, secure fixing to wall and floor with approved fasteners; silicone sealing where required; and complete finishing. Contractor shall provide all hardware, accessories, fittings, and labor required to deliver a fully installed, functional, and ready-to-use kitchen cabinet system as per approved site measurements. Note: Dismantling of existing should also be done. Wiring & Installation		JOB	1		
	Wiring of single light point and exhaust fan to switch board with 1.5					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.28	<p>sq.mm 1 core wires for ECC green in colour and 2x2.5 sq.mm common neutral and live including PVC back boxes PVC insulated wire in 1" dia. PVC conduit is recessed in wall, ceiling etc. complete with all conduit accessories such as junction boxes, bent etc., including sheet cover fixed with CP screws, roses dimmers complete in all respect. Cables are approved make including Switch boards are approved make. This also includes any cutting, grinding etc required for concealing the wiring. (24 points)</p> <p>Wiring & Installation</p> <p>WIRING OF 15AMP SOCKET Wiring for 15A switch socket Testing equipments / Electric Gyser from Distribution in conduit in 6Sqmm x 3Core cable in PVC conduit. Complete with all conduit accessories including providing and fixing 3 pin, 15A switch socket unit of approved make fixed on 16 SWG steel board of suitable size recessed in wall</p> <p>Terms & Conditions:</p> <ol style="list-style-type: none"> All labour, tools, material and transportation to be provided by the contractor. Payment will be made as per actual work done. All HSE standards to be followed by the contractor. All contractor staff must wear proper PPEs during work execution. The contractor would have to follow all safety and HSE standards at site with mandatory PPEs (Safety Helmet, Safety Shoes, Cover all or Trouser with T-Shirt as the loose clothes are not allowed) Contractor will ensure proper housekeeping and cleaning of the area during and after completion of work. Job is subject to inspection and verification of Terminal Engineer / Location In charge Work should be completed within 90 days after acknowledgement of work order. If the Contractor fails to complete the work within time stipulated <(>,<) the Engineer In charge will be entitled to deduct from his bills a value of 0.10% of total work order amount per day up to maximum 10% value of P.O. All materials and items are to be provided and installed subject to 		JOB	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	9
RFQ No	OP-19736AM	
DATE	22.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017049

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	07.07.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY % PO/DD NO. _____

Title: Rehabilitation of OMC Building Washrooms and Pantries at Mehmoodkot Terminal

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>approval from location in charge / engineer and to their satisfaction.</p> <p>10) All the dismantled material including bricks, cement block<(>,<)> floor<(>,<)> tiles, bricks, debris etc. are to be disposed of at a municipality approved location outside PSO Depot by the vendor or PSO designated area</p> <p>11) Rates are inclusive of all types of taxes e.g., PST, GST<(>,<)> etc.</p> <p>12) Contractor will depute Site Engineer (BE-Civil) 5 years minimum work experience for the execution of job.</p> <p>13)Contractor will endeavor to supply the material/equipment of the brand mentioned in the BOQ /specifications. If the contractor wants to offer/use material/equipment other than specified brand, he will clearly mention in his bid which brand he wants to offer as equivalent. He will submit all technical and commercial details, test reports/FAT#s reports/data sheets and other necessary details of the offered material/equipment along with the samples. PSO may ask the bidder to carry out testing, inspections for the offered material/equipment. PSO reserves the right to approve or disapprove the offered brand as equivalent and will not have an obligation to assign any reason thereof. All such inspections and testing cost are to be borne by the bidder.</p> <p>Special Note: i. Vendor will take sample of tiles/glass/windows/doors from engineer before purchase. ii. Design/Color of material can be changed as per site requirement. iii. IT IS ADVISABLE FOR ALL BIDDER TO VISIT MEHMOODKOT TERMINAL PRIOR TO SUBMIT THE TENDER, IN ORDER TO ASCERTAIN THE ACTUAL WORK SCOPE CLEARLY & COMPLETELY, AND TO UNDERSTAND THE SITE CONDITION.</p>					