



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	6
RFQ No	OP-19992AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018219

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Scully Permissive Cabling at Tank Lorry Loading Gantry # PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Metering System Cabling Works KTA</u>	<u>Keamari</u>				
1.01	<u>Cables 2 C-1.5 sq.mm PVC/PVC</u> Laying of 4 core 2.5 mm sq. Cable From Control Room to Gantry for Metering System (Scully, Microload, Flow Meter, Control Valve) The job includes Laying, handling, testing & termination of 4 core 2.5 mm sq. Cu/PVC/PVC insulated and sheathed cable for Metering System (Scully, Microload, Flow Meter, Control Valve) from Control Room to Gantry through cable tray, GI pipe, etc as per instruction of Terminal Engineer. The length of cable is 2000 meters. The job also includes supply and installation of Seal off Fittings at both sides of cable. The cabling work need to connect Control Room Scully and Main Meter System Supply with the following Meter Filing Systems/points: 1. PMG-01 2.,PMG-02 3.,PMG-03 4.,PMG-04 5.,PMG-05 6.,PMG-06 7.,PMG-07 8.,PMG-08 9.,HSD-01 10.,HSD-03 11.,HSD-04 12.,HSD-05 13.,HSD-08 14.,HOBC-07 Note: This line item also includes removal and shifting of old cables after laying of new cables.	<u>Terminal</u>	<u>M</u>	2,000		
1.02	<u>G.I. Conduit 3/4"</u>		<u>M</u>	320		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	6
RFQ No	OP-19992AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018219

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Scully Permissive Cabling at Tank Lorry Loading Gantry # PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	Installation of G.I Conduit of size 3/4 Inch dia GI Pipe on Gantry: Installation of 3/4" dia GI Conduit (Medium Gauge) including all bends<(>,<)> tees, sockets, unions hooks to hand/fix with steel structure etc. complete in all respects. Job to be done as per the satisfaction of engineer incharge. The G.I. Conduiting work needs to be carried out between boundary wall and Gantry's filling points which connect Control Room Scully and Main Meter System Supply with the following Meter Filing Systems/points: 1. PMG-01 2.,,PMG-02 3.,,PMG-03 4.,,PMG-04 5.,,PMG-05 6.,,PMG-06 7.,,PMG-07 8.,,PMG-08 9.,,HSD-01 10.,,HSD-03 11.,,HSD-04 12.,,HSD-05 13.,,HSD-08 14.,,HOBC-07 Note: This line item also includes removal and shifting of old GI Pipe and fittings after laying of new ones. Installation, Testng and Termination of Cable Terminations at Scully, Control Valve, Flow Meter & Microloads Required termination of all cables will be done for the following 14 meter systems: 1. PMG-01 2.,,PMG-02 3.,,PMG-03		EA	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	6
RFQ No	OP-19992AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018219

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Scully Permissive Cabling at Tank Lorry Loading Gantry # PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	4,,PMG-04 5,,PMG-05 6,,PMG-06 7,,PMG-07 8,,PMG-08 9,,HSD-01 10,,HSD-03 11,,HSD-04 12,,HSD-05 13,,HSD-08 14,,HOBC-07					
1.04	<u>Instl. of Ex-Proof Seal Off Fitting</u> Installation of Seal off fittings on metering system at Gantry. The size of seal off fittings is 3/4"dia.		<u>EA</u>	28		
1.05	<u>Cable Tray (100 x 100mm)</u> Installation, fixation of following Cable Tray system with all accessories including Supports, nuts, bolts, washers, unions, bushing, etc. #,100x100 mm Ladder Type (Hot Dip Galvanized) Cable Tray		<u>M</u>	100		
1.06	<u>Dismantling of Existing Civil Structure</u> Dismantling of Existing Hard Standing and/or Asphalt Road from Boundary Wall to Bay 08 Filling Gantry Point. Dismantling of existing hard standing and/or Asphalt Road including masonry, stone soling, brick soling, concrete tiles, and other floor structures. The job also includes removal and shifting of debris within 01 KM radius to scrap yard as per advice of Terminal Engineer.		<u>M3</u>	10.000		
1.07	<u>Excavation</u> Excavation For Cable Trench. Excavation in all kinds of strata / soil (dry or wet, hard or soft<(>,<(> etc) including clearing and grubbing of site complete in all respects<(>,<(> including all operation, complete with breaking clods, levelling<(>,<(> dressing, dewatering, shoring & compacting. The depth		<u>M3</u>	20.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	6
RFQ No	OP-19992AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018219

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Scully Permissive Cabling at Tank Lorry Loading Gantry # PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.08	of excavation will not exceed 2 feet as per instruction of Terminal Engineer. Laying of Pipeline		M	20		
1.09	Shifting and Placement of 06"dia. (or as per site requirement and instruction of Terminal Engineer) Pipeline in Excavated Floor for Laying of cable. The MS Pipe will be provided by PSO for laying. Vendor has to shift and lay the pipe as per advice of Terminal Engineer. Backfilling of cable trench		M3	20.000		
	Backfilling of cable trench after laying of cables as per PSO drawing and following details: - Providing of 100 mm sand cushion below and above the cables. - Providing of bricks covering entire width of cable trench (if access was available and needed as per advice of Terminal Engineer). - Backfilling with rubble free earth upto the depth of 300 mm below ground. -Laying of caution tape (Warning tape) of standard width. The contractor shall make all required finishing to match it with existing flooring / finish ground. - Cleaning of debris remained after backfilling.					
1.10	Providing and laying 1:2:4 with SR cemen		M3	10.000		
	"Providing and laying 1:2:4 with SR cement for construction of hardstanding and/or road using graded material including cost of work(>,<) vibrating, leveling and curing as per PSO drawings / specifications (Cost of reinforcement is not included)"					
2	CONDUIT GI 3/4"dia (E L G)	Keamari Terminal	M	320		
	Supply of GI Conduit (Medium Gauge) of 3/4" dia along with all fittings, elbows, etc required for the job to be done.					
3	Explosion Proof Fitting	Keamari Terminal	EA	28		
	Supply of Seal off Fittings of size 3/4" dia.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	6
RFQ No	OP-19992AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018219

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Scully Permissive Cabling at Tank Lorry Loading Gantry # PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
4	<u>CABLE 2 C-1.5 sq.mm PVC/PVC</u> Supply of 4 core 2.5 mm sq. Cu/PVC/PVC insulated and sheathed cable for scully, control valve, flow meter and Batch Controller of make Pakistan Cables/equivalent.	<u>Keamari Terminal</u>	<u>M</u>	2,000		
5	<u>Cable Tray</u> Supply of 100x100 mm Ladder Type (Hot Dip Galvanized) Cable Tray. SCOPE: The job needs to be done within 30 days after issuance of PO. Terms and Conditions: 1. All services, tools, tackle, material, transportation to be arranged by the contractor. 2. All PSO HSE standards relevant to the subject job to be followed by the contractor. 3. Contractor will provide adequate and fully functional protective equipment (i.e. Safety Shoes, Helmets, Gloves, Mask, Safety harness with shock absorber, Goggles etc) to all its workers and ensure their proper usage as per requirement and instructions the Terminal Engineer. 4. Contractor will ensure proper housekeeping and cleaning of the area after completion of work. 5. Job is subject to inspection of Terminal Engineer. 6. If the Contractor fails to complete the work within time stipulated, the Engineer In-charge will be entitled to deduct from his bills for a value of .10% of work order per day and subject to maximum 10% value of P.O. 7. Tanking of all KPT permissions is vendor's responsibility. 8. The vendor must have past experience in cabling<(>,<(> termination, etc. with flow meter associated equipment. **All the work done and task completed within 60 days, after the	<u>Keamari Terminal</u>	<u>M</u>	100		



6	OF	6
RFQ No	OP-19992AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018219

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	29.10.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: Replacement of Scully Permissive Cabling at Tank Lorry Loading Gantry # PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	issuance of Service Order**					