Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019121

RFQ No	OP-20107AM
DATE	25.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	09.12.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith

EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Repairing of concrete flooring around tank at Chakpirana depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Repairing of Tank pad at CKP depot**	**Chakpirana (Depot)**				
1.01	**PCC (1:2:4)** The scope of work includes but not limited to: Providing and laying CC 1:2:4 in 75mm Thickness (using S.R Cement) of specified strength and approved quality 1/2 inch max: size graded crushed stone and fine aggregate (Sakhi sarwer/Chenab sand or equivalent) using Curing Compound and including form work (installation & removal) mixing<(>,<)> transporting placing, compacting, finishing and curing laid in panels having 9' wide by casting alternately etc Complete in all respects as specified. To confirm the desired cube strength of min. 3000 Psi at 28 days the cube tests for 7 & 28 days will be carried out by contractor on need requirement from PSO's approved laboratory at his own cost and no extra payment will be made to contractor.		**FT2**	2,700		
1.02	**Installation of deformed steel** Providing and Installation of deformed steel reinforcement bars including straightening, removing twists, cutting bending, binding, wastage and overlaps, placing in position on steel chairs, tying with binding wire, complete as per instructions of the site incharge.		**KG**	1,500.000		
1.03	**Associated civil works** Providing services for levelling, dressing dewatering, shoring (if required) and compaction of subgrade with plate/ rollar compactor as to achieve 95% AASHTO modified dry density according to the specification and as directed by Engineer Incharge. The job includes disposal of surplus material outside of depot/ site up to sites allocated by Municipality/city authorities for this purpose and housekeeping of the site complete in all respect.		**JOB**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019121

RFQ No	OP-20107AM
DATE	25.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	09.12.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith

EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Repairing of concrete flooring around tank at Chakpirana depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Terms & Conditions: - Quality is the prime concern of PSO; no compromise shall be made in this regard. Only first class approved quality material which shall strictly conform to the PO specifications must be supplied. -Rates are inclusive of all Govt Taxes, loading unloading and transportation charges. - Work should be completed within 30 days after issuance of service order. -Payment will be made as per actual work done after completion of the job. -If the contractor fails to complete the work within the stipulated time, a penalty of 0.1% of SO amount per day up to a maximum of 10% will be charged due to delayed compliance of service order. -Contractor's labour to follow Company's rules and procedures as well as HSE guidelines and safety procedures.					