



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>CANOPY SIGNAGE SUPPORTING STRCUTURE</u>	<u>PSO House</u>				
1.01	<u>Signage Miscellaneous</u> Replacement of Canopy Signage Supporting Structure. At KARWAN FS, Jaranwala Road, FAISALABAD. Job includes: 1. Safe Removal of existing 4-feet Blue-bars from the canopy structure and keeping on a safe place (to be re-used). 2. Safe removal of tube rods, holders and wiring from the structure and keeping on a safe place (to be re-used). 3. Safe Removal of existing Aluminum Composite Material (ACM) from the Canopy Structure and keeping on a safe place (to be re-used). 4. Removal of old signage supporting structure from the canopy and keeping on a safe place (to be handed over to PSO Nominee). 5. Providing, Fabricating and Installing/Welding the 16-SWG pipe frame of 3/4"*3/4", 1-1/2"*3/4"(as per PSO approved specification , refer to(Annexure-02) The minimum pipe gauge (thickness) to be used for the job is 16-SWG. 6. Applying two coats of Red Oxides and two coats of Enamel Paint (Smoke Gray) on the pipe frame (scrapping and finishing included). 7. Reinstalling the Aluminum composite Material Sheet (ACM) (in PSO approved specification, refer to Annexure-02). Note: Supply of All connectors, holders, hooks and other joining material is included in the scope as per satisfaction of engineer in charge. 8. Providing and Installation of L and Z channel on the installed pipe frame as per drawing (Annexure-02) 9. Complete wiring for canopy fascia as per line item No. 03 for LED Rods and canopy logo. 10. Installing the 4-feet long 5mm thick Blue-bars (removed earlier/Provided by PSO) as per the quantity, refer to Annexure-02). After installation of LED Tube rods (removed earlier/Provided by PSO) and wiring works. HERE Unit of Measure for JOB is SFT **Formula for SFT = Length (RFT) X 2.08	<u>JOB</u>	550			



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.02	<u>Signage Miscellaneous</u> <u>JOB</u> CANOPY SIGNAGE WIRING WORKS At KARWAN FS. Job Includes: Complete Wiring of Canopy Fascia by providing and laying Wire 3/0.29 for LED tube rods in duct strip with proper dressing. 1. Wiring will be laid on as required basis. 2. Contractor will assess existing wires and share details with Divisional Engineer (DE) of the required new wiring. 3. At least 05 Nos circuit loops to be laid for canopy fascia. 4. Only PSO approved cables brands are acceptable for the job. Here EA = Complete JOB		<u>JOB</u>	1		
1.03	<u>Signage Miscellaneous</u> <u>JOB</u> REPLACEMENT OF CANOPY LAPPING SHEET At KARWAN FS Job includes: Installation of 22 SWG GI Lapping Sheet at all sides of the canopy between Canopy Signage Structure and Canopy Top Sheets. Width of the sheet = 2feet. All riveting works are included in the job. All binding material (i.e. J-Hooks, Bolts, nuts, riveting material) is included in the job. HERE Unit of Measure for JOB is RFT		<u>JOB</u>	220		
1.04	<u>LED Tube Lights</u> Providing and Installing New LED-Tube Rods in Canopy Fascia with following specs: Body: Plastic Length: 4-feet Wattage: 16W or below Lumens: 1600 or above		<u>EA</u>	60		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2 2.01	JP holder class: IP-65 or above Note: Contractor will provide the sample for LED-Tube Rods and Holders to Divisional Engineer (DE) for verification before the execution of the job. Here EA = Complete JOB <u>CANOPY SIGNAGE SUPPORTING STRCUTURE</u> <u>PSO House</u> <u>Signage Miscellaneous</u> <u>JOB</u> Replacement of Canopy Signage Supporting Structure. At ABBAS Fs(>,<)> FAISALABAD. Job includes: 1. Safe Removal of existing 4-feet Blue-bars from the canopy structure and keeping on a safe place (to be re-used). 2. Safe removal of tube rods, holders and wiring from the structure and keeping on a safe place (to be re-used). 3. Safe Removal of existing Aluminum Composite Material (ACM) from the Canopy Structure and keeping on a safe place (to be re-used). 4. Removal of old signage supporting structure from the canopy and keeping on a safe place (to be handed over to PSO Nominee). 5. Providing, Fabricating and Installing/Welding the 16-SWG pipe frame of 3/4"3/4", 1-1/2"3/4"(as per PSO approved specification, refer to (Annexure-02) The minimum pipe gauge (thickness) to be used for the job is 16-SWG. 6. Applying two coats of Red Oxides and two coats of Enamel Paint (Smoke Gray) on the pipe frame (scrapping and finishing included). 7. Reinstalling the Aluminum composite Material Sheet (ACM) (in PSO approved specification, refer to Annexure-02). Note: Supply of All connectors, holders, hooks and other joining material is included in the scope as per satisfaction of engineer in charge. 8. Providing and Installation of L and Z channel on the installed pipe frame as per drawing (Annexure-02) 9. Complete wiring for canopy fascia as per line item No. 03 for LED Rods and canopy logo. 10. Installing the 4-feet long 5mm thick Blue-bars (removed			550		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.02	earlier/Provided by PSO) as per the quantity, refer to Annexure-02). After installation of LED Tube rods (removed earlier/Provided by PSO) and wiring works. HERE Unit of Measure for JOB is SFT **Formula for SFT = Length (RFT) X 2.08 <u>Signage Miscellaneous</u> CANOPY SIGNAGE WIRING WORKS At ABBAS FS. Job Includes: Complete Wiring of Canopy Fascia by providing and laying Wire 3/0.29 for LED tube rods in duct strip with proper dressing. 1. Wiring will be laid on as required basis. 2. Contractor will assess existing wires and share details with Divisional Engineer (DE) of the required new wiring. 3. At least 05 Nos circuit loops to be laid for canopy fascia. 4. Only PSO approved cables brands are acceptable for the job. Here EA = Complete JOB		<u>JOB</u>	1		
2.03	<u>Signage Miscellaneous</u> REPLACEMENT OF CANOPY LAPPING SHEET At ABBAS FS Job includes: Installation of 22 SWG GI Lapping Sheet at all sides of the canopy between Canopy Signage Structure and Canopy Top Sheets. Width of the sheet = 2feet. All riveting works are included in the job. All binding material (i.e. J-Hooks, Bolts, nuts, riveting material) is included in the job. HERE Unit of Measure for JOB is RFT		<u>JOB</u>	240		
2.04	<u>LED Tube Lights</u> Providing and Installing New LED-Tube Rods in Canopy Fascia with following specs:		<u>EA</u>	60		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
3 3.01	Body: Plastic Length: 4-feet Wattage: 16W or below Lumens: 1600 or above JP holder class: IP-65 or above Note: Contractor will provide the sample for LED-Tube Rods and Holders to Divisional Engineer (DE) for verification before the execution of the job. Here EA = Complete JOB <u>CANOPY SIGNAGE SUPPORTING STRUCTURE</u> <u>PSO House</u> <u>Signage Miscellaneous</u> <u>JOB</u> Replacement of Canopy Signage Supporting Structure. At GM PETROLEUM <(> ,<> FAISALABAD CITY. Job includes: 1. Safe Removal of existing 4-feet Blue-bars from the canopy structure and keeping on a safe place (to be re-used). 2. Safe removal of tube rods, holders and wiring from the structure and keeping on a safe place (to be re-used). 3. Safe Removal of existing Aluminum Composite Material (ACM) from the Canopy Structure and keeping on a safe place (to be re-used). 4. Removal of old signage supporting structure from the canopy and keeping on a safe place (to be handed over to PSO Nominee). 5. Providing, Fabricating and Installing/Welding the 16-SWG pipe frame of 3/4"*3/4", 1-1/2"*3/4"(as per PSO approved specification, refer to (Annexure-02) The minimum pipe gauge (thickness) to be used for the job is 16-SWG. 6. Applying two coats of Red Oxides and two coats of Enamel Paint (Smoke Gray) on the pipe frame (scrapping and finishing included). 7. Reinstalling the Aluminum composite Material Sheet (ACM) (in PSO approved specification, refer to Annexure-02). Note: Supply of All connectors, holders, hooks and other joining material is included in the scope as per satisfaction of engineer in charge. 8. Providing and			550		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
3.02	Installation of L and Z channel on the installed pipe frame as per drawing (Annexure-02) 9. Complete wiring for canopy fascia as per line item No. 03 for LED Rods and canopy logo. 10. Installing the 4-feet long 5mm thick Blue-bars (removed earlier/Provided by PSO) as per the quantity, refer to Annexure-02). After installation of LED Tube rods (removed earlier/Provided by PSO) and wiring works. HERE Unit of Measure for JOB is SFT **Formula for SFT = Length (RFT) X 2.08 Signage Miscellaneous CANOPY SIGNAGE WIRING WORKS At GM PETROLEUM. Job Includes: Complete Wiring of Canopy Fascia by providing and laying Wire 3/0.29 for LED tube rods in duct strip with proper dressing. 1. Wiring will be laid on as required basis. 2. Contractor will assess existing wires and share details with Divisional Engineer (DE) of the required new wiring. 3. At least 05 Nos circuit loops to be laid for canopy fascia. 4. Only PSO approved cables brands are acceptable for the job. Here EA = Complete JOB		JOB	1		
3.03	Signage Miscellaneous REPLACEMENT OF CANOPY LAPPING SHEET At GM PETROLEUM Job includes: Installation of 22 SWG GI Lapping Sheet at all sides of the canopy between Canopy Signage Structure and Canopy Top Sheets. Width of the sheet = 2feet. All riveting works are included in the job. All binding material (i.e. J-Hooks, Bolts, nuts, riveting material) is included in the job.		JOB	250		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
3.04	HERE Unit of Measure for JOB is RFT <u>LED Tube Lights</u> Providing and Installing New LED-Tube Rods in Canopy Fascia with following specs: Body: Plastic Length: 4-feet Wattage: 16W or below Lumens: 1600 or above JP holder class: IP-65 or above Note: Contractor will provide the sample for LED-Tube Rods and Holders to Divisional Engineer (DE) for verification before the execution of the job. Here EA = Complete JOB		<u>EA</u>	60		
4.01	<u>CANOPY SIGNAGE SUPPORTING STRUCTURE</u> <u>Signage Miscellaneous</u> Replacement of Canopy Signage Supporting Structure. At BISMILLAH TRADERS, Faisalabad-Sheikhupura-Lahore Road. (LAFCO). Job includes: 1. Safe Removal of existing 4-feet Blue-bars from the canopy structure and keeping on a safe place (to be re-used). 2. Safe removal of tube rods, holders and wiring from the structure and keeping on a safe place (to be re-used). 3. Safe Removal of existing Aluminum Composite Material (ACM) from the Canopy Structure and keeping on a safe place (to be re-used). 4. Removal of old signage supporting structure from the canopy and keeping on a safe place (to be handed over to PSO Nominee). 5. Providing, Fabricating and Installing/Welding the 16-SWG pipe frame of 3/4" x 3/4", 1-1/2" x 3/4" (as per PSO approved specification, refer to (Annexure-02) The minimum pipe gauge (thickness) to be used for the job is 16-SWG. 6. Applying two coats of Red Oxides and two coats of Enamel Paint (Smoke Gray) on the pipe frame (scrapping and finishing included).	<u>PSO House</u>	<u>JOB</u>	550		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
4.02	7. Reinstalling the Aluminum composite Material Sheet (ACM) (in PSO approved specification, refer to Annexure-02). Note: Supply of All connectors, holders, hooks and other joining material is included in the scope as per satisfaction of engineer in charge. 8. Providing and Installation of L and Z channel on the installed pipe frame as per drawing (Annexure-02) 9. Complete wiring for canopy fascia as per line item No. 03 for LED Rods and canopy logo. 10. Installing the 4-feet long 5mm thick Blue-bars (removed earlier/Provided by PSO) as per the quantity, refer to Annexure-02). After installation of LED Tube rods (removed earlier/Provided by PSO) and wiring works. HERE Unit of Measure for JOB is SFT **Formula for SFT = Length (RFT) X 2.08 <u>Signage Miscellaneous</u> CANOPY SIGNAGE WIRING WORKS At BISMILLAH TRADERS. Job Includes: Complete Wiring of Canopy Fascia by providing and laying Wire 3/0.29 for LED tube rods in duct strip with proper dressing. 1. Wiring will be laid on as required basis. 2. Contractor will assess existing wires and share details with Divisional Engineer (DE) of the required new wiring. 3. At least 05 Nos circuit loops to be laid for canopy fascia. 4. Only PSO approved cables brands are acceptable for the job. Here EA = Complete JOB		<u>JOB</u>	1		
4.03	<u>Signage Miscellaneous</u> REPLACEMENT OF CANOPY LAPPING SHEET At BISMILLAH TRADERS Job includes: Installation of 22 SWG GI Lapping Sheet at all sides of the canopy		<u>JOB</u>	250		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
4.04	between Canopy Signage Structure and Canopy Top Sheets. Width of the sheet = 2feet. All riveting works are included in the job. All binding material (i.e. J-Hooks, Bolts, nuts, riveting material) is included in the job. HERE Unit of Measure for JOB is RFT LED Tube Lights Providing and Installing New LED-Tube Rods in Canopy Fascia with following specs: Body: Plastic Length: 4-feet Wattage: 16W or below Lumens: 1600 or above JP holder class: IP-65 or above Note: Contractor will provide the sample for LED-Tube Rods and Holders to Divisional Engineer (DE) for verification before the execution of the job. Here EA = Complete JOB		EA	60		
5.01	CANOPY SIGNAGE SUPPORTING STRUCTURE Signage Miscellaneous Replacement of Canopy Signage Supporting Structure. At NAEEM JASPAL FS <(>,<)> Salam Interchange M-2 Bhalwal. Job includes: 1. Safe Removal of existing 4-feet Blue-bars from the canopy structure and keeping on a safe place (to be re-used). 2. Safe removal of tube rods, holders and wiring from the structure and keeping on a safe place (to be re-used). 3. Safe Removal of existing Aluminum Composite Material (ACM) from the Canopy Structure and keeping on a safe place (to be re-used). 4. Removal of old signage supporting structure from the canopy and keeping on a safe place (to be handed over to PSO Nominee). 5. Providing, Fabricating and Installing/Welding the 16-SWG pipe frame of	PSO House	JOB	550		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	16
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
5.02	3/4"3/4", 1-1/2"3/4"(as per PSO approved specification , refer to(Annexure-02) The minimum pipe gauge (thickness) to be used for the job is 16-SWG. 6. Applying two coats of Red Oxides and two coats of Enamel Paint (Smoke Gray) on the pipe frame (scrapping and finishing included). 7. Reinstalling the Aluminum composite Material Sheet (ACM) (in PSO approved specification, refer to Annexure-02). Note: Supply of All connectors, holders, hooks and other joining material is included in the scope as per satisfaction of engineer in charge. 8. Providing and Installation of L and Z channel on the installed pipe frame as per drawing (Annexure-02) 9. Complete wiring for canopy fascia as per line item No. 03 for LED Rods and canopy logo. 10. Installing the 4-feet long 5mm thick Blue-bars (removed earlier/Provided by PSO) as per the quantity, refer to Annexure-02). After installation of LED Tube rods (removed earlier/Provided by PSO) and wiring works. HERE Unit of Measure for JOB is SFT **Formula for SFT = Length (RFT) X 2.08 Signage Miscellaneous CANOPY SIGNAGE WIRING WORKS At NAEEM JASPAL FS. Job Includes: Complete Wiring of Canopy Fascia by providing and laying Wire 3/0.29 for LED tube rods in duct strip with proper dressing. 1. Wiring will be laid on as required basis. 2. Contractor will assess existing wires and share details with Divisional Engineer (DE) of the required new wiring. 3. At least 05 Nos circuit loops to be laid for canopy fascia. 4. Only PSO approved cables brands are acceptable for the job. Here EA = Complete JOB		JOB	1		
5.03	Signage Miscellaneous		JOB	250		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	16
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
5.04	REPLACEMENT OF CANOPY LAPPING SHEET At NAEEM JASPAL Job includes: Installation of 22 SWG GI Lapping Sheet at all sides of the canopy between Canopy Signage Structure and Canopy Top Sheets. Width of the sheet = 2feet. All riveting works are included in the job. All binding material (i.e. J-Hooks, Bolts, nuts, riveting material) is included in the job. HERE Unit of Measure for JOB is RFT LED Tube Lights Providing and Installing New LED-Tube Rods in Canopy Fascia with following specs: Body: Plastic Length: 4-feet Wattage: 16W or below Lumens: 1600 or above JP holder class: IP-65 or above Note: Contractor will provide the sample for LED-Tube Rods and Holders to Divisional Engineer (DE) for verification before the execution of the job. Here EA = Complete JOB TERMS AND CONDITIONS 1. All material labor, tools and equipment is included in the scope. 2. Job to be completed within 30 DAYS from the date of PO Signed by the contractor. 3. Contractor to submit before and after pics. of each activity (i.e. Numbers wise for each activity mentioned in item 01 TO 4 respectively) with the submission of bill. Signed site verification form of ech site "Tasdeeq nama" is mandatory requirement of the bill. 4. Contractor to intimate for mobilization prior a day before each site.		EA	60		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

12	OF	16
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Before work photographs of the team to be share at each site for go ahead from concerned engineer. If in any case the work started without approval, an instant penalty of Rs. 100000/- for the instance may be imposed on vendor and same may result to cancellation of PO without any claim in case of repeated event. 5. Any damages occurred while uninstalling and re-installing any item (i.e. ACM, Bluebars LED rods, holders and others) will be re-imbursed by the contractor without any extra charges. 6. SOP for Structure replacement Dated; 19-10-2020 to be strictly followed throughout the all the jobs. 7. Frame pipe to be presented to concern DE for sample and gauge measurement before execution of work. 8. The contractor needs to ensure all necessary HSE precautionary measures (i.e. JHAs and as instructed by Divisional Engineer as per PSO policy) before executing the job. 9. Cleaning of the site and removal of waste recovered from the job is the sole responsibility of contractor. Neat and clean area of work must be ensured before submitting the bill. 10. The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 11. All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 12. Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. A fresh pair of safety harness to be tied while working on scaffolding, the outriggers of scaffolding are mandatory. Violation of SOP define in Clause:5 and removal/non-presence of out-riggers at any instance will result to straight penalty of Rs.100000/- per instance and may lead to disqualification and termination of the contract. 13. Wherever applicable, contractor is bound to engage certified licensed electrician for electrical works.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

13	OF	16
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
6	14. Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm<(>,<(> etc.). For any special case, approval from DE will be required and work will be performed under supervision of DE. 15. The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines<(>,<(> overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 16. All govt. taxes and levis are included in the quoted rates. 17. Old material i.e. Canopy Structure, LED rods and Canopy Wiring to be handed over to PSO at site after completion of job.					
6.01	<u>ACRYLIC PUMP SPREADERS</u> <u>Supply and Installation of Spreader</u> SUPPLY AND INSTALLATION OF ACRYLIC PUMP SPREADERS Job includes: Fabrication, providing and installation of spreaders as per following specifications: SUBSTRATE: 4 mm Thick, Acrylic Sheet in the required Size and Shape. GRAPHICS:(Electronically cutting and pasting of approved translucent vinyl of 3M(3630-156, 3630 VT, 3630-015<(>,<(> 3630-22, 3630-22)/Avery (5560 <(><(>,<(><(>) 5500-763, 5504<(>,<(>) 5501and White) /Equivalent on the rigid substrate as per the approved design of spreader i PSO's approved colors for PSO Products as per artwork provided and as per drawing# DWG-RC/037 Rev: 01 dated 06-04-2022. Convertor to provide Warranty of FIVE (5) years from the Principle 3M/Avery/Equivalent.	<u>PSO House</u>	<u>EA</u>	55		
6.02	<u>Supply and Installation of Spreader</u>		<u>EA</u>	10		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

14	OF	16
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
7 7.01	Job includes: Providing and installation of Spreader MS frame. All structure details shall be approved by PSO as per drawing# DWG-RC/037 DATED 06-04-2022. The structure to be easily attachable/ detachable with the canopy columns. The spreader frame to be painted with primer coating and enamel paint before installation. New hole in canopy column (where required) for wiring is the part of the scope. Necessary wiring for LED tube-rods (02 Nos) in the spreader are the part of the scope. Job also includes transportation to the site and all electrical mechanical fittings complete in all respects as per site requirement. <u>ACLYLIC BLUEBARS</u> <u>Supply and Installation of Blue Bar</u> SUPPLY, FABRICATION AND INSTALLATION OF ACRYLIC BLUE BARS JOB INCLUDES: 1. Safe Removal of existing blue bars from canopy fascia (to be reused further) at NVRO in Faisalabad Division 2. Stacking of blue bars and full covering with polythene wraps of approved specs. 3. Providing and installation of New blue bars of material description provided below: Material Description: Acrylic Light Bar Supply and fabrication of Acrylic light bar in 5mm thick Acrylic sheet. The light bar is to be molded to shape as per attached sketch (PSO Dwg No: S-006 Rev:5 dated 5th May 2017.3M film i.e. 3M (3630 VT 1986) /Avery CC (5500-763 Blue)/Equivalent should be applied by a qualified and approved converters /	<u>PSO House</u>	<u>FT</u>	920		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

15	OF	16
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	applicator. Joint of djacent two acrylic bars to be covered with same material. Warranty 5 Years 1. Acrylic sheet with a thickness of 5 mm is to be used<(>,<)> molded in the required shape, size and color as per the drawing. 2. Acrylic should be thermoplastic with an outstanding strength (min: Compressive strength of 11 ksi and min: Tensile Strength of 560 psi<(>,<)>(> ,<(>,<)>)> stiffness (Rockwell M80-100) and optical clarity. 3. Acrylic sheet should have to be easily fabricated; bonds well with adhesive sand solvents and should have a property of thermoform. 4. Acrylic should not be easily affected by moisture (water absorption 0.2% - 0.4%) and must have a high strength to weight ratio and high remittances. 5. Vinyl Pasting- Electronically cutting and Pasting with Translucent Blue (PSO Standard blue) Vinyl of 3M- 3630 series/Avery- 5500 series/Equivalent. TERMS AND CONDITIONS: 1. All material tools, transportation and labors charges are the part of the scope. 2. Only third party certified scaffolding to be used for the job (the certification must not more than 3-months old at the time of job execution). 3. Contractor to share site mobilization images for each site with fully functional PPEs to concerned DE before job execution. If at any instance job activity witnessed (without approval) by any official /dealer /team mate, a straight penalty amounting R. 100000/- be applicable for the instance and repeat of the instance may lead to the cancellation of PO without any claim by vendor.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

16	OF	16
RFQ No	RC-20134AM	
DATE	26.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018793

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

05.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: REPLACEMENT OF CANOPY SIGNAGE STRUCTURE(s), BLUE BARS AND SPREADERS AT NVRO(s) IN
FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	4. Job completion time is 60 Days after the PO issuance to contractor via email/SAP Ariba. 0.1% to 10% of the bill to charged as per day penalty in case of delay by the contractor. 5. Third party material specification test of acrylic bars is the sole responsibility of contractor with approved sample from the designated laboratory nominated by concerned DE. In case of any deviation from the approved specifications, the contractor will replace the material without any extra cost. 6. The contractor will share step by step pictures of the works with Concerned Engineer during job execution. 7. Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. All material, tools and labor charges are included in the scope. 8. All govt taxes and rates are included in the scope.					