Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018786

RFQ No	OP-20141JG
DATE	23.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: REPLACEMENT OF 04 INCH DIA PIPING SECTIONS OF PMG RETURN LINE AT PSO ZOT

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Services req for Replacement of piping**	Zot (Inst.)				
1.01	**Cutting of pipelines** COLD CUTTING OF 04 INCH DIA PIPELINE: Cold Cutting by means of pneumatically operated cutter with approved tool preferably HSS for cutting of 04inch diameter in-service gasoline pipeline previously emptied/ degassed/ nitrogen purged. Contractor will ensure compliance to all HSE protocols as per PSO requirements. Provision of air compressor is included in job.		EA	4		
1.02	**Degassing of Vessels** DEGASSING/NITROGEN PURGING OF 04 INCH DIA RETURN LINE: This job includes degassing of gasoline piping using air compressor and nitrogen gas purging. Piping dimensions: Diameter: 04 Inch Length : 240 Meters The contractor shall carry out degassing by means of air compressor and nitrogen purging prior to commencement of any maintenance activities. Nitrogen shall be introduced into the pipeline at a controlled pressure to displace residual gasoline vapors and oxygen from the line. The purging operation shall continue until the pipeline is rendered safe for maintenance work<(>,<)> as verified through gas testing. The contractor shall provide all necessary equipment required for job i.e. nitrogen filled certified cylinders, pressure regulators, hoses, fittings (04 inch diameter flanges with provision to connect cylinder hose and venting), gaskets, monitoring instruments/gauges, and competent personnel required to safely execute the operation.		JOB	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018786

RFQ No	OP-20141JG
DATE	23.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: REPLACEMENT OF 04 INCH DIA PIPING SECTIONS OF PMG RETURN LINE AT PSO ZOT

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Provision of air compressor and unbolting/bolting of flanges for installation of fittings is included in job.					
1.03	**Bolting/Unbolting of pipe joints** BOLTING OF FLANGED JOINTS: Bolting-up flanged joints in piping with gaskets between flanges. Gaskets and stud bolts will be provided by the contractor. Rates should include cost of spiral wounded gasket rings (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20), STUD BOLTS (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 04" diameter		**EA**	5		
1.04	**Making weld joints of Pipes 4 dia** WELDING OF 04 INCH DIA PIPE: Making weld joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges. The job includes beveling, preparation of threads in piping (for threaded piping), flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures: Note: 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint. 2) The welding joints also includes the tie-connections in the pipelines. 3) Mud-plugging of line for the subject line prior to welding is to be done by inserting circular GI plate and mud to comply with safety protocols. This is included in contractor's scope.		**EA**	9		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018786

RFQ No OP-20141JG
DATE 23.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date) 16.11.2026 BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: REPLACEMENT OF 04 INCH DIA PIPING SECTIONS OF PMG RETURN LINE AT PSO ZOT

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	4) NDT certification of weld joints also included in contractor's scope. Shifting and placing pipes & fittings in position with subject piping for welding is also included in job. Provision of Pipe lengths and Flanges will be responsibility of PSO.					
1.05	**Installation of Valve 4 dia** INSTALLATION OF 04 INCH DIA GATE VALVE: Placing / shifting of cast steel / forged steel body type gate valve having flanged ends of 04 inch dia size in position aligned with piping. The job does not include bolting up of flange joints but includes loading transporting, unloading, and making space between lines and ensuring line alignement. Providing Gate valve will be responsibility of PSO.		**EA**	1		
1.06	**Mechanical Cleaning** MECHANICAL CLEANING/ SURFACE PREPARATION: Surface preparation/Mechanical cleaning of external surface of piping as per PSO Approved Maintenance Coating system. All equipment, tools<(>,<)> material, labor required to be provided by the contractor. Contractor will ensure complete removal of loose contaminants to achieve a sound substrate suitable for coating SA 2.5 minimum or as per manufacturers recommendation. Applicable Standards i. Surface preparation shall comply with SSPC-SP 3 # Power Tool Cleaning. ii. All work shall be performed in accordance with the Company's HSE procedures, Permit to Work (PTW) requirements, and approved Method Statement.		**M2**	120		
1.07	**Coating of tank** APPLICATION OF COATING SYSTEM:		**M2**	120		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018786

RFQ No	OP-20141JG
DATE	23.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: REPLACEMENT OF 04 INCH DIA PIPING SECTIONS OF PMG RETURN LINE AT PSO ZOT

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	This includes supply and application of 02 Base coats (having DFT of 150 Microns each) Epoxy Primer and 01 top coat of Polyurethene based coating (having DFT of 60 microns) of PSO's approved make on piping as per instructions of Terminal Engineer. Job should be done according to applicable codes, standards, as per specifications of Paint manufacturer instructions of PSO Engineer.					

Terms and Conditions:

==========

1) All type of taxes are included in the above rates.
2) Contractor should strictly follow the Safety and Security Rules of PSO.
3) Contractor will provide adequate and fully functional protective equipment to all its workers including Safety Shoes, Hard Hat, Safety Goggles, Gloves, face masks, life lines and Safety Harness depending upon the nature and requirement of job and ensure their proper usage as per requirement and instructions of the Terminal Engineer no worker shall be allowed to work without the use of PPE's.
4) All labor, tools, equipment, materials and transportation to execute the job will be to be provided by contractor. All utilities required at site (Electricity, Water etc.) are the responsibility of the contractor. PSO will not assist in any way in this regard. If required the contractor shall arrange for DG set at his own expense. All other tools (lifting equipment, explosion proof lights, Exhaust Fan explosion proof etc.) shall be arranged by the contractor at his own expense.
5) Payment will be made after completion of job as per Directions/satisfactions of Engineer and actual quantity of work done.
6)The contractor must complete the job within 20 days after the issuance of PO. If the Contractor fails to complete the job within stipulated time, PSO will be entitled to deduct an amount equivalent to 0.1% of the

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018786

RFQ No	OP-20141JG
DATE	23.10.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith

EARNEST MONEY %
Rs._____ PO/DD NO. _____

Title: REPLACEMENT OF 04 INCH DIA PIPING SECTIONS OF PMG RETURN LINE AT PSO ZOT

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Purchase Order value per day as liquidated damages for the period up to maximum of 10% of the value of PO. 7) The contractor will be responsible for any sort of damage to the material/items during transportation. 8) Contractor shall responsible to rectify any damage occurred to PSO property or any other Govt / local item during execution of job without charging any cost to PSO. 9) The Services will be provided at PSO Zulfiqarabad Oil terminal Port Qasim, Karachi.					