

Repair of Office Building in Directorate of Intelligence Peshawar

S#		Description	Unit	Qty	Rate (Rs)	Amounts (Rs)
1	07-05-a-03	1st class brick work in ground floor Cement, sand mortar 1:4	pm3	15	20850	312,750
2	10-55-j	Providing and Fixing of Bath Room Tiles 12"x18" of approved quality	pm2	16	3000	48,000
4	12-78-a	Kitchen Floor Cabinet as per approved Design/Specification..	pm2	5	18000	90,000
5	12-78-b	Kitchen Wall Cabinet as per approved Design/Specification.	pm2	5	15000	75,000
6	13-25-a	Preparing surface & painting with snowcem / weathershield paint : First coat	pm2	2000	500	800,000
7	13-25-b	Preparing surface & painting with snowcem / weathershield paint : 2nd & subsequent coats	pm2	2000	250	400,000
8	14-03-a	Providing and fitting glazed earthenware water closet (WC), squatter type (orisa pattern) combined with foot rest. complete in all respects : White	Each	1	10000	10,000
9	14-01-a	Providing and Fixing glazed earthen ware WC European type of approved size excluding cost of seat & cover, complete in all respects: White	Each	1	20000	20,000
10	14-17-a	Providing and fixing best quality looking glass 5 mm thick neatly fitted on masonry wall etc. as per instruction of Engineer In-charge complete. Mirror 60 x 45 cm (24"x18") size	Each	2	10000	20,000
11	14-24-a	Providing and fixing chromium plated (CP) bib-cock heavy duty of approved quality : 2 cm 3/4	Each	10	3000	30,000
12	14-24-b	Providing and fixing chromium plated (CP) bib-cock heavy duty of approved quality : 1.5 cm 1/2"	Each	5	2000	10,000
13	14-10-a	Providing and Fixing glazed earthen ware low down flushing cistern 3 gallons (13.63 Liters) capacity including bracket set, copper connection, etc. complete in all respects: White	Each	-2	11000	22,000

14	14-26-a	Providing and fixing chorimum plated (CP) shower rose complete : Size 1/2"x4" (15 mm x 100 mm) (Best Quality)	Each	2	2500	5,000
15	14-55-a	Providing and Fixing GI pipe & including specials complete 2" dia (light)	pm	25	2000	50,000
16	14-55-e	Providing and Fixing GI pipe & including specials complete: 3/4" dia (light)	pm	25	1500	37,500
17	15-50	Wiring of light/fan/call-bell point in 3/0.029" PVC insulated bare cable in PVC pipe recessed	Each	50	3000	150,000
18	04-45-b	Scraping : Ordinary distemper, oil bound distemper or paint off wall	pm2	1500	120	180,000
19	11-21-b-02	Distemping Old surface : Two coats	pm2	2300	160	200,000
20	13-02-b-01	Painting old surfaces : Sashes, fanlights, doors or windows : First coat	pm2	200	248	49,600
21	11-09-b	Cement plaster 1:4 upto 20' height 1/2" thick	pm2	50	700	35,000
22	25-60-c	Supply and fixing razor wire (2'-0" dia) consisting of 1-1/2"X1-1/2"X3/16" angle iron Y post 2'-6" long 6' to 8' center to center fixed with bolt anchorage, at top of boundary wall including painting posts etc. Complete in all respects.	pm	48	2000	96,000
23	Oct-64	Chemical polishing of marble floor/Dado	pm2	800	450	260,000
24	Dec-68	Providing and fixing PVC wall Panelling 9" wide and 10 ft long hard including all accessories of approved design in any color, shade and pattern in ground floor.	pm2	100	2000	200,000

25	14-87	Providing and fixing Providing and Fixing of Bath accessories set (choricum plated (C) soap dish, CP toilet paper holder, towel rail, best quality looking glass 5 mm thick neatly fitted with Mirror 60 x 45 cm (24"x18") size, glazed earthenware shelf (60x13 cm) 24"x5" with chorium plated (CP) brackets & railing) complete in all respect	Each	2	10000	20,000
26	15-68-c	Supply and Erection best quality AC ceiling fan complete with GI rod, canopy, blades & regulator : 56" sweep	Each	3	10000	30,000
27	NSI	Supply and fixing ceiling light		50	1000	50,000
28	26-0-c-06	Supply and Erection of AC ENERGY EFFICIENT LED LIGHT BULBS (16-20 W)		50	1000	5,000
29	25-68-d	Fabrication/providing and fixing of Fiber Glass Shed consisting of 2 layers of imported TGI matt of best quality. The fiber glass will be installed on high strength MS frame consisting of 1.5"•x1.5"• MS square pipe of 18 SWG mains having blocks of 2.5x2.5 feet and truses of 1.5"•x1.5"• MS square pipe 18 SWG. Fiber glass will be fixed to the square MS pipe frame with aluminum rivets, drilled, punched, cutted leveled confirming to the size of fiber glass panel and MS frame. Fiber glass sheet will be sealed with polyester resin to give a smooth homogenous and water proof finish to the entire surface. Vertical supporting pillars will consist of MS Pipe of 4"• dia 18 SWG. All steel fabrications will be treated with redoxide coat and subsequently with color enamel paint using compressor gun complete in all respect.	Pm2	40	17611	604,440
30	15-220-c	Supply and fixing of 8-14 Litres Electric Geyser including all accessories and fittings	Each	2	25000	50,000
31	12-27-b	Provide & fix wooden box type wardrobe 22" deep Deodar wood boxing & deodar shelves etc	Pm2	80	45000	3,200,000
32	11-37-a	Providing and fixing Chakwal tiles red colour in 1:3 cement mortar complete.	Pm2	50	2500	125,000

33	10-60-a	Providing and laying 3/4"(19mm) thick Granite Black polished tiles of approved quality of any size on floor over 3/8" thick base cement sand mortar 1:3 including setting the tiles with portland cement slurry over cement sand jointing and washing the tiles with cement slurry of matching color including grinding, rubbing, polishing & mortar cost.	Pm2	2	13000	26,000
34	03-07-b	Earth fill in lawns including dressing & compaction with suitable earth borrowed.	Pm3	2500	600	1,500,000
35	12-08-a	First class deodar wood wrought joinery in doors and windows etc. complete : 2" thick	Pm2	6	37000	220,000
36	NSI	Repair & Polishing Furniture				500,000
37	14-5-a-06	Providing and Fixing glazed earthen ware wash hand basin (WHB) complete size 56x40 cm (22"x16"), including bracket set, waste coupling, complete in all respects: Colour with pedestal (Normal Quality)	Each	3	10000	30,000
38	06-05-f	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	Pm3	10	20000	181,210
39	15-22-a	Supply and Erection button holder/angle holder Bakelite large size	Each	30	500	15,000
40	15-05-e	Supply and Erection single core PVC insulated copper conductor 250/440 V grade cable : 7/0.044"	pm	200	500	100,000
41	15-05-c	Supply and Erection single core PVC insulated copper conductor 250/440 V grade cable : 7/0.029"	Pm	200	350	70,000
42	15-70-c	Supply and Erection transpower auto circuit breaker 3-phase, 400V fungus moisture proofing : 100 Amp.	Each	5	8000	40,000
43	15-71-a	Supply and Erection single phase imported auto circuit breaker 6 Amp.	Each	5	2500	12,500

44	15-71-b	Supply and Erection single phase imported auto circuit breaker 15 Amp.	Each	10	2000	20,000
45	15-75-b	Supply and Erection cubical type factory fabricated floor/wall mounting steel main board comp. : Recessed	Pm2	1	50000	50,000
46	15-20-b	Supply and Erection 3 pin switch & plug combined recessed type : 10/15 Amp	Each	20	2500	50,000
					Total	10,000,000