



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	OP19584SI	
DATE	25.03.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016216

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

15.04.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Service required for Chime Coating at 06 Nos. of Tanks (TK-401, TK-402, TK-408, TK-409, TK-412, TK-413) at PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Chime Coating of KTA Gaso Tanks</u>	<u>Keamari Terminal</u>				
1.01	<p><u>Coating of Projection plate</u></p> <p>Service required for providing and application of Tank Base Seal System for Protection & Sealing of Storage Tanks Chime Angle by chime coating.</p> <p>Surface Preparation: Cleaning of chime area using organic solvents to remove oil(>,<)> grease, and contaminants. Mechanical cleaning (wire brushing / power tools) to remove rust, scale, and loose material. Disposal of old chime coating material as per location Engineer advice. Application of Tank Base Seal System (TBSS) Priming: Application of UPS Primer on metal and concrete areas for surface conditioning and adhesion promotion. Gap Filling: Insertion of Polyethylene Foam Backer Rod between annular plate edge and concrete foundation. Sealing of backer rod with bridging tape to provide continuous flexible base. Maintaining slope from projected annular plate edge down to concrete surface for water drainage. Coating System: First Coat: Application of UPS#778 (Breathable & UV Resistant Sealing System) in conjunction with reinforcement fleece to provide waterproofing and mechanical strength. Subsequent Coats: Multi-layer topcoat applications of UPS#778 to achieve an overall thickness of 1.5 # 2 mm. TBSS system shall effectively bridge up to 6# vertical steel projection and 6# horizontal concrete bottom, ensuring complete protection. The following Tanks' Diameters will be covered. T-401: 28.40 Mtr T-402: 28.45 Mtr</p>		M	395		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	OP19584SI	
DATE	25.03.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016216

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	15.04.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Service required for Chime Coating at 06 Nos. of Tanks (TK-401, TK-402, TK-408, TK-409, TK-412, TK-413) at PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>T-408: 15.20 Mtr T-409: 15.20 Mtr T-412: 18.30 Mtr T-413: 18.20 Mtr</p> <p>From TK-412 and 413 removal of old chime coating(>,<) disposing is also included in scope of work.</p> <p>The job also includes, removing of any rust through mechanical cleaning from all tanks base.</p> <p>Work to be performed in accordance with company#s HSE standards and industry best practices (API 653).</p> <p>Site Preparation: Barricading and safety signage to ensure safe working environment. Deployment of all required tools, equipment, and PPE. Verification of tank accessibility and housekeeping of work area. Tools, Materials, Services etc. required for above job is included in same scope of work.</p> <p>----- TERMS AND CONDITIONS and Work Completion Period: ----- Work Completion Period: The Work Completion Period is 30 working days after site hand over. Non-Working day means Permit to work not issued by PSO due to any reason on that particular day. If vendor does not mobilize team due to any reason then that day will be counted as a working day as well.</p> <p>1. All material, tools, labor, etc. to be provided by the Contractor. The vendor must be used Aluminum Alloy bronze tool for mechanical cleaning of tanks. 2. The rates are inclusive of all Govt. taxes, transportation(>,<) loading/unloading, labor, etc. 3. The contractor and his staff will strictly abide by the HSE / Security rules and regulations of the Company. It is the responsibility of contractor to provide his staff PPE's safety</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	OP19584SI	
DATE	25.03.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016216

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

15.04.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Service required for Chime Coating at 06 Nos. of Tanks (TK-401, TK-402, TK-408, TK-409, TK-412, TK-413) at PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>shoes, helmet, gloves, certified safety harness belt with shock absorber while working inside terminal. During painting work at height use proper third-party certified scaffolding.</p> <p>4. Earnest Money shall be released after 06 Month satisfactory completion of job during which contractor shall be responsible to remove any defects / if found in the paint work.</p> <p>5. Contractor should maintain housekeeping of the worksite during progress of work and shall clear and remove all surplus materials and rubbish from site after completion of job as per instruction of Terminal Engineer.</p> <p>6. Contractor must assign site supervisor(s) to receive the necessary documentation including work permits and other instructions prior to start of work. The said supervisor(s) shall be available at the job site while work is being carried out. The contractor must assign qualified HSE Supervisor(s).</p> <p>7. 10. Quantities against various items are estimated and may increase or decrease, or any line item may not be executed-<(>,<(>> however payment shall be made as per actual verified quantities.</p> <p>8. Work Completion time 30 days after site hand over to Contractor.</p> <p>9. Taking NOC/permission from relevant KPT authorities for the job to be done is the responsibility of vendor without any extra charges.</p> <p>10. If for any reason the vendor is not permitted to work, then that day will not be counted as working day.</p> <p>11. Sundays won't be counted as working day. However-<(>,<(>> Saturday (half-day) will be counted as a full working day.</p> <p>12. Vendor will ensure that at least 01 PEC Registered Engineer is always present at site during execution.</p>					