



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016495

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Construct wall & gate warehouse LMPA LMPA</u> <u>(Blending)</u>					
1.01	<u>Providing and laying solid block masonry</u> Providing and laying solid block masonry Services are required to construct closed boundaries wall along with Gate in existing open shed (adjacent to Tank wagon track area) at LMPA KEAMARI PSO. The work shall be comprised of ; Solid Cement Block Masonry Works Providing Laying and Fixing 6 inch thick solid cement block masonry in 1:4 cement sand mortar, Scope of work shall be includes Clear and level the construction area, removing debris and ensuring a stable foundation. Mark the wall layout using stakes and a string line for accurate alignment. Ensure the foundation is level and strong enough to support the wall's weight. Mix the mortar to the appropriate consistency. Lay a thick layer of mortar on the foundation for the first course of blocks. Place the blocks carefully, checking alignment with a string line and level. Laying Subsequent Courses: Apply a layer of mortar on top of each block course and between each block. Stagger the joints (like a brick bond) for added strength, Continuously check for plumb (vertical) and level alignment to maintain a straight wall. Once the wall is complete, fill the joints with mortar (pointing) to enhance weather resistance and appearance. Construction of Concrete ramp shall be done with c.c 1.2.4 and height 6"inch with long inclined surface both side of the entrance of the warehouse, for smooth movement of Forklift truck. Clean off any excess mortar from the surface for a tidy finish. Regularly spray water on the wall for a minimum of 7 days to ensure proper curing and prevent cracking. (Note: Arrangement of Water and Pump for curing purpose will be responsibility of contractor. Curing for block - masonry work and Plaster work will be separate)		M3	30.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016495

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	07.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.02	<p>Inspect the wall for alignment, level, and plumb accuracy, as well as for any cracks or gaps that need filling.</p> <p>The scope of work including the cost of curing, including the cost of jointing with existing masonry, including the cost of all tools<(>,<)> materials and Services required, working at any height.</p> <p>Providing, mixing, placing and casting Reinforced Cement Concrete (RCC) beam over block masonry [RCC BEAM Area : 0.3cubic meter], using approved quality materials of specified grade, including proper alignment<(>,<)> leveling, and placement as per drawings and instructions of the Engineer-Incharge. The work includes providing, fixing and removal of formwork (fair face shuttering) to achieve smooth and even concrete finish, including all supports, bracing, centering, and staging as required. Concrete shall be properly compacted using mechanical vibrators, ensuring dense and honeycomb-free structure. After casting<(>,<)> curing shall be carried out for a minimum period of 7 days to achieve required strength and durability. Complete in all respects including Services<(>,<)> materials (excluding/including steel if required), tools <(>,<)> equipment, shuttering, compaction, curing, and finishing as per specifications and to the satisfaction of the Engineer-Incharge.</p> <p>Complete in all respects as per site requirements and as directed by the engineering in charge.</p> <p>cement plaster with SR cement mortar 1:4</p> <p>cement plaster with SR cement mortar 1:4</p> <p>Providing, mixing and applying 1/2" thick cement-sand Mortar (1:4) , Regularly spray water on the wall for a minimum of 7 days to ensure proper curing and prevent cracking.</p> <p>(Note: Arrangement of Water and Pump for curing purpose will be responsibility of contractor.</p> <p>Cleaning of the site of any debris, disposal of all debris away from the premises. All safety measure related to Workmanship safety shall be strictly</p>		EA	297		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016495

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	<p>observed by the contractor. Complete in all respects as per side requirements and as directed by the engineering in-charge. [Note:- UoM: EA = Sq-Mtr]</p> <p><u>Fitting in position of steel supports</u></p> <p>Services for Mechanical Fabrication Works: Fabricate and fix in position including of M.S Steel Double Sliding Door Gate with 2mm M.S Sheet, M.S FLAT BAR IRON 38mm x 6mm and 50x50x6mm steel angle iron door frame. And locking system With supports, anchor supports, anchor bolts, to mount at designated place, complete as per sketch drawing(>,<)></p> <p>Scope of work shall also include Rubbing, scrapping and Mechanical cleaning, 3 coats of enamel paint over two coats of primer of M/s. ICI or M/s Berger etc.; Complete in all respect and as approve by the site incharge. The job also includes the provision of steel structure frame to hold the gate and fixed with the steel structure in all respects and satisfaction of engineer /incharge. (Approx size of door will be confirmed from Engineer Incharge.) [Note:- UoM: EA = KG]</p>		EA	1,458		
1.04	<p><u>Application of synthetic enamel paint</u></p> <p>Application of synthetic enamel paint Services are required durable, weather-resistant, and aesthetically pleasing weather shield synthetic enamel paint finish on a newly constructed wall. Scope of work shall be comprised of Get Approve color shade from shade card of well know color brand i.e Nipon, Jotun, Burger or Equivalent from LMPA officials(>,<)> Application of one coat of Primer Coat (minimum DFT of 50 microns); Use alkali-resistant primer suitable for masonry surface. Use compatible primer as recommended by selected enamel paint manufacturer, Mix Primer, Stir well and dilute with recommended thinner (usually turpentine oil or enamel thinner). Apply primer coat evenly using brush, roller, or spray gun. Ensure full coverage with no sagging or missed spots. Allow 6-8 hours drying time (as per product datasheet and weather conditions). Prepare paint for First Coat of Synthetic Enamel Paint; Stir the enamel paint thoroughly.</p>		M2	370		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
 Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
 SAP No.6100016495

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	07.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	<p>Apply the first coat with a good-quality brush, roller, or spray (minimum DFT of 50 microns). Maintain uniform thickness and avoid lap marks. Allow 10-12 hours drying time before applying the next coat. Apply the second coat of enamel paint using the same method. Ensure smooth, even finish and full color development. Let the painted surface cure for 24-48 hours for full hardness and gloss.</p> <p>[Note: Contractor must have to arranged Ultrasonic DFT Meter to check Dry Film Thickness of color on concrete wall as desired Micron level in scope.]</p> <p>Fitting in position of steel supports</p> <p>Steel Reinforcement Fitting Services Services for cutting, bending and fixing reinforcement steel bars deformed of approved make and grade, in beams or any RCC member<(>,<)> strictly in accordance with drawings and specifications. The work includes straightening, cutting, bending, binding with G.I binding wire (16 SWG), placing in position with proper cover using cover blocks, and securing in alignment as per bar bending schedule (BBS). The rate shall include all services, material (steel bars), binding wire <(>,<)> tools, equipment, wastage, lapping, chairs, spacers, and complete fixing in position as per specifications and to the satisfaction of the Engineer-Incharge. [Note:- UoM: EA = KG]</p>		EA	54		
2	<p>Miscellaneous steel structure</p> <p>Supply of M.S Angle Iron 50x50x6mm, M.S Flat Bar Iron 38x6mm and M.S Sheet 2mm Thickness and Pertinent supporting structural steel for fabrication of supporting guided rail and anchors for fitting stud bolts, nut bolts, washers, etc.</p>	LMPA (Blending)	KG	1,512.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016495

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>Supply of M.S Steel Bar 12mm and 8mm Thickness and Pertinent to RCC structural steel for BEAM Total Lenght M.S Steel Round Bar 12mm (for Two Beam) : 55 Meter Total Lenght M.S Steel Round Bar 8mm (for Two Beam) : 12 Meter . . General Terms: 1)The contractor must visit the site before quoting. 2)Contractor should submit the document along with bid like Project Schedule, Material Procurement Schedule inclusive of mobilization, Site Organogram, list of equipment and manpower to be deployed at site during execution. 3)Contractor will depute Site Supervisor (DAE-Civil) 5 years minimum work experience for the execution of job. Contractor will submit CV of Supervisors along with certificates. 4)Contractor will depute HSE Supervisor with necessary trainings and minimum three (3) years of relevant work experience. Contractor will submit CV of HSE Supervisors along with training certificates. 5)The contractor will obtain prior written approval of PSO site in charge before undertaking any major construction activities at site. 6)The contractor should have to follow all safety and HSE standards at site with mandatory PPEs (Safety Helmet, Safety Shoes, cover all or Trouser with T-Shirt as the loose clothes are not allowed) 7)All such inspections and tastings cost are to be borne by the Contractor. 8)Contractor to ensure good housekeeping including proper stacking of useful material at site and removal of surplus material</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016495

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ **PO/DD NO.** _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>outside of depot / terminal on daily basis. lear and safe passage should be provided and marked at site for labor movement and material shifting.</p> <p>9)The contractor will adopt special care for dismantling /installation of Structures if any.</p> <p>10)The contractor must execute all cares/precautions to save the items/material during dismantling and installation it should be done with professional way.</p> <p>11)This work is in operational area and the shifting/accumulation of debris or surplus material construction material is solely of contractor's responsibility.</p> <p>12) Billing shall be done on as per actual measurement of work done.</p> <p>13) The Contractor is required to conduct a site visit to LMPA Keamari prior to submitting its bid, in order to fully ascertain, verify, and understand the complete scope of work and all associated conditions. By submitting a bid, the Contractor confirms that it has inspected the site and is fully aware of all requirements, constraints, and existing circumstances relevant to the execution of the work. Proceeding with the stated scope of work shall be deemed the Contractor's acceptance of all job requirements. Accordingly, the Contractor shall be obligated to provide all services, labor, materials, and supplies necessary for the successful completion of the work, regardless of any discrepancies, omissions, or reductions observed during execution. No claims for additional payment or scope adjustment will be entertained on the basis of conditions that should have been identified during the site visit.</p> <p>14) In the event of Contractor's/ Supplier failure to deliver the Services/ Goods within the time mention in purchase order/service order, in that event PSO shall be entitled to deduct from his bills/outstanding payments or other works done by him for PSO or from any amount due to him by PSO a sum of Rs.0.1% of Purchase Order/Service Order value per</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016495

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	07.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>day as liquidated damages for the period which the said services/material remains incomplete or fail to pass the quality tests subject to a maximum 10% of work order#s amount to be recovered from the contract on his default.</p> <p>[Note: Penalty/liquidity demerge may be waived in case of force majeure situation contractor will be required to furnish documentary proof.]</p> <p>Project Requirements:</p> <ol style="list-style-type: none"> Contractor to Ensure deployment of competent team at site in order to complete the Project in scheduled duration, Contractor has to take care of the levels as per the instructions of engineer in charge. Contractor to take all safety measures for existing piping, cables, cable trays, during execution of work. In case of any damage it is responsibility of contractor to rectify without any additional cost to Company. <p>Mandatory Requirements:</p> <ol style="list-style-type: none"> Contractor to maintain Log book on daily basis and same to be signed through the PSO representative at terminal/depot regularly, Contractor to keep the record of material gate passes (IN/OUT) for all the materials,3.Contractor to keep record of all material testing reports (Concrete blocks, bricks/blocks, structural steel MTC etc) etc. for all the materials to reach at site or as and when required byengineer in charge, Contractor to keep complete record of all HSE requirements like Tool talks, induction details or any other HSE requirements fulfilled at site, 					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	8
RFQ No	LM19639AA	
DATE	22.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016495

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	07.05.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Conversion of Open Drum Shed into Closed Warehouse for Finished Lubricant Storage at LMPA

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.