



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	6
RFQ No	RF19651SI	
DATE	03.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016588

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

20.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Providing Services For Replacement of Canopy Top Sheets <(>&<)> False Ceiling at M/s SONY PS (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Canopy Repair - SONY SS</u>	<u>PSO House</u>				
1.01	<u>Providing and Laying of GI sheet</u> Replacement of Canopy Top Sheets: Job includes removal of old canopy top GI Sheets and providing, fabrication and fixing of corrugated G.I. continuous sheet, 22 SWG (atleast 30 micron powder coated) including overlaps, crown and edge elements, expansion joints and making openings. Also included are fixings such as galvanized steel J-bolts, nuts and washer. Unit of Measurement: SQFT Note: 1- Contractor will be responsible for the removal/disposal of debris outside retail outlet premises 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Bending sheering of sheet should be as per automatic machine. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.Ft 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material		M2	2,200		
1.02	<u>GI corrugated sheet</u> Providing Fabricating and fixing in position on existing structure, 16 SWG plain GI Sheet dain water channel including self tapping screw or galvanized M S J-Bolts, Rubber washer<(>,<)> Cup washer and Nuts etc. Joining each other rivet and Silicon filing in joins, making opening for drainage and fixing UPVC drain cover. Unit of Measurement: SQFT		M2	500		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	6
RFQ No	RF19651SI	
DATE	03.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016588

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

20.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services For Replacement of Canopy Top Sheets <(>&<) False Ceiling at M/s SONY PS (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	<p>Note:</p> <p>1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises.</p> <p>2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Will be measured with roof sheeting in Sq.ft</p> <p>3- Cost of Item = Cost of new material - Cost of old scrapped /removed material.</p> <p>Installation of of UPVC Pipe Class D 4"</p> <p>Providing and Instaling 4" Dia, local made UPVC drain pipe complete with all fitting as per site requirements hanged with MS hanger/support For drainage of Rain water, job also includes complete with cutting<(>&<) jointing,& wastage etc. Complete in all respect.</p> <p>Unit of Measurement = RFT</p>		M	250		
1.04	<p>Provid Erectng.Fixng. of GI drain ridge</p> <p>Providing and Laying of 24 Swg(atleast 30 micron powder coated) Plain top sheet on fascia complete in all respects.</p> <p>Unit of Measurement: SQFT</p> <p>Note:</p> <p>1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises.</p> <p>2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft</p> <p>3- Cost of Item = Cost of new material - Cost of old scrapped /removed material.</p>		M2	600		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	6
RFQ No	RF19651SI	
DATE	03.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016588

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	20.05.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services For Replacement of Canopy Top Sheets <(>&<) False Ceiling at M/s SONY PS (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	<p>Civil Miscellaneous</p> <p>Providing services for high elastomeric water proofing of canopy top sheet and drain channels after complete replacement.</p> <p>Providing and applying of two coat of sealing flex after complete cleaning and removal of dust from the sheet and apply two coats. Sealing flex is water based modified acrylic /synthetic rubber emulsion.</p> <p>Job also includes complete sealing of the holes and openings and ensure proper workmanship with approved sealant and silicone packing where required.</p> <p>Brand: Ultra Seal flex or approved equivalent.</p>		SFT	2,400		
1.06	<p>Miscellaneous</p> <p>Providing Material and Service, for proper arrangement of loose Electric wires in proper conduit(flexible wiring, channel patti and taping)lying at top of canopy, Tank area, DB room and office area, Complete in all respect.</p> <p>Job also includes removal/ redirectioning of electric/other wiring passing over or attached with Canopy.</p> <p>Providing services for replacement/repair of Fascia LED lights, Signage items, if found fused with proper connector arrangements and wiring, where necessary.</p>		EA	1		
1.07	<p>False Ceiling (Canopy)</p> <p>Providing and fixing of new false ceiling under canopy with 4" wide 26 SWG pre-painted (white color) steel sheet strips with no perforations and maximum length of 12 ft. hinges, bolts and all necessary fittings including sofit return of 22 swg for false ceiling finish of approved shades to be suspended with metal</p>		EA	2,400		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	6
RFQ No	RF19651SI	
DATE	03.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016588

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	20.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Providing Services For Replacement of Canopy Top Sheets <(>&<)> False Ceiling at M/s SONY PS (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>adjustable suspension system as per standard. Complete in all respect as per direction of engineer incharge.</p> <p>Job also includes safe removal and reinstallation of LED Canopy lights, and any additional Canopy light to be installed at site, inclusive of additional wiring and light frame, as and where required at site.</p> <p>Job means Square Foot; i.e. unit of measurement for this item.</p> <p>General TERMS & CONDITIONS: =====</p> <p>1) The above rates are inclusive of all material, labour<(>&<)> transportation and Govt taxes.</p> <p>2) Contractor should strictly follow the safety and security rules of PSO.</p> <p>3) Quality is the prime concern of PSO, no compromise shall be made in this regard. Only first class approved quality material, workmanship and supervision will be utilized by the contractor which shall strictly confirm to the WO/SO specification.</p> <p>4) The contractor will follow all HSE requirements and will provide all PPE'S to his labour and will ensure safe working.</p> <p>5) Payment of bill to contractor is subject to acceptance of job.</p> <p>6) The Contractor/Supplier hereby represents that he has paid the requisite amount of stamp duty (0.035% Sindg Govt.)to the concerned revenue authority on this Purchase Order.</p> <p>9) Contractor will be responsible for the removal / disposal of debris outside retail outlet premises as per the instruction of the engineer incharge 10) Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety.</p> <p>11) The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time.</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	6
RFQ No	RF19651SI	
DATE	03.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016588

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	20.05.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Providing Services For Replacement of Canopy Top Sheets <(><)> False Ceiling at M/s SONY PS (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>Contractor will be responsible to ensure risk assessment<(><)> undertake steps to mitigate risk and work planning for the high risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes, Gloves<(><)> Helmets, Goggles, Safety harness, etc) during execution of work. PSO reserves the right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor.</p> <p>12) The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers.</p> <p>13) All tools, equipment used by the contractor must be properly maintained and remain HSE compliant.</p> <p>14) Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it.</p> <p>15) Wherever applicable, contractor is bound to engage certified / licensed electrician for electrical works.</p> <p>16) Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall<(><)> thunderstorm, etc.). For any special case, approval from DE will be required and work will be performed under supervision of DE. 17) The contractor must ensure that the #work area# and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment.</p> <p>18) The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	6
RFQ No	RF19651SI	
DATE	03.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016588

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

20.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Providing Services For Replacement of Canopy Top Sheets <(>&<)> False Ceiling at M/s SONY PS (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>drugs, smoking in #no smoking# area, etc) during work.</p> <p>Contactors will also ensure proper work planning and risk assessment prior to start of work.</p> <p>19) The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 20) The contractor shall indemnify PSO, its offices <(>,<)> employees, agents and representatives from and against all losses, costs, penalties, fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated by his contract.</p> <p>21) Contractor shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO.</p> <p>22) All material, tools, labor, etc. to be provided by the Contractor.</p> <p>23) Quoted rates are inclusive scrap materials.</p>					