



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	IT19685-SJ	
DATE	18.05.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016806

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON (Date)	03.06.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Provision of service installation and supply of miscellaneous works at PSO House

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<b><u>Miscellaneous Work</u></b>	<b><u>PSO House</u></b>				
1.01	<b><u>ELECTRICAL WORKS</u></b> Wire for Three Phase Connection: Providing and laying 4 Core 6 Sqmm electrical wire (Make: Pakistan Cables or Fast Cables) in heavy-duty PVC conduit for power distribution, complete in all respects. The scope includes the supply of high#quality copper conductor, PVC insulated and sheathed cable, along with heavy-duty PVC conduit, bends, junction boxes, and related accessories. The wire shall be properly routed through PVC conduits with secure fixing, terminations, and tagging at both ends. All work shall be carried out as per site conditions and engineering specifications, including all tools, materials, and labor required for completion in all respects.  Job= Rft		<b><u>JOB</u></b>	182		
1.02	<b><u>Miscellaneous services</u></b> Supply, Installation, testing and commissioning of the 7W COB Lights including all accessories like electronic ballast, lamps, mounting arrangements etc. Complete in all respects. Mounting accessories shall be provided by contractor like screws, nuts, bolts, strings etc.		<b><u>JOB</u></b>	230		
1.03	<b><u>CAT6 Wiring (Point Wiring) (EA)</u></b> Reconfiguration and re-termination of CAT-6 wiring into the new IT rack, including proper routing, dressing, and secure fixing of cables. The work includes re-punching of information outlets (I/Os), labeling, and ensuring proper connectivity for network functionality. All tasks shall be carried out using standard tools and practices to maintain performance and minimize signal loss. The scope includes all necessary accessories, labor, and testing to complete the job in all respects as per specifications and instructions of the Engineer.		<b><u>EA</u></b>	1		
1.04	<b><u>Miscellaneous services</u></b> Installation of owner-supplied sockets at workstations, including proper mounting, alignment, and secure fixing as per site requirements. The work includes making necessary electrical connections to the existing wiring system, ensuring safe, reliable, and functional operation. All tools, labor, and accessories required for installation shall be		<b><u>JOB</u></b>	1		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	IT19685-SJ	
DATE	18.05.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016806

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON (Date)	03.06.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Provision of service installation and supply of miscellaneous works at PSO House

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	provided, with the work completed in all respects as per specifications and instructions of the Engineer. <b>ELECTRICAL WORKS</b> Providing and laying 4 Core 35 sq.mm main electric wire (Make: Pakistan Cables, Fast Cables, Allied Cables, or equivalent) from Sub Main Distribution Boards to Floor Distribution Boards. The work includes proper routing through conduits, trays, or trenches as required, complete with terminations, lugs, and tagging at both ends. All materials, tools, labor, and accessories necessary to ensure safe, secure, and efficient power distribution are included, with the work completed in all respects as per specifications and instructions of the Engineer  Note: JOB = METERS		<b>JOB</b>	29		
1.06	<b>PVC Piping Work (2 inch Dia) (RET)</b> Piping works using the required diameter sch 80 pipe of approved brand. This includes all fittings such as elbows, Tee, Unions, Sockets etc. required for complete job		<b>RET</b>	455		
1.07	<b>Miscellaneous services</b> Providing and Installation of 1" Brass Gate Valves  Note: Job = No.		<b>JOB</b>	4		
1.08	<b>Miscellaneous services</b> Providing and Installation of 1.5" Brass Gate Valves  Note: Job = No.		<b>JOB</b>	1		
1.09	<b>Miscellaneous services</b> Installation of SCH-80 PVC pipes in grey color, including cutting, aligning, joining with appropriate solvent cement, and securely fixing in place with necessary supports, clamps, and hangers as per site requirements. The work shall ensure leak#proof joints and proper alignment in accordance with approved drawings and specifications. All tools, labor, and accessories required for installation are included, with the work completed in all respects as per instructions of the		<b>JOB</b>	1		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	IT19685-SJ	
DATE	18.05.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016806

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	03.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Provision of service installation and supply of miscellaneous works at PSO House

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.10	Engineer. <b>Miscellaneous services</b> Removal of existing GI pipes, including careful dismantling and detachment from fittings, supports, and connections without causing damage to adjacent works. The scope includes collection, segregation<> ,<> and either disposal of the dismantled pipes or handing them over to the client, as per the evaluation and instructions of the Engineer. All necessary tools, equipment, labor, and handling arrangements are included to complete the work in all respects as per site conditions and specifications		<b>JOB</b>	1		
2	including Supply and Installation of Clipsal made PDU (8 / 6 ports) <b>6" Pipe</b> M=RFT	<b>PSO House</b>	<b>M</b>	140		
3	<b>6" Yee</b>	<b>PSO House</b>	<b>EA</b>	8		
4	<b>6" 45° Elbow</b>	<b>PSO House</b>	<b>EA</b>	1		
5	<b>6 x 4 R Bush</b>	<b>PSO House</b>	<b>EA</b>	8		
6	<b>6" Sockets</b>	<b>PSO House</b>	<b>EA</b>	10		
7	<b>4" Pipe</b>	<b>PSO House</b>	<b>M</b>	10		
8	<b>Jointing Cements 16oz</b> Supply of SCH-80 PVC pipes in grey color (Make: Hydroplast, Pakarab, or equivalent), of approved quality and conforming to relevant standards. Pipes shall be suitable for pressure and non-pressure applications, delivered to site with proper handling, unloading, and stacking as directed. All materials shall be new and of specified make, ensuring completion in all respects as per project specifications and instructions of the Engineer.	<b>PSO House</b>	<b>EA</b>	12		