



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	RF19707SI	
DATE	02.06.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016906

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON (Date)	17.06.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ **PO/DD NO.** \_\_\_\_\_

**Title:** Providing Services For Replacement of Canopy Top Sheets at M/s Askari (CF Site) Sukkur Division,

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<b><u>M&amp;R - MA</u></b>	<b><u>PSO House</u></b>				
1.01	<b><u>22 SWG CGI SHEET FOR CANOPY ROOF</u></b> Askari (CF Site)  Replacement of Canopy Top Sheets Job includes removal of old canopy top GI Sheets and providing, fabrication and fixing of corrugated G.I. continuous sheet, 22 SWG (at least 30-micron powder coated) including overlaps, crown and edge elements, expansion joints and making openings. Also included are fixings such as galvanized steel J -bolts, nuts and washer.  Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer in charge instruction. Bending sharing of sheet should be as per automatic machine. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material		<b><u>SFT</u></b>	3,500		
1.02	<b><u>16 SWG GI SHEET, GUTTER &amp; CLADDING</u></b> Providing Fabricating and fixing in position on existing structure, 16 SWG plain GI Sheet drain water channel including self-tapping screw or galvanized M S J-Bolts, Rubber washer, Cup washer and Nuts etc. Joining each other rivet and Silicon filing in joints, making opening for drainage and fixing UPVC drain cover. Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises. 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer in charge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.FT 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material		<b><u>SFT</u></b>	550		
1.03	<b><u>P/L UPVC PIPE 4" DIA, CLASS-D</u></b>		<b><u>RFI</u></b>	550		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RF19707SI	
DATE	02.06.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016906

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	17.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Providing Services For Replacement of Canopy Top Sheets at M/s Askari (CF Site) Sukkur Division,

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	<p>Providing and Installing 4" Dia, local made UPVC drain pipe complete with all fitting as per site requirements hanged with MS hanger/support</p> <p>For drainage of Rain water, job also includes complete with cutting&lt;(&gt; ,&lt;(&gt; jointing, &amp; wastage etc. Complete in all respect.</p> <p><b>Water Proofing</b></p> <p>Water Proofing Providing services for water proofing of canopy top sheet after complete replacement, providing and laying bitumen coat after complete cleaning and removal of dust from the sheet and apply two coat of bitumen coats, then apply polyester sheet / cotton doth on complete sheet and apply final bitumen coat, job also intrudes complete sealing of the holes and opening and ensure proper workmanship.</p>		<b>SFT</b>	3,500		
1.05	<p><b>PROVID. FRECT. FIXING OF G.I CROWN RIDGE</b></p> <p>Providing and Laying of 24 Swg(at least 30 micron powder coated) Plain top sheet on fascia complete in all respects.</p> <p>Note:</p> <p>1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises.</p> <p>2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer in charge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.meter</p> <p>3- Cost of Item = Cost of new material - Cost of old scrapped /removed material.</p> <p>Terms &amp; Conditions:</p> <p>=====</p> <p>1. The rates of items are inclusive of all taxes or any other tax applicable and contractor is required to submit GST/ SST invoice at the time of invoice.</p> <p>2. Contractor will arrange testing of equipment at his own cost, if required.</p> <p>3. Quality of work is the prime concern of PSO. The contractor will be</p>		<b>M2</b>	550		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	RF19707SI	
DATE	02.06.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016906

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	17.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Providing Services For Replacement of Canopy Top Sheets at M/s Askari (CF Site) Sukkur Division,

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>required to produce best quality work.</p> <p>4. Work must be completed within 80 days after site handed over to contractor</p> <p>5. Contractor has to comply with all HSE procedures and policies during execution of the work.</p> <p>6. Contractor should strictly follow the safety and security rules of PSO. Contractor's team has to follow Company's rules and procedures as well as HSE guidelines and safety procedures. 7. All labour, tools (&lt;&gt; ,&lt;&gt;) materials and transportation to be provided by contractor.</p> <p>8. Payment will be made as per actual quantity of Work Done.</p> <p>9. If the Contractor fails to complete the work with in time stipulated ,the Engineer Incharge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Service Order per day and subject to maximum 10% Value of SO.</p> <p>10. Contractor should maintain housekeeping of the workplace during progress of work and shall clear and remove all surplus materials and rubbish from workplace after completion of job as per instruction of Incharge.</p> <p>11. The work will only be accepted after inspection and approval by the DE.</p> <p>12. Bidder must visit the site before quoting for the job to properly asses the scope of work.</p> <p>13. Damage to the False Ceiling during replacement of sheets is to be born by contractor himself.</p> <p>14. Rates are inclusive of scrap materials</p> <p>15. Work will be performed using proper PPEs like, harness, safety helmets, Shoes etc complete in all respect.</p>					