



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Replacemnet of pipelines at HVAC</u>	LMT				
1.01	<u>Cutting / Removal of Pipelines 12" dia</u> The scope of work includes dismantling and removal of the existing deteriorated pipelines installed in the cooling tower area. The work also includes shifting/transportation of new pipelines and associated materials to the site, complete in all respects. Installation of new pipelines shall be carried out at the cooling tower area through proper welding process, including alignment, fit-up, joint welding, and necessary supports/accessories required for satisfactory completion of the job. The scope further includes cleaning of welded joints, leak checking, and commissioning of the pipeline system to the satisfaction of the concerned engineer. Epoxy coating to be apply on pipelines as per standard. (Matreial will be provided by PSO)		M	3.350		
1.02	<u>Cutting / Removal of Pipelines 8" dia</u> The scope of work includes dismantling and removal of the existing deteriorated pipelines installed in the cooling tower area. The work also includes shifting/transportation of new pipelines and associated materials to the site, complete in all respects. Installation of new pipelines shall be carried out at the cooling tower area through proper welding process, including alignment, fit-up, joint welding, and necessary supports/accessories required for satisfactory completion of the job. The scope further includes cleaning of welded joints, leak checking, and commissioning of the pipeline system to the satisfaction of the concerned engineer. Epoxy coating to be apply on pipelines as per standard. (Matreial will be provided by PSO)		M	12.800		
1.03	<u>Cutting / Removal of Pipelines 6" dia</u> The scope of work includes dismantling and removal of the existing cladding/insulation from the pipeline area to access the installed butterfly valves. The work further includes dismantling and removal of the existing butterfly valves along with all necessary accessories and		M	9.140		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	30.06.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	<p>fittings.</p> <p>The scope also includes provision, installation, alignment, and fixing of new butterfly valves complete in all respects. After completion of valve replacement work, reinstallation of cladding/insulation shall be carried out properly, including all necessary finishing and fixing accessories required for satisfactory completion of the job. (Testing of valve by filling water in cooling tower).</p> <p>Shift/Pacing of Pipes 4" dia (HSE)</p> <p>The scope of work includes dismantling and removal of strainers from the existing pipeline system. The removed strainers shall be shifted to the workshop/site area for complete repair and overhaul, including cleaning, inspection, replacement/repair of damaged parts, rectification of leakages, and restoration of proper functionality.</p> <p>The scope further includes surface preparation and application of paint coating complete in all respects. After completion of repair and painting work, the strainers shall be reinstalled/fixes in the line with proper alignment, tightening, and leak testing to ensure satisfactory operation of the system. (Removal of cladding and supply, installation of new cladding is included in job).</p>		M	30.500		
1.05	<p>Replacement of butterfly valves 4 inch</p> <p>The scope of work includes dismantling and removal of the existing cladding/insulation from the pipeline area to access the installed butterfly valves. The work further includes dismantling and removal of the existing butterfly valves along with all necessary accessories and fittings.</p> <p>The scope also includes provision, installation, alignment, and fixing of new butterfly valves complete in all respects. After completion of valve replacement work, reinstallation of cladding/insulation shall be carried out properly, including all necessary finishing and fixing accessories required for satisfactory completion of the job. (Testing of</p>		JOB	20		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	<p>valve by filling water in cooling tower). Valves to be provided by contractor.</p> <p>Replacement of butterfly valves 2 inch</p> <p>The scope of work includes dismantling and removal of the existing cladding/insulation from the pipeline area to access the installed butterfly valves. The work further includes dismantling and removal of the existing butterfly valves along with all necessary accessories and fittings.</p> <p>The scope also includes provision, installation, alignment, and fixing of new butterfly valves complete in all respects. After completion of valve replacement work, reinstallation of cladding/insulation shall be carried out properly, including all necessary finishing and fixing accessories required for satisfactory completion of the job. (Testing of valve by filling water in cooling tower). Valves to be provided by contractor.</p>		JOB	8		
1.07	<p>Overhauling of HVAC lines strainers</p> <p>The scope of work includes dismantling and removal of strainers from the existing pipeline system. The removed strainers shall be shifted to the workshop/site area for complete repair and overhaul, including cleaning, inspection, replacement/repair of damaged parts, rectification of leakages, and restoration of proper functionality.</p> <p>The scope further includes surface preparation and application of paint coating complete in all respects. After completion of repair and painting work, the strainers shall be reinstalled/fixd in the line with proper alignment, tightening, and leak testing to ensure satisfactory operation of the system. (Removal of cladding and supply, installation of new cladding is included in job).</p>		JOB	16		
1.08	<p>Overhauling of HVAC lines NRV</p> <p>The scope of work includes dismantling and removal of NRVs (Non-Return Valves) from the existing pipeline system. The removed NRVs shall be</p>		JOB	16		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.09	<p>shifted to the workshop/site area for complete repair and overhaul, including cleaning, inspection, replacement/repair of damaged internal parts, seat and disc repairing, rectification of leakages, and restoration of proper operational condition.</p> <p>The scope further includes surface preparation and application of paint coating complete in all respects. After completion of repair and painting work, the NRVs shall be reinstalled/fixd in the line with proper alignment, tightening, and leak testing to ensure satisfactory and trouble-free operation of the system. (Removal of cladding and supply, installation of new cladding is included in job).</p> <p>De scaling and flushing of system</p> <p>The scope of work includes complete de-scaling, chemical cleaning, and flushing of the cooling water system from the cooling tower up to all associated pipelines, including the cooling water circuit, primary circuit, and secondary circuit of the chiller system.</p> <p>The work shall be carried out by using suitable circulation/flushing pumps and required accessories to ensure proper circulation of chemicals throughout the complete system. The bidder shall provide all required chemicals, consumables, equipment, tools, manpower, and temporary arrangements necessary for execution of the job.</p> <p>The scope further includes draining of contaminated water, flushing with clean water after chemical treatment, removal of scales/deposits/sludge from the system, and ensuring satisfactory flow and cleanliness of the complete circuit. The entire job shall be completed to the satisfaction of the concerned engineer.</p>		JOB	1		
1.10	<p>Supply and inst of flange 8 inch</p> <p>The scope of work includes removal and dismantling of the existing 8-inch flange from the pipeline system, including loosening/cutting of nuts, bolts, and associated fittings as required.</p>		JOB	6		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.11	<p>The work further includes supply, installation, alignment, and fixing of a new 8-inch flange complete in all respects, including provision of gasket, nuts, bolts, welding/fabrication work (if required), and tightening of joints. The scope also includes leak testing, cleaning, and commissioning after completion of installation to ensure satisfactory operation of the pipeline system. Flanges to be provided by contractor.</p> <p>Supply and inst of flange 2 inch</p> <p>The scope of work includes removal and dismantling of the existing 2-inch flange from the pipeline system, including loosening/cutting of nuts, bolts, and associated fittings as required.</p> <p>The work further includes supply, installation, alignment, and fixing of a new 8-inch flange complete in all respects, including provision of gasket, nuts, bolts, welding/fabrication work (if required), and tightening of joints. The scope also includes leak testing, cleaning, and commissioning after completion of installation to ensure satisfactory operation of the pipeline system. Flanges to be provided by contractor.</p>		JOB	8		
1.12	<p>Supply and inst of elbow 10 inch</p> <p>The scope of work includes dismantling and removal of the existing 10-inch elbow from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 10-inch elbow complete in all respects. The scope also includes provision of necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the line shall be carried out to ensure smooth and leak-free operation of the system. Elbows to be provided by contractor.</p>		JOB	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.13	<p>Supply and inst of elbow 4 inch</p> <p>The scope of work includes dismantling and removal of the existing 4-inch elbow from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 4-inch elbow complete in all respects. The scope also includes provision of necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the line shall be carried out to ensure smooth and leak-free operation of the system.</p>		JOB	12		
1.14	<p>Supply and inst of elbow 6 inch</p> <p>The scope of work includes dismantling and removal of the existing 6-inch elbow from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 6-inch elbow complete in all respects. The scope also includes provision of necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the line shall be carried out to ensure smooth and leak-free operation of the system.</p> <p>Elbows to be provided by contractor.</p>		JOB	2		
1.15	<p>Supply and inst of elbow 2 inch</p> <p>The scope of work includes dismantling and removal of the existing 2-inch elbow from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p>		JOB	10		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

30.06.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.16	<p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 2-inch elbow complete in all respects. The scope also includes provision of necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the line shall be carried out to ensure smooth and leak-free operation of the system.</p> <p>Elbows to be provided by contractor.</p> <p>Supply and inst of 45 deg elbow 8 inch</p> <p>The scope of work includes dismantling and removal of the existing 45 degree 8 inch elbow from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 45-degree elbow complete in all respects. The scope also includes provision of necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the line shall be carried out to ensure smooth and leak-free operation of the system.</p> <p>Elbows to be provided by contractor.</p>		JOB	1		
1.17	<p>Supply and inst of reducer seamless 6x4</p> <p>The scope of work includes dismantling and removal of the existing 6" x 4" reducer from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 6" x 4" seamless reducer complete in all respects. The scope also includes provision of all necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After</p>		JOB	6		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

30.06.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.18	<p>installation, proper cleaning and commissioning of the pipeline system shall be carried out to ensure smooth and leak-free operation. Reducer to be provided by contractor.</p> <p>Supp and inst of reducer seamless 12x10</p> <p>The scope of work includes dismantling and removal of the existing 12" x 10" reducer from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 12" x 10" seamless reducer complete in all respects. The scope also includes provision of all necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the pipeline system shall be carried out to ensure smooth and leak-free operation. Reducer to be provided by contractor.</p>		JOB	2		
1.19	<p>Supply and inst of reducer seamless 12x8</p> <p>The scope of work includes dismantling and removal of the existing 12" x 8" reducer from the pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 12" x 8" seamless reducer complete in all respects. The scope also includes provision of all necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the pipeline system shall be carried out to ensure smooth and leak-free operation. Reducer to be provided by contractor.</p>		JOB	2		
1.20	<p>Supply and inst Tee 6 inch</p> <p>The scope of work includes dismantling and removal of the existing 6-inch tee from the pipeline system, including cutting/disconnection of</p>		JOB	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1 . 21	<p>the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 6-inch tee complete in all respects. The scope also includes provision of all necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the pipeline system shall be carried out to ensure smooth and leak-free operation.</p> <p>Tee will be provided by contractor.</p> <p>Supply and inst of ball valve 1 inch</p> <p>The scope of work includes dismantling and removal of the existing 1-inch ball valves from the Air Handling Unit pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 6-inch tee complete in all respects. The scope also includes provision of all necessary consumables, joint preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the pipeline system shall be carried out to ensure smooth and leak-free operation.</p> <p>Valves to be provided by bidder.</p>		JOB	8		
1 . 22	<p>Supply and inst of pipe nipple 1 inch</p> <p>The scope of work includes dismantling and removal of the existing 1-inch pipe nipples from the Air Handling Unit pipeline system, including cutting/disconnection of the connected pipeline and removal of associated fittings as required.</p> <p>The work further includes supply, fabrication, installation, alignment, and welding/fixing of a new 6-inch tee complete in all respects. The scope also includes provision of all necessary consumables, joint</p>		JOB	8		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	12
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.23	<p>preparation, welding, grinding, fitting, and leak testing required for satisfactory completion of the job. After installation, proper cleaning and commissioning of the pipeline system shall be carried out to ensure smooth and leak-free operation.</p> <p>Pipe nipples to be provided by bidder.</p> <p>GI sheet for cladding 4 feet x 4 feet</p> <p>The scope of work includes supply, fabrication, and installation of GI sheet cladding measuring 4 ft. x 4 ft. complete in all respects. The work includes cutting, bending, shaping, and fixing of the GI sheet at the required location using necessary supports, fasteners, and accessories.</p> <p>The scope further includes removal of damaged/deteriorated cladding (if required), proper fitting and finishing of the new GI sheet cladding, and ensuring complete coverage and neat appearance after installation. All necessary tools, materials, labor, and consumables required for satisfactory completion of the job shall be included in the contractor's scope. Cladding to be provided by bidder.</p>		FT2	130		
1.24	<p>Supply and fixing Glass wool</p> <p>The scope of work includes supply and installation of glass wool insulation at the required area as per site conditions. The work includes cutting, fitting, and proper placement of glass wool with required thickness, ensuring full coverage of the specified surfaces.</p> <p>The scope further includes removal of existing damaged or deteriorated insulation (if any), surface preparation, and fixing of new glass wool with proper securing materials such as wire mesh, binding, or cladding supports as required. All necessary accessories, consumables, manpower <(>,<)> and tools required for satisfactory completion of the job shall be included in the contractor's scope, ensuring proper insulation performance and finishing.</p>		FT2	400		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	12
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>Glass wool to be provided by bidder.</p> <p>General Terms & Conditions =====</p> <p>The bidder must visit the location to understand the actual scope of work.</p> <p>The work has been included with supply of all the material and its fabrication and installation in complete respect.</p> <p>The quoted prices shall be deemed all-inclusive, covering the cost of materials, fabrication, labor, installation, transport-<,> loading/unloading, equipment usage, consumables, and tools required for the complete execution of the work.</p> <p>All applicable government taxes, duties be included in the quoted rates. No additional payment shall be made under these heads.</p> <p>Transportation and Logistics:</p> <p>The contractor shall be responsible for arranging transportation of all materials and equipment to and from the site at their own cost.</p> <p>All site handling, lifting, rigging, and storage of materials shall be done by the contractor using suitable equipment and manpower.</p> <p>Workforce and Supervision:</p> <p>The contractor shall deploy adequate and skilled manpower for timely and quality execution of work.</p> <p>A competent site supervisor must be available at all times during work execution to coordinate with the client's representative.</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

12	OF	12
RFQ No	LM19731AA	
DATE	15.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017011

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	30.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Replacement of Deteriorated Pipelines and Valves, Maintenance of Strainers and NRVs, and De-scaling of Complete HVAC System at LMT.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>Compliance with HSE Requirements:</p> <p>All activities shall strictly comply with PSO HSE (Health, Safety & Environment) standards and procedures.</p> <p>The contractor shall ensure that all personnel wear proper PPEs (Personal Protective Equipment) and adhere to safe work practices.</p> <p>Any unsafe act or non-compliance may result in work stoppage and necessary penalties.</p> <p>Material and Workmanship Quality:</p> <p>All materials used shall be new, certified, and of approved make.</p> <p>Workmanship must meet relevant engineering and industry standards, and any defective work shall be rectified at the contractor's cost.</p> <p>Work Schedule and Delays:</p> <p>The contractor shall complete the job within the agreed timeline. Any delay must be communicated in advance and duly justified.</p> <p>Penalties may apply for unjustified delays or failure to meet performance requirements.</p> <p>The work shall be complete within 30 days after issuance of PO.</p>					