



**PMDC**  
PAKISTAN MINERAL DEVELOPMENT CORP.

**Head Office**

Plot No: 13, Sector H/9, Islamabad 44000,  
Pakistan.  
Tel: 9265123-24  
E-mail: [info@pmdc.gov.pk](mailto:info@pmdc.gov.pk)  
[www.pmdc.gov.pk](http://www.pmdc.gov.pk)

**Invitation of E-BID**

Pakistan Mineral Development Corporation is an autonomous corporation under the administrative control of Ministry of Energy (Petroleum Division), Government of Pakistan invites electronic bids from the interested Parties/contractors having valid registration with Federal Board of Revenue (FBR)/Respective Revenue Boards for income tax & sales tax and who are on active taxpayer list (Income & Sales Tax) of the Federal Board of Revenue (FBR)/Respective Revenue Boards for "**Construction of Bachelor Rooms along with attached Washroom in Bungalow No. 05 at PMDC Collieries, Sharigh**"

E-Bidding documents containing detailed terms and conditions, method of procurement, bid security, opening of bid, etc. are available electronically and can be downloaded from EPADS-PPRA Website: <https://eprocure.gov.pk> free of cost.

The electronic bids, prepared in accordance with the instructions in the bidding document along with bid money **Rs.150,000/-** in the shape of demand draft/pay order from Schedule Bank in the name of Pakistan Mineral Development Corporation on account of bidder must be submitted by using **EPADs (1.0)** on or before **29.06.2026 at 11:00 AM**. Tenders will be opened on EPADs (1.0) on the same date at **11:30 AM** in the presence of participants who may desire to attend the tender opening.

**Note:-**

1. Original Bid Security Instrument Must be submitted to undersigned, before the online submission deadline of the bid; otherwise, respective bid will not be entertained.
2. In case of any technical difficulty in using EPADs, prospective bidders may contact PPRA Office, 1<sup>st</sup> Floor, FBC building Sector G-5/2, Islamabad. Contact Number 051-111-137-237.

**AVP (Procurement)**  
**PMDC Head Office, H-9/4, Islamabad**  
**Phone: 051-9265128**  
**E-mail: [dgm-pro@pmdc.gov.pk](mailto:dgm-pro@pmdc.gov.pk)**





**PMDC**  
PAKISTAN MINERAL DEVELOPMENT CORP.

**Head Office**

Plot No: 13, Sector H/9, Islamabad 44000,

Pakistan.

Tel: 9265123-24

E-mail: [info@pmdc.gov.pk](mailto:info@pmdc.gov.pk)

[www.pmdc.gov.pk](http://www.pmdc.gov.pk)

**Tender Enquiry No. Ref: No. PMDC/Pro/Room/SGH/  
DUE FOR OPENING ON: 29.06.2026 AT 11:30 AM**

Electronic bids are invited from the interested parties/contractors registered with Federal Board of Revenue (FBR)/Respective Revenue Boards for income tax & sales tax and who are on active taxpayer list (Income & Sales Tax) of the Federal Board of Revenue (FBR)/Respective Revenue Boards for following works at PMDC Collieries, Sharigh as per BOQ/Technical Specs given below :-

**SUMMARY OF COST**

| Sr. No. | Detail of Works  | Total Cost in PKR<br>(inclusive of all taxes) |
|---------|--|---|
| 01      | Construction of Bachelor Rooms along with attached washroom in Bungalow No. 05 at PMDC Collieries, Sharigh.<br><b>Specifications/Bill of Quantities as per Annex - A</b> |   |

**GENERAL TERMS AND CONDITION:**

1. Electronic Bid must be submitted on EPADs (1.0) on or before **29.06.2026 at 11:00 AM** which will be opened on the same day at **11:30 AM** in the presence of tenderers or their representatives who desire to participate.
2. Bid Money as per following detail in the form of pay order/demand draft made in the name of Pakistan Mineral Development Corporation on account of bidder from any scheduled bank shall accompany the bid/tender. Tender with less or without bid money (in the form of pay order/demand draft) or pay order/demand draft without the name of bidder shall not be considered:-

| Sr. No. | Detail of Works  | Bid Security        |
|---------|--|---------------------|
| 01      | Construction of Bachelor Rooms along with attached Washroom in Bungalow No. 05 for PMDC Collieries, Sharigh. | <b>Rs.150,000/-</b> |

3. Successful tender will be required to deposit security money @ 10% of the total value and bid money already deposited will be converted into security deposit while balance amount shall have to be deposited to maintain the Security deposit @ 10% of the total value which will be refunded after successful completion the DLP.
4. The successful bidder shall be required to furnish Integrity Pact if applicable, as per PPRA Rules.

4



5. Bidders meeting the required all mandatory required documents and relevant experience, will be considered Technical responsive among the technical responsive bidders the contract will be awarded to the bidder offering the lowest evaluated price.
6. The rates should be quoted in PKR and should be inclusive of all applicable/prevaling taxes. Any increase in taxes at any stage shall not be considered.
7. The rates, prices and amounts shall be entered against each item in the Schedule of Prices/BOQ. Any item against which no rate or price is entered by the bidder will not be paid for by the Employer when executed and shall be deemed covered by the rates and prices for other items in the Schedule of Prices.
8. Interpretation of the PMDC regarding the tendered rates in case of any discrepancy regarding unit rates and total amount shall be final.
9. Escalation of cost at any circumstances will not be permitted.
10. **Bidders are requested to visit the sites before quoting rates.**
11. The bidder will be responsible to carry out the works as per detailed mentioned in BOQ and the payment to the contractor shall be made on actual work done.
12. The work shall be executed using new, unused, and approved materials of specified quality, in accordance with best engineering practices, relevant codes, standards, and specifications. The execution shall ensure high quality workmanship, structural safety, durability, and full compliance with all applicable statutory requirements.”
13. No advance & running/interim payment will be applicable.
14. The Project Manager/Engineer may request samples of material to be installed in order to check its quality for approval purpose.
15. The quantity can be increased (up to 15% of the total contracted quantities/price) or decreased during the period of the contract at the sole discretion of PMDC without any prior notice to contractor.
16. No extra item shall be allowed to be executed without written orders from the concern Project Manager.
17. Concern Project Manager shall reserve the right to add/ delete any item from bill of quantities and the contractor will be responsible to execute any extra item required at site to complete the work and the payment for the same shall be made on mutually agreed rates.
18. The Water Charges shall be deducted at the rate of 1% of the contract price from the bill of the contractor. Electricity charges shall be deducted as per the prevailing per-unit rate against the actual consumed units from every bill submitted by the contractor, in accordance with applicable rules. The contractor shall install a sub-meter at his own cost for the purpose of recording electricity consumption at the site.
19. However, if PMDC resources (water and/or electricity etc.) are not used during execution of the work and the contractor arranges all such utilities at his own cost, then no deduction on account of water or electricity charges shall be made from the contractor’s bills.
20. The Contractor shall be responsible to make complete arrangements for the transportation/storage/security of the material etc. and the security/stay of his staff/workers.



21. Any damages to PMDC assets, HR of whatsoever nature shall be completely borne by the contractor.
22. The contractor shall execute works in a manner that daily operations/works of PMDC may not be affected.
23. Bids should remain valid for a period of 90 days from the date of opening of tenders. In case no specific date of validity is mentioned in the offer, it will be presumed to be valid for a period of 90 days from the date of opening of tender.
24. If the contractor fails to fulfill the contractual obligations of the contract, then the Security deposit will be forfeited.
25. All taxes will be applicable/deducted as per prevailing Government rules.
26. Firm/Contractor should be of sound financial health and shall provide Bank statement covering last 12 months (from the date of submission of bid).
27. Firm/Contractor must provide a list of the construction machinery and equipment available with the tenderer.
28. The Firm/Contractor should have 03 years' experience in relevant Project/ work with Govt. departments and other organizations/companies. Proof of relevant experience/work order as well as satisfactory completion certificates should be attached.
29. The tender for the supply / work will be completed / delivered at PMDC Collieries, Sharigh.
30. Completion time period of project will be 04 months. In case of delay, LD Charges @ rate 0.05% of total contract value will be applied per day upto 10 % of Total Contract Value.
31. Defect liability period (DLP)/warranty is 12 months, which will be start from the issuance of completion certificate.
32. If the Supplier/Contractor, having been notified, fails to remedy the defect(s) within the specified period, PMDC may proceed to take such remedial action as may be necessary, at the Supplier's risk and expense.
33. The successful Bidder will have to execute a contract within the specified time, Final Bill Payment will be made after satisfactorily completion work as per specification and on submission of the bill in duplicate along with satisfactory completion certificate/ report whereas security deposit/ Retention Money will be disbursed after expiry of DLP/warranty period which is 12 Month from the date of completion of project..
34. The authorized representative of the bidder/bidding firm will only be allowed to sit in the tender opening on presentation of authority letter from the bidder/bidding firm issued in favor of representative to participate in the specific tender.
35. Firm/Contractor or any its subsidiary firms or of its directors/owners or any their relatives' parents, children, brother, sister) should not be under litigation with PMDC in any local or foreign court law.
36. Firm/Contractor or any its subsidiary firms or of its directors/owners or any their relatives' parents, children, brother, sister) should not have any ongoing, under resolved business dispute with PMDC, PMDC shall be sole judge of fulfillment of this requirement.



37. Firm/Contractor or any its subsidiary firms or of its directors/owners or any their relatives' parents, children, brother, sister) should not have any direct or indirect conflict of interest with the procuring agency.
38. In case of any dispute regarding this purchase order/assignment, the same will be resolved between the relevant parties through negotiations. If negotiations shall fail, then matter will be referred to the Arbitrator. The MD, PMDC will act as sole Arbitrator as per Arbitration Act, 1940. Decision/award of Arbitrator will be final and binding on the both parties.
39. The tenderer/supplier shall appoint a representative at the project and furnish his postal address and contact number to PMDC. Any notice to be served on or document to be signed by the contractor shall be either delivered personally or through the representative and in case it is not possible it shall be treated to have delivered if it has been mailed by registered post on the Postal Address of the representative.
40. PMDC Reserved the right to accept or reject the tender of the tenderer at any time without assigning reasons and cannot be challenged in any court of law.
41. The tenderer/supplier will be blacklisted who is found to the tender process by making coercive practices, collusive practices, corrupt practices, fraudulent practices & obstructive practices.
42. I agree to the above terms and conditions and give my acceptance.
43. Checklist of documents to be attached.

Note: Please feel no hesitation to contact the Officer Incharge, PMDC Branch Office, Quetta regarding any query in this regard. Monday to Saturday 08:00 A.M to 2:00 P.M on Phone No.081-9201103.

Signature of tenderer: \_\_\_\_\_

Name of tenderer: \_\_\_\_\_



A handwritten signature in black ink, appearing to read "Sajid Hussain".

(Sajid Hussain)

AVP (Procurement)

PMDC Head Office, H-9/4, Islamabad

Phone: 051-9265128

E-mail: dgm-pro@pmdc.gov.pk

## MATERIAL SPECIFICATIONS/BRANDS TO BE USED

| Sr. No. | Item                              | Brand/Make  |
|---------|-----------------------------------|---|
| 1       | Bricks                            | 1 <sup>st</sup> class brick or approved Eqv.                |
| 2       | Sand                              | Local available Premium Quality                             |
| 3       | Crush                             | Local available Premium Quality                             |
| 3       | Cement                            | Bestway, Maple or approved Eqv.                             |
| 4       | Tiles                             | Times/Master or approved Eqv.                               |
| 5       | Paint/Weather shield              | Berger, ICI Dulux or approved Eqv.                          |
| 6       | Aluminum                          | Alco or approved Eqv. 2.0mm or 1.6mm as per site            |
| 7       | Glass                             | Ghani or approved Eqv.                                      |
| 8       | Lamination Sheet                  | ZRK/Patex or approved Eqv.                                  |
| 9       | Wood                              | Kail or approved Eqv.                                       |
| 10      | Conduits                          | Adam Jee or approved Eqv.                                   |
| 11      | Wires                             | Pakistan/Fast Cables  |
| 12      | Electric Switches/Socket etc.     | TJ or approved Eqv.   |
| 13      | Breakers                          | Chint or approved Eqv.                                      |
| 14      | Lights                            | Osaka or approved Eqv.                                      |
| 15      | Fans                              | GFC or approved Eqv.  |
| 16      | Sanitary Pipes                    | Minhas, Popular or approved Eqv.                            |
| 17      | Sanitary Fixtures                 | Faisal or approved Eqv.                                     |
| 18      | Commode (Indian & English), Basin | Three Star or approved eqv.                                 |
| 19      | False Ceiling                     | Arish with Aluminum T, channel etc. of CMK or approved eqv. |



### Check List

| Sr. No. | Description   | Yes     | No           |     |       |    |              |  |  |  |  |
|---------|---|---------|--------------|-----|-------|----|--------------|--|--|--|--|
| 1       | Original Bid money as per following detail is attached/handed over to the PMDC :-<br><table border="1" style="margin-left: 20px;"><thead><tr><th>Sr. No.</th><th>Bid Security</th><th>No.</th><th>Dated</th></tr></thead><tbody><tr><td>1.</td><td>Rs.150,000/-</td><td></td><td></td></tr></tbody></table> | Sr. No. | Bid Security | No. | Dated | 1. | Rs.150,000/- |  |  |  |  |
| Sr. No. | Bid Security  | No.     | Dated        |     |       |    |              |  |  |  |  |
| 1.      | Rs.150,000/-  |         |              |     |       |    |              |  |  |  |  |
| 2       | List of the construction machinery and equipment available with the tenderer.   |         |              |     |       |    |              |  |  |  |  |
| 3       | Copy of CNIC and Authority Letter.  |         |              |     |       |    |              |  |  |  |  |
| 4       | Copy of registration certificate with FBR/relevant authority department.  |         |              |     |       |    |              |  |  |  |  |
| 5       | Copies of experience certificate, work orders as well as completion/performance certificate not less than 03 years.   |         |              |     |       |    |              |  |  |  |  |
| 6       | List of technical staff available with the tenderer who will execute/ supervise the work.   |         |              |     |       |    |              |  |  |  |  |
| 7       | Financial Soundness Proof (Bank Reference or Bank Statement, Audited Report / Accounts).  |         |              |     |       |    |              |  |  |  |  |
| 8       | Affidavit of No litigation with PMDC.   |         |              |     |       |    |              |  |  |  |  |
| 9       | Affidavit regarding No dispute with PMDC.   |         |              |     |       |    |              |  |  |  |  |
| 10      | Affidavit regarding No conflict of interest with PMDC.  |         |              |     |       |    |              |  |  |  |  |



**Tenderer/Bidder Signature**

## BILL OF QUANTITIES (BOQ)

### Construction of Bachelor Rooms along with attached Washroom in Bungalow No. 05 at PMDC Collieries, Sharigh

| Sr. No. | Description  | Unit | Qty | Unit Rate in PKR<br>(inclusive of all<br>taxes) | Total Amount<br>in PKR (inclusive of all<br>taxes) |
|---------|--|------|-----|---|--|
| 1       | Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m) Shingle or gravel. Complete in all respect.  | 2175 | Cft |   |  |
| 2       | Providing and laying cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) & down gauge in foundation including leveling, compacting and curing. 1 : 4 : 8. Complete in all respect.  | 310  | Cft |   |  |
| 3       | Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and ground floor including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such overlaps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height. Complete in all respect. | 1900 | Kg  |   |  |
| 4       | Providing and laying cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) & down gauge in foundation including leveling, compacting and curing. 1 : 2 : 4. Complete in all respect.  | 930  | Cft |   |  |
| 5       | Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi/2000psi) including scaffolding, raking out joints and curing in foundation and substructure/Basement i/c cost of testing Cement Sand 1 : 2. Complete in all respect.  | 870  | Cft |   |  |
| 6       | Providing and laying 1" (25mm) thick damp proof course with 1:2:4 cement concrete using Coarse Sand and crushed aggregate 1/2" (13mm) and down gauge mixed with any approved water proofing agent including compacting, curing, formwork and its removal cost of water proofing agent will be paid separately. Complete in all respect.  | 580  | Sft |   |  |
| 7       | Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and ground floor including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such overlaps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height. Complete in all respect. | 800  | Kg  |   |  |
| 8       | Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm.) and down gauge in plinth band, door band and roof band of required shape or section including formwork and its removal, compacting and curing in basement and ground floor but excluding the cost of reinforcement. Plinth band. Complete in all respect.   | 90   | Cft |   |  |
| 9       | Providing and laying first class solid burnt brick masonry (Brick Strength:1800psi-2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing Above 4.5" (115mm) nominal thick brick work Cement sand 1 : 2. Complete in all respect.   | 1220 | Cft |   |  |
| 10      | Providing and laying in situ cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) and down gauge in pillars and columns of any shape in super structure including compacting, curing, cost of form-work & its removal in basement and ground floor. 1 : 1 : 2. Complete in all respect.  | 80   | Cft |   |  |



|    |  |      |     |  |  |
|----|--|------|-----|--|--|
| 11 | Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and ground floor including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such overlaps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height. Complete in all respect. | 1000 | Kg  |  |  |
| 12 | Filling, watering and compacting earth under floors in layers not exceeding 8 inches in thickness. With new earth excavated from outside, lead upto 100 ft. (30m) and lift upto 5 ft. (1.5m) including royalty of Clay. Complete in all respect.   | 1680 | Cft |  |  |
| 13 | Providing and laying 1:2:4 cement concrete floor using using crushed aggregate 3/4" (19mm) and down gauge in ground floor laid in panels including formwork, consolidation, finishing and curing. 5" (125 mm) nominal thick flooring. Complete in all respect.   | 1120 | Sft |  |  |
| 14 | Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and ground floor including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such overlaps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height. Complete in all respect. | 850  | Kg  |  |  |
| 15 | Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm.) and down gauge in plinth band, door band and roof band of required shape or section including formwork and its removal, compacting and curing in basement and ground floor but excluding the cost of reinforcement. Plinth band. Complete in all respect.   | 90   | Cft |  |  |
| 16 | Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and ground floor including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such overlaps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m).                                 | 3000 | Kg  |  |  |
| 17 | Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) and down gauge in slabs including formwork and its removal, compacting and curing Upto 6" (150 mm) thickness In basement, plinth and ground floor. Complete in all respect.  | 840  | Cft |  |  |
| 18 | Cement plaster using Coarse Sand on soffits of ceiling, cantilever slabs, sides and soffits of beams, in basement and ground floor including making edges, corners and curing. 1/2 inch (13mm) thick cement sand plaster 1 : 3. Complete in all respect.   | 1120 | Sft |  |  |
| 19 | P/L 3/4 inch (19mm) thick cement plaster using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. 1 : 3 15-4-ii)  | 3320 | Sft |  |  |
| 20 | Applying weather resistant paint coating such as ICI weather shield, Berger weather coat or equivalent to interior or exterior walls or ceiling including supplying all labour, materials, scaffoldings and removal of debris etc. @ atleast 3.50 litre per 10 Sq.m. Complete in all respect.  | 3320 | Sft |  |  |
| 21 | Painting with ICI/Berger or equivalent super gloss synthetic enamel paint in two or more coats as per manufacturer's instructions on wood work over and including the cost of priming coat, surface preparation, rubbing down smooth, knotted, filling cracks, holes and joints in ground floor or basement. (@ atleast 1.65 Litre per 10 Sq.m) Complete in all respect.   | 3320 | Sft |  |  |



|    |  |      |        |  |  |
|----|--|------|--------|--|--|
| 22 | Painting with ICI/Berger or equivalent super gloss synthetic enamel paint in two or more coats as per manufacturer's instructions on steel and iron work over and including the cost of priming coat, surface preparation, removing rust, scales and dust with wire brush in ground floor or basement. (@ atleast 1.25Litre per 10 Sq.m). Complete in all respect.   | 3320 | Sft    |  |  |
| 23 | Providing and fixing First class deodar wood shutters fully panelled with same wood and fixed with approved brass hinges and tower bolts. Complete in all respect.   | 145  | Sft    |  |  |
| 24 | Providing and fixing moulded steel door frame of approved profile, manufactured from zinc-coated mild steel sheets 16 gauge made by Shahah Industries or equivalent standard conforming to B.S.S.1245, treated with special primer base paint all round, fitted with six fixing lugs, three steel hinges for fixing door shutters standard lock-strike plate, one sliding holt eye, and three rubber buffers, including cutting holes and making good damages to walls and floor & any other surface. Complete in all respect.                 | 126  | Rft    |  |  |
| 25 | Providing and fixing fully glazed single leaf hung/sliding aluminium windows, ventilators (Deluxe model - 1.6mm) of anodized champagne or approved color of Prime, Chawala, Pakistan Cable or any approved section as approved by Engineer incharge including aluminium fittings, 5 mm local tinted glass, lugs, cutting holes and and making good the damages to walls. Complete in all respect.  | 40   | Sft    |  |  |
| 26 | Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing. Complete in all respect.   | 1120 | Sft    |  |  |
| 27 | Providing and fixing 3/8" (9mm) thick super white marble tiles dressed on the surface in dado/skirting and facing in ground floor over 1/2" (13mm) thick base of cement sand mortar 1:3, setting of tiles in slurry of grey cement over mortar base including filling the joints and washing the tiles with white cement slurry, curing, finishing, grinding, cleaning & polishing. Complete in all respect.   | 900  | Sft    |  |  |
| 28 | Providing and fixing squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC down pipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. W.C. Indian/Desi/902 with glazed earthen ware 4" (100 mm) trap. Complete in all respect.   | 2    | Nos.   |  |  |
| 29 | Providing and fixing approved quality white glazed earthenware lavatory basin with 1/2" (15 mm) dia. single hole C.P. mixer tap, 2 way deluxe pillar tap, stop cocks, 6" C.I. or W.I. brackets built into walls, rubber plug, C.P. brass chain, C.P. brass waste, malleable iron or C.P. brass bottle trap with malleable iron or brass union and making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. Lavatory basin 22" x 16" (550 mm x 400 mm). Complete in all respect. | 3    | Nos.   |  |  |
| 30 | Providing and fixing approved quality glazed fire clay sink 24" x 18" with 6" (150mm) size C.I. or W.I. brackets built in walls, 1.5" (40 mm) rubber plug and C.P. brass chain, C.P. brass waste, pillar tap 2 way deluxe, malleable iron or C.P. brass trap and unions and making requisite numbers of holes in walls, plinth and floor for pipe connections and making good with approved material. Complete in all respect.   | 3    | Nos.   |  |  |
| 31 | Providing and Installing uPVC pipe ILL, Dadex or equivalent make registered with PSQCA in sewerlines and/or laying, cutting, jointing, testing including all specials in pipe lines in trenches. Class B, 4" (100 mm) dia. Complete in all respect.  | 172  | Rft    |  |  |
| 32 | Providing and fixing standing shower concealed in wall with approved quality control valves, mixer unit and moveable shower head. Complete in all respect.   | 2    | Nos.   |  |  |
| 33 | Light circuit concealed/open wiring with length upto 65 ft. (20m) from distribution board to point/switch with 3x2.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables for offices/multi storeyed buildings. Complete in all respect.  | 50   | Points |  |  |



|   |  |     |        |  |  |
|---|--|-----|--------|--|--|
| 34  | Open pipe wiring with M.S. conduit and accessories such as bends, elbows, junction boxes etc. Light circuit concealed/open wiring with length upto 65 ft. (20m) from distribution board to point/switch with 3x2.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables for offices/multi storeyed buildings. Complete in all respect.  | 50  | Points |  |  |
| 35  | Supply and install 25 sq.mm PVC insulated single core 600/1000V.cable with copper conductor in already concealed PVC conduit. Complete in all respect.   | 400 | Rft    |  |  |
| 36  | Supply and install weather proof incandescent light fixture comprising die-cast aluminium body with front glass cover fixed to the body by means of stainless steel screws and neoprene gasket, G.I. wire guard, 1 No 100W lamp, including all installation material Philips type or approved equivalent. Complete in all respect.   | 10  | Nos.   |  |  |
| 37  | Supply, install, connect Ceiling Fan energy efficient model as approved and rated 3- Star by NEECA with power consumption of less than 50 W+10% Complete in all respect.   | 5   | Job    |  |  |
| 38  | Provide, install, test and commission recessed wall mounting type distribution board fabricated from 16 SWG steel sheet, powder coated with approved color back box comprising one incoming MCCB-TP/60A and outgoing 9 single phase MCB of various capacity having overload & short circuit protection and of 6 KA braking capacity complete with internal wiring earthing, neutral link, termination blocks, phase indicating lights alongwith 500V voltmeter. Complete in all respect. | 3   | Nos.   |  |  |
| <b>G. Total in PKR (inclusive of all taxes)</b> |  |     |        |  |  |

