



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Services</u>	<u>New</u>				
		<u>Faisalabad</u>				
		<u>(Depot)</u>				
1.01	<u>Cutting, removal of steel structure</u>		<u>KG</u>	300.000		

	Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad					

	Salient Scope of Work:					
	#, #, #, #,					
	1), Dismantling and removal of existing deluge piping from T-7001 & T-7002.					
	2), Mechanical works for re-routing of deluge pipeline from back of the tanks to the front.,					
	3), Fabrication and erection of sprinkler supports on T-7001., #, #, #, #, #,					
	4), Piping works for installation of sprinkler system on T-7001.,					
	5), Dismantling and removal of existing sprinkler piping from T-7002. #, #, #, #,					
	6), Mechanical works for re-routing of sprinkler pipelines from back of T-7002 to the front., #,					
	#, #, #, #,					
	7), Civil works for construction of pipeline sleepers and foundation.,					
	8), Painting works on the new pipeline system., #					
	., #, #, #, #,					
	9), Supply of pipeline, fittings, valves and sprinkler nozzles material.					
	”					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.02	Cutting of Existing Structure Cutting, removal and dismantling of the existing Structure, Steel Plates, Staircase, Supports, walkways, Platforms, Railings, pipe bridge, shed etc. as per instructions of PSO Project Engineer. The job also includes stacking of the same structure within the Terminal premises of PSO as per instruction of PSO Project Engineer. Note: All types of consumables (gas etc.) & scaffoldings required for the cutting, removal & dismantling job shall be provided by Contractor, without any additional cost. <u>FABRICATION WORKS</u> Fabrication Works ” Fabrication, erection, installation & welding of all structure steel works for tank appurtenances such as crossover platforms, pipe sleepers, field supports, foam / water sprinkler supports etc. complete in all respect in accordance with specs., drawings and instructions of PSO site engineer. Job also includes shifting (including loading and unloading) materials required to carryout the above work from site store to work site as per instruction of PSO site engineer. All handling, supporting, lifting, laying, placing in position, aligning, cutting, machining, bending, rolling, forging, drilling, grinding, fabrication and welding in position of steel plates, structural and or other similar material as required for the construction of the above defined items of works is included in this item.,, NOTE:,, a,,Cost of welding qualification procedure tests, destructive tests from shipyard (or other PSO approved company) & welder tests are included in		<u>KG</u>	2,000.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	scope. The contractor shall submit his welding procedure and reports to the owner's representative for approval., b,,All types of consumables (welding electrodes, gas etc.) required for the fabrication, erection, installation & welding job shall be provided by Contractor, without any additional cost., <u>SCAFFOLDING</u> Contractor to provide Scaffolding and Staggering Platform in-accordance with Safety requirements for the execution of work for construction. The job includes erection & dismantling of scaffolding / staggering platform for tank (inside and outside) entire mechanical work, grit blasting & painting works inside and outside during the entire course of project. Scaffolding / staging platform shall be the responsibility of contractor. Scope of work also include providing and fixing of of metal planks platform, bracing, provision of step ladders and lifeline, etc. as applicable. The contractor will also bear the cost of third party inspection and certification of the scaffolding. All direct / indirect cost of material, labour, transportation required to carry out the activity is included in this item.		<u>EA</u>	1		
1.04	<u>Grit Blasting</u> Grit Blasting Grit blasting (Local or Imported garnet / copper slag) for outer surface of Tank bottom, shell, roof, underground/above ground pipeline, steel structure to near white metal surface to the satisfaction of PSO Engineer completely stain free surface. Follow the standard of surface preparation to Swedish Standard SIS 055900 Sa-2-1/2 or Steel Structures Painting Council SSPC-SP10 (i.e #near white" blasted finish). Any solvent required clean greasy spots to be supplied by the contractor.		<u>M2</u>	250		
1.05	<u>Providing and applying Paint</u> Coating of tank outer shell / pipeline etc.		<u>M2</u>	250		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	Coating of Tank outer shell, staircase, platforms, pipeline as per specifications attached in Annexure (PSO-PS-01 Rev-0 dated: 30.08.2019). Notes: 1. Color scheme may change as per PSO requirements. 2. Minimum no. of coats and Drying Time to be provided in accordance with paint manufacturer recommendations. 3. Arrangement of Instrument for measurement of paint thickness is included in contractor scope. 4. Contractor to submit technical literature / brochure of paint and obtain prior aprocal from PSO before procurement of material. <u>Providing and applying Paint</u> Coating of Tank outer shell / pipeline etc (Existing paint available)		<u>M2</u>	10		
1.07	Coating of Tank outer shell, staircase, platforms, pipeline as per specifications attached in Annexure (PSO-PS-01 Rev-0 dated: 30.08.2019). Notes: 1. Color scheme may change as per PSO requirements. 2. Minimum no. of coats and Drying Time to be provided in accordance with paint manufacturer recommendations. 3. Arrangement of Instrument for measurement of paint thickness is included in contractor scope. 4. Contractor to submit technical literature / brochure of paint and obtain prior aprocal from PSO before procurement of material. <u>Mechanical cleaning</u> Mechanical cleaning Mechanical cleaning of external surface of tank shell, allied pipelines, platform, structural supports, etc. as per instructions of PSO engineer. All equipment, material labour required to be provided by the contractor.		<u>M2</u>	10		
1.08	<u>Application of Red Lead Primer</u>		<u>M2</u>	10		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.09	<u>Application of enamel</u>		<u>M2</u>	10		
1.10	<u>Radiographic Testing</u> Radiographic Testing of the Pipeline,, Radiographic Testing of Pipeline (wherever required) as per standard and as per satisfaction of PSO Engineer. All arrangement for Radiographic Testing and availability of equipment to be made available by contractor. NOTE: 1 EA includes quantity of weld joints on a pipeline.,, #,, 08" dia,,		<u>EA</u>	10		
1.11	<u>Radiographic Testing</u> Radiographic Testing of the Pipeline,, Radiographic Testing of Pipeline (wherever required) as per standard and as per satisfaction of PSO Engineer. All arrangement for Radiographic Testing and availability of equipment to be made available by contractor. NOTE: 1 EA includes quantity of weld joints on a pipeline.,, #,, 06" dia,,		<u>EA</u>	5		
1.12	<u>Radiographic Testing</u> Radiographic Testing of the Pipeline,, Radiographic Testing of Pipeline (wherever required) as per standard and as per satisfaction of PSO Engineer. All arrangement for Radiographic Testing and availability of equipment to be made available by contractor. NOTE: 1 EA includes quantity of weld joints on a pipeline.,, #,, 04" dia,,		<u>EA</u>	3		
1.13	<u>Dye Penetrant Testing</u> Dye Penetrant Testing of Pipeline,, #,, DPT of weld joints as per ASME Section V,,		<u>EA</u>	20		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.14	08" dia,, <u>Dye Penetrant Testing</u> Dye Penetrant Testing of Pipeline,, #,, DPT of weld joints as per ASME Section V,,		<u>EA</u>	15		
1.15	06" dia,, <u>Dye Penetrant Testing</u> Dye Penetrant Testing of Pipeline,, #,, DPT of weld joints as per ASME Section V,,		<u>EA</u>	15		
1.16	04" dia,, <u>Hydrostatic testing of Pipe 8" dia</u> Hydrostatic testing of complete pipeline system as per API. 1110, recommended practice for the pressure testing of liquid petroleum pipelines. All pipeline, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be provided by Contractor.,, #,, 08" dia,,		<u>M</u>	252		
1.17	<u>Hydrostatic testing of Pipe 6" dia</u> Hydrostatic testing of complete pipeline system as per API. 1110, recommended practice for the pressure testing of liquid petroleum pipelines. All pipeline, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be provided by Contractor.,, #,,		<u>M</u>	156		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.18	06" dia,, <u>Hydrostatic testing of Pipe 4" dia</u> Hydrostatic testing of complete pipeline system as per API. 1110, recommended practice for the pressure testing of liquid petroleum pipelines. All pipeline, testing equipment and labour to be arranged by the contractor. Water for hydrostatic testing to be provided by Contractor.,, #,, 04" dia,,		<u>M</u>	75		
1.19	<u>Cutting / Removal of Pipelines 8" dia</u> Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO terminal and stacking the same in position for safe store-keeping within the depot premises as per sizes below: 08" dia		<u>M</u>	112		
1.20	<u>Cutting / Removal of Pipelines 6" dia</u> Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO terminal and stacking the same in position for safe store-keeping within the depot premises as per sizes below: 06" dia		<u>M</u>	48		
1.21	<u>Cutting / Removal of Pipelines 4" dia</u> Cutting, removal and transportation of existing above ground / underground pipeline / pipings and pipe fittings etc. From site within the PSO terminal and stacking the same in position for safe store-keeping within the depot premises as per sizes below: 04" dia		<u>M</u>	54		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.22	<u>Shifting and Placing of Pipes 8" dia</u> Shifting and placing pipes & fittings in position underground , aboveground pipe for welding or screwing, as per sizes below: 08" dia		<u>M</u>	252		
1.23	<u>Shifting and Placing of Pipes 6" dia</u> Shifting and placing pipes & fittings in position underground , aboveground pipe for welding or screwing, as per sizes below: 06" dia		<u>M</u>	156		
1.24	<u>Shifting and Placing of Pipes 4" dia</u> Shifting and placing pipes & fittings in position underground , aboveground pipe for welding or screwing, as per sizes below: 04" dia		<u>M</u>	75		
1.25	<u>Making weld joints of Pipes 8" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures:,, Note: ,, 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint.,, 2) The welding joints also includes the tie- connections in the pipelines. Branch pipe connection will be considered for welding joint. ,, #,, 08" dia,,		<u>EA</u>	130		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.26	<u>Making weld joints of Pipes 6" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures:,, Note: ,, 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint.,, 2) The welding joints also includes the tie- connections in the pipelines. Branch pipe connection will be considered for welding joint. ,, #,, 06" dia,,		<u>EA</u>	52		
1.27	<u>Making weld joints of Pipes 4" dia</u> Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures:,, Note: ,, 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint.,, 2) The welding joints also includes the tie- connections in the pipelines. Branch pipe connection will be considered for welding joint. ,, #,, 04" dia,,		<u>EA</u>	30		
1.28	<u>Making weld joints of Pipes ½" dia</u>		<u>EA</u>	50		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.29	Making weld / thread joints as per ASME B 31.3 and API 1104 in CS pipe in joining pipe lengths and in welded pipe fittings such as flanges, bends, elbows, reducers tees etc. The job includes beveling, preparation of threads in piping (for threaded piping), flame cutting, grinding etc. All welding to be in accordance with relevant standard & done using specified welding procedures:,, Note: ,, 1) The welding of both the faces of S.O. R.F. flanges will be considered as one welding joint.,, 2) The welding joints also includes the tie- connections in the pipelines. Branch pipe connection will be considered for welding joint. ,, #,, 1/2" dia,, <u>Bolting flanged joints in Pipes 8" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. Rates should include cost of gasket rings (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20) , STUD BOLTS (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below: 08" dia		EA	10		
1.30	<u>Bolting flanged joints in Pipes 6" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. Rates should include cost of gasket rings (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20) , STUD BOLTS (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below:		EA	7		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.31	06" dia <u>Bolting flanged joints in Pipes 4" dia</u> Bolting-up flanged joints in pipelines / pipings with gaskets in between flanges , as per sizes below. Gaskets will be provided by the contractor. Rates should include cost of gasket rings (150 #, 3mm Thick Compressed Graphite filled, Spiral Wound 304 S.S. Central Ring per ASME B 16.20) , STUD BOLTS (studs with 2 nuts as per ANSI B 16.5, Stud Material A 193 Gr. B7 & Nuts Material A194 Gr 2H) and of specified standards & ratings as per sizes given below:		<u>EA</u>	4		
1.32	04" dia <u>Unbolting of flanged joints</u> Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>EA</u>	6		
1.33	08" dia <u>Unbolting of flanged joints</u> Unbolting flanged joints in pipelines / pipings as per sizes below.		<u>EA</u>	4		
1.34	06" dia <u>Unbolting of flanged joints</u> Unbolting flanged joints in pipelines as per sizes below.		<u>EA</u>	4		
1.35	04" dia <u>Installation of Valve 8" dia</u> Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as		<u>EA</u>	4		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

12	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.36	per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 08" dia <u>Installation of Valve 6" dia</u> Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 06" dia		EA	1		
1.37	<u>Installation of Valve 4" dia</u> Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel / forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 04" dia		EA	2		
1.38	<u>Installation of Valve ½" dia</u> Placing / removing in position in pipelines / pipings, all ratings / class flanged end or screwed end valves of all types (cast steel /		EA	50		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

13	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.39	forged steel body gate valve, ball valve, globe valve, check valve with flapper seat of stainless steel type), gauges, strainers, foot valve, fire water monitors, fire water hydrants, water spray nozzles, expansion joints, or other similar devices having flanged ends or screwed ends as per sizes given below. The job does not include bolting up of flange joints but includes loading transporting and unloading at site all valves etc. 1/2" dia Excavation Excavation,, Excavation in all kinds of strata / soil (dry or wet, hard or soft, etc) including clearing and grubbing of site complete in all respects, including all operation, complete with breaking clods, levelling, dressing, dewatering, shoring & compacting. Also include backfilling of excavated stuff inclusive of breaking clods, dressing, watering and consolidating by ramming (by power roller, mechanical rammer, plate vibrator, roller of suitable size or other approved equipment as per instructions of PSO Site Engineer) in layers not exceeding 6" depth. 95% modified AASHTO density to be achieved where applicable. Lifting, shifting or disposing of surplus strata outside the premises or as per instructions & approval of PSO Engineer area also included in this item. Contractor will carryout compaction test as per specification & instructions (where required by PSO) without any extra cost.,, Note: Excavation dimensions as per approved drawing / PSO instruction shall be considered for measurement / payment. Cost includes Compaction Test and other related tests to be carried out (where required) through approved laboratory to be arranged and paid by the contractor. No extra charges/payments will be paid to contractor.,,		M3	10.000		
1.40	Stone Soling Stone Soling Providing and laying stone soling of approved quality under foundations, plinth, floors, hard standing etc including hand packing vertically and		M3	5.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

14	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.41	filling voids with spawels (stone dust), consolidating and compacting with mechanical means, as per instructions of PSO Engineer. <u>Laying of CC 1:2:4 S.R Cement</u> Concrete CC 1:2:4,, Providing and laying CC 1:2:4 (using S.R cement) of specified strength using approved quality 3/4" max. size graded crushed stone and and fine aggregate of required properties including water tight approved form work, mixing, transporting, placing, levelling, compaction, rodding, vibrating, finishing and curing etc. scaffolding, racking out and cleaning, excluding cost of reinforcement, complete in all respects and as per instructions of PSO Engineer. Cube test for finding the crushing strength of concrete will be carried out to confirm the desired strength at contractors own cost i.e. (3000 psi at 28 days, 2100 psi at 7 days). The cube tests will be carried out by contractor from PSO approved laboratory or as per instruction of PSO site Engineer. Cost also includes preparation of construction joints as per site conditions, specifications and directions of Engineer Incharge.,, Note: NEW-PAGE 1) No extra charges/payment will be made for cube testing. NEW-PAGE 2) C.C 1:2:4 dimensions as per approved drawing/ PSO instruction shall be considered for measurement / payment.,,		<u>M3</u>	5.000		
1.42	<u>Laying of CC 1:4:8 S.R. Cement</u> Concrete CC 1:4:8,, Providing and laying C.C. 1:4:8 with S.R.Cement specified strength at any level using approved quality 3/4" max. size graded crushed stone and fine aggregate of required properties of approved source including water tight approved form work (installation & removal), mixing, transporting, placing, compacting, vibrating, finishing and curing etc., scaffolding, racking out and cleaning complete in all respects and as per instructions of PSO Engineer. Note: C.C 1:4:8 dimensions as per approved drawing/ PSO instruction		<u>M3</u>	2.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

15	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.43	shall be considered for measurement / payment.,, <u>Providing and applying Cement Plaster</u> Plaster,, Providing and applying cement plaster 3/4" thick in 1:4 cement sand mortar (using SR cement) to walls, base including all corners, recesses, jams and racking out joints, roughing the surfaces and cement slurry backing to all surfaces, curing and scaffolding. This job also includes using of pudlo 5 lbs per bag of cement. All work will be carried out as per instructions of PSO Engineer.,,		<u>M2</u>	25		
1.44	<u>PB4 CONCRETE WAT.PROOF.</u> PB4 Hot Bitumen,, Providing & applying PB4 Hot/Cold Bitumen of approved make with water proof chemical on foundations (inside/ outside) upto plinth level to sides and top of footings, situ walls, columns, sides of plinth beams and floor etc. as per manufacturer recommendations including cost of all material, labour, equipments complete as per specification and as directed by the PSO Engineer Incharge.,,		<u>M2</u>	20		
1.45	<u>Dismantling of Existing Civil Structure</u> Dismantling of existing civil structure including foundation, supports, pedestals, pavements, tank wall, roof, tank bottom or any other structure to a varying depth as required. This Job also includes removal of deformed steel from the civil structure, shifting of debris outside the terminal to a suitable place, general cleaning of the site and shifting of useful material on proposed location complete in all respect as advised by Site Incharge / Engineer.		<u>M3</u>	5.000		
1.46	<u>BRICK / BLOCK MASONARY</u> Providing & laying first class brick / machine made block masonry (in super structure using graded screened 'Bajri') in SR cement of specified thickness set in 1:4 cement sand mortar. The job includes required scaffolding, staging, racking out, curing D.P.C. etc. & cleaning and provision of expansion joints & 15 days water curing of masonry. The		<u>M3</u>	3.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

16	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.47	complete Job to be done as per directives of PSO Engineer. Supply & application of expansion joint is included in this item. <u>Providing and laying TOR steel reinforce</u> Installation of deformed steel reinforcement bars including straightening, removing twists, cutting, bending, binding, wastage and overlaps, placing in position on precast cc chairs, tying with binding wire 18 SWG, complete as per instructions of the PSO Engineer. Only actual laid quantities will be considered for payment. Deformed steel reinforcement of yield strength 60000psi.		<u>KG</u>	300.000		
2	<u>PIPE CS 8" DIA SCH-40 (ERW)</u> CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List. 2) Manufacturer must be an API certificate holder for the last 5 years minimum. 08" dia Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>M</u>	50		
3	<u>PIPE CS 6" DIA SCH-40 (ERW)</u> 08" dia Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>M</u>	36		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

17	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
4	CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List. 2) Manufacturer must be an API certificate holder for the last 5 years minimum. 06" dia Sch 40 <u>PIPE CS 4" DIA SCH-40 (ERW)</u> CS Pipe, Beveled end, API 5L Gr. B PSL-1 (ERW/SAW/SMLS) as per ANSI B 36.10. Single Random length. Standard Compliance: 1) API 5 L Latest edition 2) All materials properties and parameters shall conform to minimum requirement of API 5L, PSL 1 Pipeline 3) All test shall be performed and results shall conform to minimum requirement of API 5 L PSL 1. 4) Documentation support i.e. MTC, ISO certificate, API certificate etc to be furnished / provided by contractor for PSO review / approval before shipment of material to requisite site. Certification: 1) Manufacturer must have a valid API 5L certificate with active status on the API composite List. 2) Manufacturer must be an API certificate holder for the last 5 years minimum.	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>M</u>	60		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

18	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
5	04" dia Sch 40 <u>GATE VALVE 8"dia</u> Gate Valves Specifications as mentioned in PSO-GV-01: 08" Dia	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	2		
6	<u>GATE VALVE 4"dia</u> Gate Valves Specifications as mentioned in PSO-GV-01: 04" Dia	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		
7	<u>ELBOW CS 8"dia 45deg (B.W)</u> Supply of Elbow 45 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 08" Dia Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	4		
8	<u>ELBOW CS 6"dia 45deg (B.W)</u> Supply of Elbow 45 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 06" Dia Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		
9	<u>ELBOW CS 4"dia 45deg (B.W)</u> Supply of Elbow 45 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9. 06" Dia Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

19	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	(Depot)					
	Supply of Elbow 45 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9.					
	04" Dia Sch 40					
10	<u>ELBOW CS 8"dia 90deg (B.W)</u>	<u>New Faisalabad (Depot)</u>	<u>EA</u>	14		
	Supply of Elbow 90 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9.					
	08" dia Sch 40					
11	<u>ELBOW CS 6"dia 90deg (B.W)</u>	<u>New Faisalabad (Depot)</u>	<u>EA</u>	2		
	Supply of Elbow 90 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9.					
	06" dia Sch 40					
12	<u>ELBOW CS 4"dia 90deg (B.W)</u>	<u>New Faisalabad (Depot)</u>	<u>EA</u>	4		
	Supply of Elbow 90 degree, Long Radius, B.W. ASTM A-234 Gr. WPB as per ASME B16.9.					
	04" dia Sch 40					
13	<u>FLANGE SORF MS 8"dia Class-150</u>	<u>New Faisalabad (Depot)</u>	<u>EA</u>	8		
	Supply of Slip-on Flanges 150#, R.F. as per ASME B16.5, ASTM A-105.					
	08" Dia					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

20	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
14	<u>FLANGE Sorf MS 6" dia Class-150.</u> Supply of Slip-on Flanges 150#, R.F. as per ASME B16.5, ASTM A-105. 06" Dia	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		
15	<u>FLANGE SORF MS 4"dia Class-150</u> Supply of Slip-on Flanges 150#, R.F. as per ASME B16.5, ASTM A-105. 04" Dia	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	4		
16	<u>FLANGE Blind MS 8"dia Class-150</u> Supply of Blind Flanges 150 # RF, as per ANSI B 16.5, ASTM A-105. 08" Dia	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	2		
17	<u>FLANGE Blind MS 6" dia Class-150 .</u> Supply of Blind Flanges 150 # RF, as per ANSI B 16.5, ASTM A-105. 06" Dia	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	5		
18	<u>FLANGE Blind MS 4"dia Class-150</u> Supply of Blind Flanges 150 # RF, as per ANSI B 16.5, ASTM A-105. 04" Dia	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

21	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
19	<u>Miscellaneous Steel structure</u> <u>New Faisalabad (Depot)</u> Supply of steel material, structure (Angles, C channel, H beam, etc.), Base Plate, Apurtenaces, railing, staircase, as per site requirement and inaccordance with relevant codes / standards/ best Engineering practises. Specifications: HR-235/A-36/SS400B,API 5L Gr. B/ ASTM A-53 GR.B ERW, ASTM A-234 Gr. WPB, ASME B16.5, ASTM A-105 or equivalent / superior as per PSO's approval, Suitable size as per site requirement. Note: Quantities for supply would be mutually decided by PSO and Contractor before proceeding with the procurement	<u>New Faisalabad (Depot)</u>	<u>KG</u>	2,000.000		
20	<u>Deformed Steel Bars</u> <u>New Faisalabad (Depot)</u> Deformed Steel Supply of deformed steel reinforcement bars. All wastage, cuttings, overlaps and chairs are included in the cost and no extra payment will be made in this regard. Only actual laid quantities will be considered for payment. Note: Mill test Certificate from the manufacturer will be provided by the contractor. Deformed steel of yield strength 60,000Psi. Destructive testing for steel to be carried out from reputed laboratory at cost of contractor Note : Only actual installed quantity will be paid. Wastage quantity will not be paid.	<u>New Faisalabad (Depot)</u>	<u>KG</u>	300.000		
21	<u>TEE EQUAL CS 8"dia (B.W)</u> <u>New Faisalabad (Depot)</u> Equal Tee Equal Tee B.W ASTM A - 234 Gr WPB as per ANSI 16.9 08" dia Sch 40	<u>New Faisalabad (Depot)</u>	<u>EA</u>	4		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

22	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
22	<u>TEE EQUAL CS 6"dia (B.W)</u> Equal Tee Equal Tee B.W ASTM A - 234 Gr WPB as per ANSI 16.9 06" dia Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	2		
23	<u>TEE EQUAL CS 4"dia (B.W)</u> Equal Tee Equal Tee B.W ASTM A - 234 Gr WPB as per ANSI 16.9 04" dia Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		
24	<u>TEE Reducing CS 8" X 4" sch-40</u> Reducing Tee Supply of Reducing Tee BW, ASTM A-234 Gr. WPB as per ANSI B 16.9 8"x 4" Sch 40	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		
25	<u>CAP Threaded 1"</u> Cap Threaded Cap, ASTM A-105, 3000 # as per ANSI B 16.11 1" Dia Sch 80	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	5		
26	<u>Pipe Nipple PBE 1"</u>	<u>New</u>	<u>EA</u>	5		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

23	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
		<u>Faisalabad</u> <u>(Depot)</u>				
	Pipe Nipple					
	Supply of CS Pipe Threaded nipple, API 5L Gr. B/ ASTM A-53 GR.B ERW as per ANSI B 36.10.					
	1" Sch-80 x 150 mm long					
27	<u>Sprinklers Brass 3/4" dia</u>	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	50		
	Water Sprinkler Nozzles					
	Specifications as mentioned in PSO-SN-028					
28	<u>REDUCER CS 8" X 6" (Concentric) Sch-40</u>	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	2		
	Reducer					
	Reducer CS 8"x 6" Sch 40					
29	<u>TEE Reducing CS 8" X 6"</u>	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	1		
	Reducing Tee					
	Supply of Reducing Tee BW, ASTM A-234 Gr. WPB as per ANSI B 16.9					
	8"x 6" Sch 40					
30	<u>Socket MS 1" dia</u>	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	5		
	Supply of Sockolet/Weldolet/Threadolet (as required), ASTM A 105, 3000#, as per					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

24	OF	24
RFQ No	CF-19824AS	
DATE	23.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017526

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Pipeline Works for Firefighting System on Product Tanks at PSO Faisalabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
31	ANSI B 16.11 The sizes below indicate outlet size (branch). Main line size may vary. Dia 1" <u>Socket MS 3/4" dia</u> Supply of Sockolet/Weldolet/Threadolet (as required), ASTM A 105, 3000#, as per ANSI B 16.11 The sizes below indicate outlet size (branch). Main line size may vary. Dia 3/4"	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	5		
32	<u>SOCKET 1/2" dia</u> Supply of Sockolet/Weldolet/Threadolet (as required), ASTM A 105, 3000#, as per ANSI B 16.11 The sizes below indicate outlet size (branch). Main line size may vary. Dia 1/2"	<u>New</u> <u>Faisalabad</u> <u>(Depot)</u>	<u>EA</u>	50		